

**EPA Superfund  
Record of Decision:**

**ROSS METALS INC.  
EPA ID: TND096070396  
OU 01  
ROSSVILLE, TN  
04/02/1999**

**ROSS METALS  
SUPERFUND SITE**

**RECORD OF DECISION**

**April 2,1999**



**U.S. Environmental Protection Agency  
Region 4**

## RECORD OF DECISION

### TABLE OF CONTENTS

---

<b>1.01</b>	<b>DECLARATION .....</b>	<b>Declaration - 1</b>
<b>2.0</b>	<b>DECISION SUMMARY .....</b>	<b>-1-</b>
2.1	SITE NAME, LOCATION, AND DESCRIPTION .....	-1-
2.2	SITE HISTORY AND ENFORCEMENT ACTIVITIES .....	-1-
2.3	HIGHLIGHTS OF COMMUNITY PARTICIPATION .....	-9-
2.4	SCOPE AND ROLE OF OPERABLE UNIT .....	-11-
2.5	SITE CHARACTERISTICS .....	-13-
2.5.1	Land Use .....	-13-
2.5.2	Climatology .....	-13-
2.5.3	Physiography. ....	-13-
2.5.4	Surface Water .....	-14-
2.5.5	Geology and Hydrogeology .....	-17-
2.5.6	Previous Investigations .....	-28-
2.5.7	Nature and Extent of Contamination .....	-30-
2.5.7.1	Soil and Sediment .....	-30-
2.5.7.2	Groundwater .....	-35-
2.5.7.3	Surface Water .....	-36-
2.5.7.4	Contaminant Fate And Transport .....	-38-
2.5.8	Treatability Studies .....	-43-
2.5.8.1	Dewatering Study, December 1997 .....	-43-
2.5.8.2	Stabilization Study, March 1998 .....	-45-
2.5.8.3	Biosolids Study, November 1998 .....	-46-
2.6	SUMMARY OF SITE RISKS .....	-46-

## RECORD OF DECISION

### TABLE OF CONTENTS

---

2.6.1	Human Health Risk Assessment Summary .....	-46-
2.6.1.1	Data Evaluation .....	-46-
2.6.1.2	Exposure Pathways .....	-48-
2.6.1.3	Toxicity Values .....	-53-
2.6.1.4	Risk Characterization .....	-56-
2.6.2	Ecological Risk Assessment Summary .....	-69-
2.6.2.1	Identification of Chemicals of Concern .....	-69-
2.6.2.2	Ecological Exposure Assessment .....	-72-
2.6.2.3	Ecological Effects Assessment .....	-78-
2.6.2.4	Conclusions .....	-90-
2.7	REMEDATION OBJECTIVES .....	-91-
2.7.1	Remedial Goals .....	-91-
2.7.2	Remedial Action Objectives .....	-93-
2.7.3	Extent of Source Material Contamination Above Remedial Goals .....	-95-
2.8	DESCRIPTION OF SOURCE MATERIAL ALTERNATIVES .....	-102-
2.8.1	Alternative S-1 -- No Action .....	-102-
2.8.1.1	Description .....	-102-
2.8.1.2	Overall Protection of Human Health and the Environment .....	-102-
2.8.1.3	Compliance with ARARs .....	-105-
2.8.1.4	Long-Term Effectiveness and Permanence .....	-105-
2.8.1.5	Reduction of M/T/V Through Treatment .....	-105-
2.8.1.6	Short-Term Effectiveness .....	-105-
2.8.1.7	Implementability .....	-105-
2.8.1.8	Cost .....	-106-

## RECORD OF DECISION

### TABLE OF CONTENTS

---

<b>2.8.2</b>	<b>Alternative S-2 -- Capping .....</b>	<b>-106-</b>
<b>2.8.2.1</b>	<b>Description .....</b>	<b>-106-</b>
<b>2.8.2.2</b>	<b>Overall Protection of Human Health and the Environment .....</b>	<b>-107-</b>
<b>2.8.2.3</b>	<b>Compliance with ARARs .....</b>	<b>-109-</b>
<b>2.8.2.4</b>	<b>Long-Term Effectiveness and Permanence .....</b>	<b>-111-</b>
<b>2.8.2.5</b>	<b>Reduction of M/T/V Through Treatment .....</b>	<b>-112-</b>
<b>2.8.2.6</b>	<b>Short-Term Effectiveness .....</b>	<b>-113-</b>
<b>2.8.2.7</b>	<b>Implementability .....</b>	<b>-113-</b>
<b>2.8.2.8</b>	<b>Cost .....</b>	<b>-114-</b>
<b>2.8.3</b>	<b>Alternative S-3 -- Capping With Pavement in Place .....</b>	<b>-114-</b>
<b>2.8.3.1</b>	<b>Description .....</b>	<b>-114-</b>
<b>2.8.3.2</b>	<b>Overall Protection of Human Health and the Environment .....</b>	<b>-115-</b>
<b>2.8.3.3</b>	<b>Compliance with ARARs .....</b>	<b>-117-</b>
<b>2.8.3.4</b>	<b>Long-Term Effectiveness and Permanence .....</b>	<b>-119-</b>
<b>2.8.3.5</b>	<b>Reduction of M/T/V Through Treatment .....</b>	<b>-120-</b>
<b>2.8.3.6</b>	<b>Short-Term Effectiveness .....</b>	<b>-121-</b>
<b>2.8.3.7</b>	<b>Implementability .....</b>	<b>-121-</b>
<b>2.8.3.8</b>	<b>Cost .....</b>	<b>-122-</b>
<b>2.8.4</b>	<b>Alternative S-4 -- Capping With Construction of Above-Ground Disposal Cell .....</b>	<b>-122-</b>
<b>2.8.4.1</b>	<b>Description .....</b>	<b>-122-</b>
<b>2.8.4.2</b>	<b>Overall Protection of Human Health and the Environment .....</b>	<b>-123-</b>

## RECORD OF DECISION

### TABLE OF CONTENTS

---

2.8.4.3	Compliance with ARARs .....	-125-
2.8.4.4	Long-Term Effectiveness and Permanence .....	-127-
2.8.4.5	Reduction of M/T/V Through Treatment .....	-128-
2.8.4.6	Short-Term Effectiveness .....	-129-
2.8.4.7	Implementability .....	-129-
2.8.4.8	Cost .....	-130-
2.8.5A	Alternative S-5 -- Excavation And Onsite Treatment With Solidification/Stabilization	
	Option A - Onsite Disposal of Treated Waste .....	-130-
2.8.5A.1	Description .....	-130-
2.8.5A.2	Overall Protection of Human Health and the Environment .....	-132-
2.8.5A.3	Compliance with ARARs .....	-134-
2.8.5A.4	Long-Term Effectiveness and Permanence .....	-136-
2.8.5A.5	Reduction of M/T/V Through Treatment .....	-137-
2.8.5A.6	Short-Term Effectiveness .....	-138-
2.8.5A.7	Implementability .....	-138-
2.8.5A.8	Cost .....	-139-
2.8.5B	Alternative S-5 -- Excavation And Onsite Treatment With Solidification/Stabilization	
	Option B - Offsite Disposal of Treated Material .....	-140-
2.8.5B.1	Description .....	-140-
2.8.5B.2	Overall Protection of Human Health and the Environment .....	-141-
2.8.5B.3	Compliance with ARARs .....	-142-

## RECORD OF DECISION

### TABLE OF CONTENTS

---

2.8.5B.4	Long-Term Effectiveness and Permanence . . . . .	-142-
2.8.5B.5	Reduction of M/T/V Through Treatment . . . . .	-142-
2.8.5B.6	Short-Term Effectiveness . . . . .	-143-
2.8.5B.7	Implementability . . . . .	-144-
2.8.5B.8	Cost . . . . .	-144-
2.8.6A	Alternative S-6 -- Capping w/ Excavation & Onsite Treatment of Principal Threat Waste	
	Option A - Onsite Disposal of Treated Principal Threat Waste	-145-
2.8.6A.1	Description . . . . .	-145-
2.8.6A.2	Overall Protection of Human Health and the Environment . . . . .	-147-
2.8.6A.3	Compliance with ARARs . . . . .	-149-
2.8.6A.4	Long-Term Effectiveness and Permanence . . . . .	-151-
2.8.6A.5	Reduction of M/T/V Through Treatment . . . . .	-152-
2.8.6A.6	Short-Term Effectiveness . . . . .	-152-
2.8.6A.7	Implementability . . . . .	-153-
2.8.6A.8	Cost . . . . .	-154-
2.8.6B	Alternative S-6 -- Capping w/ Excavation & Onsite Treatment of Principal Threat Waste	
	Option B - Offsite Disposal of Treated Principal-Threat Waste	-154-
2.8.6B.1	Description . . . . .	-154-
2.8.6B.2	Overall Protection of Human Health and the Environment . . . . .	-157-
2.8.6B.3	Compliance with ARARs . . . . .	-159-
2.8.6B.4	Long-Tenn Effectiveness and Permanence . . . . .	-161-

## RECORD OF DECISION

### TABLE OF CONTENTS

---

	2.8.6B.5	Reduction of M/T/V Through Treatment .....	-161-
	2.8.6B.6	Short-Term Effectiveness .....	-162-
	2.8.6B.7	Implementability .....	-162-
	2.8.6B.8	Cost .....	-163-
2.9	WETLAND SEDIMENT ALTERNATIVE ANALYSIS .....		-163-
2.9.1	Alternative W-1 -- No Action .....		-164-
	2.9.1.1	Description .....	164-
	2.9.1.2	Overall Protection of Human Health and the Environment .....	-164-
	2.9.1.3	Compliance with ARARs .....	-164-
	2.9.1.4	Long-Term Effectiveness and Permanence .....	-166-
	2.9.1.5	Reduction of M/T/V Through Treatment .....	-166-
	2.9.1.6	Short-Term Effectiveness .....	-166-
	2.9.1.7	Implementability .....	-166-
	2.9.1.8	Cost .....	-166-
2.9.2	Alternative W-2 — Capping with Clean Fill and Off-Site Creation of Wetlands .....		-167-
	2.9.2.1	Description .....	-167-
	2.9.2.2	Overall Protection of Human Health and the Environment .....	-167-
	2.9.2.3	Compliance with ARARs .....	-168-
	2.9.2.4	Long-Term Effectiveness and Permanence .....	-170-
	2.9.2.5	Reduction of M/T/V Through Treatment .....	-170-
	2.9.2.6	Short-Term Effectiveness .....	-171-
	2.9.2.7	Implementability .....	-171-



## RECORD OF DECISION

### TABLE OF CONTENTS

---

2.9.2.8	Cost .....	-172-
2.9.3	Alternative W-3 --Excavation & Revegetation/Restoration of Wetlands Option A - Regrading With Clean Fill .....	-172-
2.9.3A.1	Description .....	-172-
2.9.3A.2	Overall Protection of Human Health and the Environment .....	-173-
2.9.3A.3	Compliance with ARARs .....	-174-
2.9.3A.4	Long-Term Effectiveness and Permanence .....	-175-
2.9.3A.5	Reduction of M/T/V Through Treatment .....	-175-
2.9.3A.6	Short-Term Effectiveness .....	-175-
2.9.3A.7	Implementability .....	-176-
2.9.3A.8	Cost .....	-176-
2.9.3B	Alternative W-3 – Excavation& Revegetation/Restoration of Wetlands Option B -- Regrading with Biosolid Compost Material .....	-176-
2.9.3B.1	Description .....	-176-
2.9.3B.2	Overall Protection of Human Health and the Environment .....	-178-
2.9.3B.3	Compliance with ARARs .....	-178-
2.9.3B.4	Long-Term Effectiveness and Permanence .....	-179-
2.9.3B.5	Reduction of M/T/V Through Treatment .....	-179-
2.9.3B.6	Short-Term Effectiveness .....	-180-
2.9.3B.7	Implementability .....	-181-
2.9.3B.8	Cost .....	-181-
2.10	COMPARATIVE ANALYSIS OF ALTERNATIVES .....	-181-
2.11	SELECTED REMEDY .....	-185-

## **RECORD OF DECISION**

### **TABLE OF CONTENTS**

---

<b>2.12</b>	<b>STATUTORY DETERMINATIONS</b>	<b>-193-</b>
<b>2.12.1</b>	<b>Overall Protection of Human Health and the Environment</b>	<b>-193-</b>
<b>2.12.2</b>	<b>Compliance with Applicable or Relevant and Appropriate Requirements (ARARs)</b>	<b>-194-</b>
<b>2.12.3</b>	<b>Cost-Effectiveness</b>	<b>-196-</b>
<b>2.12.4</b>	<b>Utilization of Permanent Solutions and Alternative Treatment (or Resource Recovery) Technologies to the Maximum Extent Practicable</b>	<b>-197-</b>
<b>2.12.5</b>	<b>Preference for Treatment as a Principal Element</b>	<b>-197-</b>
<b>2.12.6</b>	<b>Five-Year Requirements</b>	<b>-199-</b>
<b>3.0</b>	<b>RESPONSIVENESS SUMMARY</b>	<b>-199-</b>
<b>3.1</b>	<b>RESPONSIVENESS SUMMARY OVERVIEW</b>	<b>-199-</b>
<b>3.2</b>	<b>SUMMARY OF MAJOR QUESTIONS AND COMMENTS RECEIVED BY THE ROSSVILLE COMMUNITY</b>	<b>-200-</b>
<b>3.3</b>	<b>SUMMARY OF THE MAJOR QUESTIONS AND COMMENTS RECEIVED BY THE "GROUP"</b>	<b>-200-</b>
 <b>APPENDIX A PROPOSED PLAN</b>		
 <b>APPENDIX B LETTERS OF CONCURRENCE</b>		
 <b>APPENDIX C TRANSCRIPT OF NOVEMBER 30,1998 PUBLIC MEETING</b>		

## RECORD OF DECISION

### TABLE OF CONTENTS

---

Figure 2-1	Site Location Map . . . . .	-2-
Figure 2-2	Site Layout . . . . .	-3-
Figure 2-3	100 Year Flood Plain Map . . . . .	-15-
Figure 2-4	Wetlands Delineation . . . . .	-16-
Figure 2-5	Regional Cross-Section . . . . .	-18-
Figure 2-6	Cross-Section Locations . . . . .	-21-
Figure 2-7	Cross Section A-A' and B-B' . . . . .	-22-
Figure 2-8	Cross Section Locations - 1997 Borings . . . . .	-23-
Figure 2-9	Cross Section A-A', 1997 Borings . . . . .	-24-
Figure 2-10	Cross Section B-B', 1997 Borings . . . . .	-25-
Figure 2-11	Potentiometric Surface Map - October 1, 1990 . . . . .	-26-
Figure 2-12	Potentiometric Surface Map - November 1996 . . . . .	-27-
Figure 2-13	Extent of Lead in Surface Soils . . . . .	-31-
Figure 2-14	Maximum Lead Results in Sediment (TAL Analysis - Ecological Investigation) . . . . .	-32-
Figure 2-15	Contaminant Contour in Wetlands - March 1998 . . . . .	-33-
Figure 2-16	Extent of Lead in Subsurface Soils . . . . .	-34-
Figure 2-17	Total Lead Concentrations - Water . . . . .	-37-
Figure 2-18	Lead Results in Surface Water (TAL Analysis - Ecological Investigation) . . .	-39-
Figure 2-19	Fate and Transport . . . . .	-40-
Figure 2-20	Conceptual Site Model . . . . .	-49-
Figure 2-21	Site and Reference Area Location Map . . . . .	-83-
Figure 2-22	Cleanup Goals v. Excavation Required . . . . .	-98-
Figure 2-23	Contaminant Contour in Wetlands . . . . .	-99-
Figure 2-24	Alternative S-2    Capping . . . . .	-108-
Figure 2-25	Alternative S-3    Capping with Pavement in Place . . . . .	-116-

## RECORD OF DECISION

### TABLE OF CONTENTS

---

Figure 2-26	Alternative S-4	Capping with Construction of Above-Ground Cell . . . . .	-124-
Figure 2-27	Alternative S-5A	Treatment and On-Site Disposal . . . . .	-133-
Figure 2-28	Alternative S-6A	Treatment w/On-Site Disposal of Treated Principal Threat Waste . . . . .	-148-
Figure 2-29	Alternative S-6B	Treatment w/Off-Site Disposal of Treated Principal Threat Waste . . . . .	-158-
Figure 2-30	Excavation Contours	. . . . .	-189-

## RECORD OF DECISION

### TABLE OF CONTENTS

---

Table 2-1	Non-Hazardous Waste Removed Offsite . . . . .	-7-
Table 2-2	Hazardous Waste Removed Offsite . . . . .	-8-
Table 2-3	Summary of Chemicals of Concern . . . . .	-51-
Table 2-4	Cancer Slope Factor . . . . .	-54-
Table 2-5	Reference Dose . . . . .	-55-
Table 2-6	Process Area: Future Risk Summary . . . . .	-59-
Table 2-7	Process Area: Future Use Risk Summary (w/o Groundwater Pathway) . . . . .	-60-
Table 2-8	Process Area: Exposure to Lead . . . . .	-62-
Table 2-9	Process Area: Exposure to Lead (w/o Groundwater Pathway) . . . . .	-63-
Table 2- 10	Landfill: Future Risk Summary . . . . .	-64-
Table 2-11	Landfill: Future Risk Summary (w/o Groundwater Pathway) . . . . .	-65-
Table 2-12	Landfill: Exposure to Lead . . . . .	-67-
Table 2-13	Landfill: Exposure to Lead (w/o Groundwater Pathway) . . . . .	-68-
Table 2-14	COCs Distribution and Hazard Quotient Calculations . . . . .	-71-
Table 2-15	Ecological Exposure Pathways of Concern . . . . .	-79-
Table 2-16	COC Concentrations Expected to Provide Adequate Protection of Ecological Receptors . . . . .	-92-
Table 2-17	Remedial Goals . . . . .	-94-
Table 2-18	Summary of Soil Alternatives Evaluation . . . . .	-103-
Table 2-19	Summary of Wetland Sediment Alternatives Evaluation . . . . .	-165-
Table 2-20	Comparative Analysis of Soil Alternatives . . . . .	-182-
Table 2-21	Comparative Analysis of Wetland Sediment Alternatives . . . . .	-183-
Table 2-22	Excavation Standards . . . . .	-188-
Table 2-23	Capital Costs for Selected Remedy . . . . .	-191-
Table 2-24	Operation and Maintenance Costs for Selected Remedy . . . . .	-192-

## **1.0 DECLARATION**

### **SITE NAME AND LOCATION**

Ross Metals, Operable Unit #1  
100 North Railroad Street  
Rossville, Fayette County, Tennessee

### **STATEMENT OF BASIS AND PURPOSE**

This decision document presents the selected remedial action for the Ross Metals Site, Operable Unit # 1, in Rossville, Fayette County, Tennessee. This action is chosen in accordance with CERCLA, as amended by SARA, and, to the extent practicable, the National Contingency Plan. This decision is based on the Administrative Record for this Site.

The State of Tennessee concurs with the Selected Remedy.

### **ASSESSMENT OF THE SITE**

Actual or threatened releases of hazardous substances from this Site, if not addressed by implementing the response action selected in this ROD, may present an imminent and substantial endangerment to public health, welfare, or the environment.

### **DESCRIPTION OF THE REMEDY**

This operable unit is the first action of at least two operable units that are planned for the Site.

This operable unit remedy addresses source materials (soil, sediment, waste, pavement, and debris) through treatment and off-Site disposal of principal and low-level threat wastes.

The major components of the remedy include:

- Decontamination, demolition, and off-Site disposal of pavement and buildings with recycling of metal debris;
- Excavation of contaminated soil, landfilled slag, and contaminated sediment with appropriate confirmation sampling;
- Backfill of excavated subsurface-soil areas and landfill with clean soil;
- Stabilization/solidification/fixation of contaminated soil, stockpiled slag, landfilled slag, and wetlands sediment;

- Off-Site disposal of soils, slag and sediment at a RCRA-nonhazardous waste disposal facility;
- Application of a layer of biosolids over the Site. Grass seeding of the facility and landfill areas; and revegetation of the Site wetlands according to the wetlands revegetation plan developed by EPA, 1998.
- Development of a maintenance and monitoring plan to assess the effectiveness of the cleanup action.

### **STATUTORY DETERMINATIONS**

The Selected Remedy is protective of human health and the environment, complies with Federal and State requirements that are legally applicable or relevant and appropriate to the remedial action, and is cost-effective. This remedy utilizes permanent solutions and alternative treatment technologies, to the maximum extent practicable for the Site. This Remedy satisfies the statutory preference for treatment as a principal element.

Because this Remedy will not result in hazardous substances remaining on-Site above health-based levels that allow for unlimited use and unrestricted exposure, a five-year review will not be required for this remedial action.


### **ROD DATA CERTIFICATION CHECKLIST**

The following information is included in the *Decision Summary* section of this Record of Decision. Additional information can be found in the Administrative Record file for this Site.

- Chemicals of Concern (COCs) and their respective concentrations;
- Baseline risk represented by the COCs;
- Cleanup levels established for COCs and the basis for the levels;
- Current and future land and ground-water use assumptions used in the baseline risk assessment and ROD;
- Land use that will be available at the Site as a result of the Selected Remedy;
- Estimated capital, operation and maintenance O&M), and total present worth costs; discount rate; and the number of years over which the Remedy cost estimates are projected; and Decisive factors that led to selecting the Remedy (i.e., description of how the Selected Remedy provides the best balance of tradeoffs with respect to the balancing and modifying criteria).

2 APR 99

Date



Richard D. Green, Director  
Waste Management Division

## **2.0 DECISION SUMMARY**


### **2.1 SITE NAME, LOCATION, AND DESCRIPTION**


The RM facility is located at 100 North Railroad Street in Rossville, Fayette County, Tennessee, (see **Figure 2-1**). The facility's geographic coordinates are 35 E02'57" North latitude and 89 E32'55 " West longitude, as shown on the U.S. Geological Survey (USGS) topographic map quadrangle for Rossville, Tennessee (U.S. Geological Survey [USGS] 1965). The Site includes contaminated wetlands to the north and northeast of the process area and the landfill. It is bordered by residential property to the east, the Southern Railroad tracks to the south, and a municipal wastewater treatment plant to the west. A Site layout is presented in **Figure 2-2**.

### **2.2 SITE HISTORY AND ENFORCEMENT ACTIVITIES**

From 1978 until June 20, 1992, RM operated a secondary lead smelter at the Site. Prior to 1978, the property was undeveloped. RM produced specification alloyed lead that was sold for use in manufacturing vehicle batteries, lead shot pellets, and sheet lead (radiation shields) (Ogden Environmental Energy Services Company [Ogden] 1994). The facility received spent lead acid batteries, spent lead plates, lead oxide, scrap metal, and other lead waste and material from various businesses and industries, including battery crackers and battery manufacturers. The primary material used for the recycling process was spent lead acid batteries, with automotive and industrial batteries accounting for 80 percent of the raw material processed. The remaining 20 percent consisted of other lead-bearing materials, such as recycled dross, dust slag, and factory scrap. Facility operations included not only the smelting of lead and other scrap metals but a variety of other products, such as crushed drums, limestone, steel, and cast iron. These materials were added to the blast furnace as flux to create a reducing atmosphere. Wastes generated from the process included slag, plastic chips, waste acid, lead emission control dusts, and lead-contaminated stormwater (Black & Veach Waste Science, Inc. [B&V] 1996).







ACAD FILE: ROSSV102

Ross Metals Site  
Rossville, Tennessee

CDM Federal Programs Corporation  
A subsidiary of Corp Dresser & McKee Inc.

Site Layout

Figure No.

2-2

7/98

Upon receipt, batteries were stored on pallets located east and southeast of the facility; each pallet held about 50 batteries. The batteries were then conveyed to the wrecker building for the battery breaking operation. Wastewater used for battery breaking operations conducted inside the wrecker building was managed by an on-Site wastewater treatment system. Water was used to separate lead from other battery components based on its density. After separation, lead was transported to the blast furnace slag area, where lead materials were passed through a smelter. According to facility representatives, 99 to 99.5 percent of the lead content was recovered. The molten lead product was then moved to the refinery area. The refinery area consisted of four kettles that received molten lead and formed ingots. The ingots were then moved to the finished storage area until they were shipped to customers (B&V 1996).

Acid and sludge obtained during the battery breaking operation contained residual amounts of lead and lead acid; the acid and sludge were transferred to the wastewater treatment unit to reclaim the remaining lead. Lead was reclaimed by allowing it to settle further in aboveground collection tanks. This lead sludge, collected prior to neutralization, was transferred to the blast furnace area and immediately fed into the furnace. The remaining acid was neutralized with liquid caustic soda. Upon neutralization, the solution was held for additional settling to precipitate dissolved metals. Sludge resulting from the neutralization process was also collected in settling tanks and recycled into the blast furnace with other lead scrap. The pH of the waste stream generated by the facility was further adjusted, and sludge-free effluent was discharged to the Rossville Municipal Sewage Treatment Facility (Tibbels 1983).

Several areas of the operating facility contained large volumes of lead-bearing materials. With the exception of the container storage area, the lead-bearing materials were not containerized; instead, they were placed on the asphalt foundation of the facility or directly on facility soils.

From 1979 until December 1988, blast slag that had accumulated as a part of the smelting process

was disposed of in an on-Site landfill. On November 3, 1986, RM submitted a petition for registration for an existing industrial landfill used to dispose of blast furnace slag; RM considered the slag a nonhazardous industrial waste. On November 8, 1988, RM submitted a RCRA Part B application stating that slag had been deposited on Site. Diagrams included in the application show slag piles both inside and outside of the area designated as the landfill. EPA's RCRA Compliance Section conducted a sampling investigation on December 7, 1988, to determine if the waste generated at the facility should be regulated. On December 20, 1988, the Tennessee Department of Health and Environment (TDHE) suspended all further processing of the request until results from the EPA sampling event could be assessed and the EPA could determine whether the blast slag was a nonhazardous waste (B&V 1996). Several references in the EPA files for the RM Site debate the status of blast slag as a hazardous waste. File material also indicates that on April 20, 1990, RM applied for a solid waste classification variance for the blast slag. RCRA also conducted a sampling investigation on May 9, 1990, to determine if smelting and landfiling activities at the facility were causing adverse environmental impacts. The variance was denied on June 6, 1990, because EPA determined that blast slag was a hazardous waste and subject to the full extent of RCRA regulations.

In September of 1990, RCRA issued a Complaint and Compliance Order against Ross Metals. After several months of extensive negotiations, the parties reached an agreement to settle the case. However, the company never signed the Consent Agreement, because of its precarious financial condition. In 1992, Ross Metals, Inc. received an Administrative Dissolution under Articles of Incorporation. There is no known successor entity. Because of this, all State and Federal RCRA enforcement actions at the Site ceased.

Once negotiations failed with Ross Metals and all operations ceased at the facility, the Site was referred to EPA's ERRB. In a letter dated October 25, 1993, ERRB notified TDEC that the Site was eligible for a removal action. Prior to any ERRB clean-up activities, TDEC was approached by an interested third party, Greyhound Finance Services (GFS), regarding the possible clean-up of the Site.

EPA and TDEC decided a State Lead RCRA Closure performed by GFS would be beneficial to all parties. An agreement concerning the RCRA Closure was never reached, therefore the Site was referred back to ERRB in June of 1994.

On June 15, 1994, ERRB conducted a Site visit. Based upon ERRB's file review and Site visit, the Ross Metals Site met the criteria for a high priority removal action. The removal action began in September 1994 and was completed in June 1995. The removal consisted of segregating, staging, or removing forty-six wastestreams. The wastestreams, descriptions, and approximate volumes of each is listed in the **Tables 2-1 and 2-2**.

Approximately 6,000 cubic yards (CY) of lead bearing blast slag was staged in on-Site buildings. The removal action was completed in August 1995. During the removal action, EPA was also conducting a Site investigation for the NPL listing process. In October 1996, the North Site Management Branch began remedial investigations. The Site was listed on the final National Priorities List March 31, 1997.

An Engineering Evaluation/Cost Analysis (EE/CA) was finalized in February 1998. In considering the information presented in the EE/CA and the statutory limits which apply to non-time critical removal actions, EPA determined that a Remedial Investigation/Feasibility Study Report that develops appropriate remedial action alternatives was needed for this Site.

On March 24<sup>th</sup>, 1998, EPA sent general notice letters to the Potentially Responsible Parties (PRPs).

The threat of human exposure and reports of trespassing caused EPA to perform a removal action in June and September of 1998. About 10,000 CY of slag are landfilled in an unlined and unsecured area located just north of the facility process area. About 6,000 CY of stockpiled lead slag material are still stored at the facility inside deteriorating sheet metal buildings. The buildings are no longer

<b>Table 2-1</b> <b>Non-Hazardous Waste Removed Offsite</b>			
<b>Quantity Removed</b>	<b>Dates Removed</b>	<b>Type of Waste Removed</b>	<b>Type of Disposal Facility</b>
Not Applicable	9/26 - 10/10/94	battery cracking equipment; ingot casting conveyor, baghouse blower, 17 colling crucibles, battery saw, conveyor belt, tumbler and associated framework.	Reclamation Facility
230 cubic yards	10/3 - 12/20/94	construction-type debris	Landfill
2 each	10/21/94	baghouses	Reclamation Facility
371 gallons	10/25/94	diesel fuel	Reclamation Facility
Not Applicable	10/31/94	baghouse equipment: baghouse frame and associated ductwork, screen	Reclamation Facility
850 cubic yards	11/05 - 11/18/94	conveyor, cross members, catwalk and ladder, scrap metal	Reclamation Facility
88 containers	11/11/94	laboratory chemicals	Facility Local
20 cubic yards	11/30/94	old tires	High School Local
17 cubic yards	12/12/94	soda ash	Landfill Recycling Facility

<b>Table 2-2</b> <b>Hazardous Waste Removed Offsite</b>			
<b>Quantity Removed</b>	<b>Dates Removed</b>	<b>Type of Waste Removed</b>	<b>Type of Disposal Facility</b>
250 cubic yards	11/14 - 11/15/94	battery chips/leaded debris	Regional TSDF
34,430 lbs	12/02 - 12/12/94	leaded tank sludges ((D008, D006)	Local TSDF
288 cubic yards	12/08 - 12/19/94	leaded debris; debris, soil, floor dust, rags, PPE, cinderblocks (D008)	Regional TSDF
307,220 lbs	12/12 - 12/21/94	raw materials (K069,D008)	Reclamation Facility
330 gallons	12/16/94	base-neutral liquid	Local TSDF
330 gallons	12/16/94	motor oil	Local TSDF
90 gallons	12/16/94	hydrochloric acid	Local TSDF
110 gallons	12/16/94	sodium hydroxide	Local TSDF
3500 gallons	12/16/94	sodium hydroxide	Local TSDF

providing protection from weather conditions because of deterioration. Data collected in the investigation revealed lead-contaminated surface soils (outside the fenced facility - approximately 8.58 acres). This area is adjacent to residential property and is located within a designated wetland. The removal action consisted of placing tarpaulins over the 6,000 CY of stockpiled lead slag and installing security fencing around the contaminated surface soils and landfill.

The Remedial Investigation/Feasibility Study was finalized in November 1998

## **2.3 HIGHLIGHTS OF COMMUNITY PARTICIPATION**

Local officials have said that area residents have been fairly quiet about the presence of an NPL Site in the community. A Fayette County Health Department representative said they have received very few questions regarding health concerns.

A Fact Sheet was issued January 1997, prior to a Public Availability Session, which was conducted by EPA and the Tennessee Department of Environment and Conservation. The Availability Session was conducted January 6, 1997. No citizens attended.

A fact sheet was released immediately after the Site was placed on the NPL. The Site was placed on the NPL on March 31, 1997.

The Agency for Toxic Substances and Disease Registry (ATSDR), after reviewing the available environmental data suggested that people were possibly exposed to metals in on-Site and off-Site surface soils and water. Therefore, ATSDR decided to conduct an Exposure Investigation (EI) to determine the lead level present in the soil of the adjacent residences and offered blood-lead level testing to the residents adjacent to the Site. The EI also included soil and dust testing for lead in residential areas. The EI conducted was to investigate a possible public health problem and develop



plans for its control.

Following the issuance of notices to Potentially Responsible Parties (PRPs), EPA held an informational public meeting on April 14, 1998. During that meeting, citizens were encouraged to form a Community Advisory Group (CAG).

ATSDR held a community meeting with residents of Railroad Street to explain the purpose of the EI on April 21, 1998. Prior to the community meeting, ATSDR distributed flyers throughout the community and coordinated media outreach with local newspapers in the area. In conjunction with the Tennessee Department of Environment and Conservation, ATSDR collected blood, soil and wipe samples from identified residents on May 30, 1998.

The Rossville CAG, composed of approximately 10 citizens, met for the first time in May 1998. The CAG meets the first Tuesday of each month, as needed. Their mission statement is "The Rossville Community Advisory Group exists to insure that the cleanup of the Ross Metals Superfund Site protects human health and the environment."

A Proposed Plan Fact Sheet was released to the public which described EPA's preferred remedial alternative and invited public comments about the alternatives. The Administrative Record file was made available November 18, 1998. The file can be found at the information repository maintained at the EPA Docket Room in Region 4 and Rossville City Hall. The Notice of Availability of these two documents was published in the *Commercial Appeal* on November 18, 1998. A public comment period was held from November 18, 1998 to December 18, 1998. An extension to the public comment period was requested. As a result, it was extended to January 19, 1998. In addition, a public meeting was held on November 30, 1998 to present the Proposed Plan to a broader community audiences than those that had already been involved at the Site. At this meeting, the Tennessee Department of Environment and Conservation answered questions about problems at the Site and the

remedial alternatives. EPA also used this meeting to solicit a wider cross-section of community input on the reasonably anticipated future land use. Public comments were received during this period. A transcript of the public meeting is included in the Responsiveness Summary, which is part of this ROD.

This decision document presents the selected remedial action for the Ross Metals OU#1 in Fayette County Tennessee. The remedial action chosen, is in accordance with CERCLA, as amended by SARA, and, to the extent practicable, the National Contingency Plan. The decision for this Site is based on the Administrative Record.

## **2.4 SCOPE AND ROLE OF OPERABLE UNIT**

As with many Superfund sites, the problems at the Ross Metals OU #1 are complex. As a result, EPA organized the work into two operable units (OUs). These are:

- OU #1: Contamination in the source materials.
- OU #2: Contamination in the aquifer.

The scope of this response action is to cleanup contaminated soil, wetlands, buildings and waste. Incidental ingestion of soil and the physical hazards pose the major risks to human health. Sediment poses an acute risk to ecological receptors. The cleanup of the source materials is proposed to prevent exposure to contaminated source materials and prevent contamination of groundwater and surface water. This response action is the first of two operable units that will be used to address the contamination of the entire Site.

Operable Unit #1 will address:

- Waste Slag (landfilled and stockpiled)
- Contaminated soil (in facility area and landfill area)
- Buildings
- Demolition debris (pavement)
- Contaminated sediment (in wetlands)

EPA generally expects to use treatment to address principal threats posed by a site, wherever practicable. Principal threat wastes are those source materials considered highly toxic or mobile that cannot be reliably contained or would present a significant risk to human health or the environment should exposure occur. For the Ross Metals Site, principal threat wastes conservatively include approximately:

- 600 cubic yards of soil
- 8,200 cubic yards of sediment
- 6,000 cubic yards of stockpiled slag
- 10,000 cubic yards of landfilled slag

Operable Unit #2 will require additional Site characterization studies in order to determine the nature and extent of potential groundwater contamination. A Feasibility Study may be required to identify and evaluate possible groundwater remedial actions.

## **2.5 SITE CHARACTERISTICS**

### **2.5.1 Land Use**

The area surrounding the Site is primarily rural or residential. A municipal wastewater treatment plant is located adjacent to the western Site boundary, and no other known industries would have contributed contamination to the Site. The towns of Rossville, Rossville Junction, and New Bethel are located within a 4-mile radius of the Site; the total population within the 4-mile radius is 1,947. The nearest school is located 0.3 miles southeast of the Site.

Current and reasonably anticipated future land uses and current and potential beneficial ground-water uses are discussed in Sections 2.6.1.2 and 2.6.1.5.

### **2.5.2 Climatology**

The RM Site is located in southwest Tennessee, about 30 miles west of Memphis. This area has an average annual daily temperature of about 62.3 E F. The normal daily minimum and maximum temperatures are 52.4 EF and 72.1 EF, respectively. Annual precipitation is 52.10 inches. (Source: National Weather Service Historic Data for Memphis, 1961-1990).

### **2.5.3 Physiography**

The RM Site is located in the Gulf Coast Plain Physiographic Province of western Tennessee, which is characterized by unconsolidated near-surface sands, silts, and clays. Elevations within the surrounding area vary from 290 to 470 feet National Geodetic Vertical Datum (NGVD) (USGS 1965). Ground elevations within the Site boundaries range from about 315 NGVD near the main office building to about 310 NGVD at the northeast corner of the fenced portion of the Site. The RM

Site is located about 0.5 miles south of the Wolf River.

The RM Site consists of an old fenced facility area enclosing about 5.5 acres and a blast slag landfill covering about 2.5 acres north of the old fenced area, and contaminated wetlands located north and east of the facility and landfill areas, approximately 8.58 acres. The fenced area includes several buildings, most of which are constructed of sheet metal. Most of the area inside the fenced facility area is paved with either concrete or asphalt, and an asphalt curb is located just inside the fence. The curb was apparently constructed to divert storm water runoff to the storm water collection sump in the northeast corner of the property. Several stockpiles of waste slag are located in various buildings, including the wrecker building, the slag fixation container, the furnace raw materials refinery building, and the shipment building. The buildings are generally in poor condition, and some are in danger of collapsing.


The landfill area was constructed in a wetland area north of the fenced area. Several soil-covered mounds ranging up to 6 feet high are located in the landfill area. An 8-inch-thick concrete slab is located just north of the gate in the landfill area; however, evidence suggests that some slag may be buried beneath the concrete slab. An estimated 10,000 CY of slag is buried throughout the landfill at thicknesses of up to about 4 feet. About 1 to 2 feet of fill material has been placed over the slag throughout the landfill.

As indicated on **Figure 2-3**, the RM facility and the wetlands north and east of the facility are located in a 100-year floodplain. **Figure 2-4** illustrates the type of wetlands that are part of the RM Site.


#### **2.5.4 Surface Water**

Storm water runoff from the entire facility drains into a basin located at the northeastern corner of the fenced facility. The basin discharged to a small wetland area located north and northeast of the

APPROXIMATE LOCATION  
ROSS METALS, INC.



Legend:

 100 Year Flood

NOTES:

1. Flooding effects from Wolf River
2. Flood information taken from Flood Insurance Rate Map for the town of Rossville, Fayette County, Tennessee.



Scale  
0' 250' 500'

Ross Metals Site  
Rossville, TN

**CDM** Federal Programs Corporation  
A subsidiary of Camp Dresser & McKee Inc.


100 Year Flood  
Plain Map

Figure No.

2-3

10/98

COREL ROSSI



Ross Metals Site Rossville, Tennessee CDM Federal Programs Corporation 1000 Ross Road SE	Wetlands Delineation	Figure No 2-4 5/98
---	----------------------	--------------------------

facility area. During an inspection on October 14, 1993, the holding dike of the storm water basin was observed to be overflowing, and storm water was apparently not being collected in on-Site storage tanks for wastewater treatment. Runoff from the landfill also drained to the wetland located north and northeast of the landfill; in addition, the landfill has no documented run-on, run-off, or collection facilities. The landfill is documented to lie adjacent to a wetland area; however, the wetlands are not delineated on the National Wetland Inventory (NWI) map.

The wetlands and wooded area extend to the north and ultimately drain to the Wolf River, which is the main drainage body for the region. The Wolf River flows west, through Memphis, and into the Mississippi River.


The Rossville municipal wastewater treatment plant is located west of the RM Site. The outfall for the treatment plant is located on the Wolf River at the Highway 194 bridge, about 1.5 miles upstream of the facility. The outfall and the treatment plant are not expected to have any adverse effect on the wetland located north and northeast of the Site.

### **2.5.5 Geology and Hydrogeology**

The Site is located in the Gulf Coast Plain Physiographic Province of Western Tennessee, which is characterized by unconsolidated near-surface sands, silts, and clays. Included in this sequence of unconsolidated sediments is the Memphis Sand, which contains an important water-bearing zone known as the Memphis aquifer. The Memphis Sand consists of a thick body of sand that contains clay and silt lenses or beds at various horizons. The sand ranges from very fine to very coarse (B&V 1996). A regional cross-section is provided as **Figure 2-5**.

Recharge of the Memphis aquifer generally occurs along the outcrop of the Memphis Sand. Recharge results from precipitation and from downward infiltration of water from the overlying fluvial deposits





and alluvium, where present. In the outcrop-recharge belt, the Memphis aquifer is under water-table conditions (unconfined), and the configuration of the potentiometric surface is complex and generally conforms to the topography. West of the outcrop-recharge belt, the aquifer is confined by other members of the Claiborne Group containing clay, silt, sand, and lignite. Groundwater in the unconfined portion of the Memphis aquifer typically flows to the west. Transmissivities of the Memphis aquifer in the Memphis area range from about 20,000 to 42,800 square feet per day. However, USGS literature referenced only, one test conducted in Fayette County (the location of the RM facility); the test indicated a transmissivity of 2,700 square feet per day. (B&V 1996).

The RM facility was constructed in part of a wetland; RM reportedly spread and compacted several feet of clay prior to constructing the facility. A 1987 memorandum written by the State of Tennessee indicates that clayey silt was present in the area of the industrial landfill before its construction; the clayey silt was present from 0 to 3 feet, and a silty clay was present from about 3 to 7 feet.

In May 1988, five monitoring wells were installed by RM's contractor. The borings for the monitoring wells indicated the presence of about 11 feet of silty clay and clayey silt overlying sands of the Memphis Sand aquifer. In May 1997, eight additional monitoring wells were installed at the Site. A soil boring (T-4) was also drilled in the southwest corner of the Site, but it was not completed as a monitoring well. Monitoring well depths ranged from 23 to 28 feet below ground surface (bgs).


Soil samples collected during soil boring activities revealed that Site stratigraphy conformed generally to the May 1988 data collected by the RM contractor. The predominant soil type observed in surficial to shallow soil intervals (within 10 feet bgs) consists of gray, mottled, dry to moist clay. The clay unit contains a high percentage of silt (except in the western portion of the Site, where it grades to sandy clay); exhibits low plasticity and variable organic content; and occasionally exhibits a brown to tan coloration. The clay unit extends from ground surface to depths ranging from 7 to 20 feet bgs and is generally thickest in the western portion of the Site.

Sands encountered at the Site are fine-grained and grayish-white in color. Sands are generally well sorted and exhibit a fine to medium texture with occasional clay lenses and very little silt. Sand textures generally coarsen with increasing depth, becoming medium to coarse in texture below 20 feet bgs. A trend toward a decrease in the degree of sorting and an increase in the coarse sand fraction was also observed in samples collected from below 20 feet bgs.





Groundwater at the Site is encountered in the upper portion of the sand section. The aquifer possesses a degree of hydrologic confinement due to the pervasive upper clay section, and water levels in Site monitoring wells rise above the base of the clay unit.

Information collected during the 1988 and 1997 investigations conducted by the RM contractor and PRC, respectively, conflict somewhat with a Tennessee memorandum written in 1987 concerning the actual depth of clay beneath the Site. However, it can be assumed that at least 7 feet of silty clay and clayey silt are present directly under the Site; it remains undetermined how much, if any, of it is native material. Some of the clay may be part of the base of the Cook Mountain Formation or a clay lens within the upper part of the Memphis Sand. Occurrences of the overlying members of the Claiborne Group in the area of the Site may be thin or absent above the Memphis Sand. **Figures 2-6 and 2-7** present cross-section information obtained from the EPA Site investigations. Additional cross-sections were prepared for this RI/FS report using boring logs from monitor wells constructed in 1997. The 1997 boring cross-section locations are illustrated on **Figure 2-8**. The 1997 cross-sections are presented on **Figures 2-9 and 2-10**.

Although regional groundwater flows to the west, measurements collected from Site monitoring wells in 1990 indicate that shallow groundwater movement is north towards the Wolf River. However, measurements collected from the monitoring wells in 1996 suggest a more northwesterly movement of groundwater. **Figures 2-11 and 2-12** present groundwater flow based on measurements collected in an October 1990 investigation, and November 1996 investigation, respectively. Two municipal



ACAD FILE: ROSS/ROSS-CS



HORIZONTAL SCALE: 1" = 100'  
 VERTICAL SCALE: 1" = 10'


Ross Metals Site  
 Rossville, Tennessee


**CDM Federal Programs Corporation**  
*A subsidiary of Camp Dresser & McKee Inc.*

Figure No.  
 2-7


7/98

Cross Sections A-A' and B-B'







ACAD FILE: cross







ACAD FILE: ROSS\ROSS-GW



supply wells and three industrial production wells are located within 0.75 mile of the Site and are screened in the Memphis aquifer.

#### **2.5.6 Previous Investigations**

EPA has conducted numerous sampling investigations at the RM Site. A discussion of sample results from these investigations is presented in Section 2.5.7.

In May and November 1990, EPA Region 4 conducted RCRA investigations that included the collection of groundwater, surface water, surface soil, and slag samples.

From September 22 through December 29, 1994, the EPA Emergency Response and Removal Branch (ERRB) conducted an emergency time-critical removal of hazardous substances at the RM Site. Source materials, structures, and debris were removed and disposed of off Site. Approximately 4,400 gallons, 170 tons, and 1,700 CY of waste were removed. Groundwater and surface soil samples were also collected during this event.

During the week of June 13, 1995, EPA conducted a Site Investigation for Hazard Ranking System purposes. Groundwater, surface and subsurface soil, sediment, and surface water samples were collected.

In November 1996, EPA conducted site characterization studies that included surface and subsurface soil, groundwater, surface water, and wipe samples from the buildings.

During the weeks of May 19 and May 26, 1997, EPA conducted additional field sampling at the Site. EPA completed the installation and sampling of nine monitoring wells, including borehole soil sampling. Two additional groundwater samples were collected from on-Site temporary wells, and

one groundwater sample was collected from a well at the wastewater treatment plant on adjacent property located west of the RM Site. Soil samples from the landfill and a composite sample of slag stockpiles were also collected for analysis.

The presence of lead-based paint in homes near the Site has been documented. File material indicates that children living near the Site have had elevated levels of lead in their blood. The children were moved by Housing and Urban Development. Although the documentation is not strong enough to establish an observed release, the findings are significant because of the proximity of adjacent residences and the history of the RM Site. Soil samples collected adjacent to nearby homes indicated 1,170 parts per million (ppm) of lead. An EPA time-critical removal (1994) of soils was performed at this residence.

In April 1997, EPA collected surface water, sediment, plant tissue, grasshopper, and frog tissue samples as part of the completion of an ecological risk assessment for the Site. All the sediment samples were analyzed for arsenic, cadmium, copper, and lead via field portable x-ray fluorescence (XRF). In addition, several of the surface water and sediment samples collected for the ecological risk assessment were analyzed for TAL metals by an offsite laboratory. Samples from two of the surface water and sediment locations analyzed for TAL metals also were analyzed for volatile organic compounds (VOCs), base neutral acids (BNAs) and pesticide/PCBs. Surface water and sediment results are discussed in Section 2.5.7.1 and 2.5.7.3.

In December 1997, EPA/ERTC collected and performed on-Site analysis of soil samples for metals contamination, to delineate contaminant levels in the wetlands. Additionally, the effort involved the completion of treatability studies to evaluate soil treatment, and the completion of a wetlands excavation and revegetation plan to provide a design for wetlands restoration. Target elements were arsenic, cadmium lead, and zinc. A reference grid was established on the Site and surface samples were collected at the grid nodes. The grid included the wetlands located north and east of the Site.

The results of 29% of the samples were confirmed by Inductively Coupled Plasma (ICP) analysis.


In June and September 1998, EPA conducted a second time-critical removal. The removal action included fencing the soils which contained lead above 400 ppm; covering the waste piles with tarpaulins; and posting the Site as a Superfund Site.


## **2.5.7 Nature and Extent of Contamination**

### **2.5.7.1 Soil and Sediment**

Surface soil and sediment samples were collected at depths of up to 2 feet bgs. Lead-contaminated surface soil is present across the Site and in the wetlands north and east of the facility. Lead concentrations in most surface soil and sediment samples collected throughout the Site exceeded 400 ppm. In addition, aluminum, antimony, arsenic, barium, cadmium, copper, iron, manganese, selenium, and vanadium were detected above risk-based remedial goal option (RGO) levels. **Figure 2-13 and 2-14** illustrate the extent of surface soil lead contamination throughout the Site. Additional samples collected as part of an ecological risk assessment and analyzed using both XRF analysis and ICP procedures showed a widespread presence of lead and other COCs defined in the risk assessment above RGO levels in the wetlands north and east of the Site. **Figure 2-15** illustrates lead concentration contours in the wetlands based on XRF and TAL samples collected in December 1997.


The highest levels of subsurface soil contamination were found in two isolated locations at the Site; east of the wrecker building, and southeast of the truck wash. **Figure 2-16** illustrates the extent of subsurface soil lead contamination at the Site. Elevated lead concentrations were collected at depths ranging from 18 to 40 inches beneath the pavement near the wrecker building and the truck wash and at depths of up to 5.5 feet in the landfill; however, as **Figure 2-16** indicates, none of the soil samples collected from beneath the buried slag exhibited lead concentrations in excess of the RGO level.






ACIO FILE: ROSS/LEADS

<p><b>Ross Metals Site</b>  <b>Rossville, Tennessee</b></p>	<p><b>Maximum Lead Results in Sediment</b>  <b>(TAL Analysis -</b>  <b>Ecological Investigation)</b></p>	<p><b>Figure No.</b>  <b>2-14</b></p>
<p><b>CDM Federal Programs Corporation</b>  <i>A subsidiary of Corp. Greiner &amp; McKee Inc.</i></p>		<p><b>7/98</b></p>




Ross Metals Site Rossville, Tennessee CDM Federal Programs Corporation <i>A subsidiary of Eastman Kodak Company</i>	Contaminant Contour in Wetlands March 1998	Figure No. 2-15 8/98
--	--	----------------------------






LEGEND



— INTERPRETED ISOCONTOUR LINE.  
400 mg/kg INTERVAL.

3078 LEAD CONCENTRATION, mg/kg

 LANDFILL AREA  
 WETLAND AREA



**Ross Metals Site  
Rossville, Tennessee**

**CDM Federal Programs Corporation**  
A subsidiary of CDM Brown & Kalke, Inc.

### Extent of Lead in Subsurface Soils

Figure No.  
2-16

8/98

NOIS FILE: NOIS\NOIS-1902

In addition to soils, other solid media were sampled during previous investigations. Waste slag samples contained total lead concentrations ranging from 18,500 to 94,800 milligrams per kilogram (mg/kg). Total lead and TCLP lead concentrations in a floor wipe sample collected from the furnace and raw materials refinery building were 14,700 mg/kg and 574 mg/L, respectively.

#### **2.5.7.2 Groundwater**

Analytical results of groundwater samples revealed the presence of several inorganic compounds at concentrations that either exceed the primary or secondary drinking water standards or the State of Tennessee domestic water supply criteria. Aluminum, arsenic, barium cadmium, chromium, iron, lead, manganese, nickel and vanadium were detected above respective guidance concentrations and/or RGO levels. Lead concentrations in filtered groundwater samples ranged from nondetectable to 770 micrograms per liter (  $\mu\text{g/l}$ ); the EPA action level for lead in groundwater is 15  $\mu\text{g/L}$ .

Using only the filtered data set from the May 1997 sampling event, it appears that groundwater lead contamination is limited to an area just east and downgradient of the RM wrecker building. Under this assumption, the horizontal extent of the contaminant plume is about 300 feet by 200 feet. In contrast, using groundwater quality data from all historic unfiltered samples, combined with unfiltered and filtered data from the May 1997 sampling event, it could be interpreted that groundwater contamination is Site-wide. In this case, the entire Site would be considered a source. Under this assumption, the horizontal extent of the contaminant plume is at least 800 feet by 450 feet and extends off Site.

Although EPA Region 4 policy is to use only unfiltered sample results for risk assessment and determining extent of contamination, the difficulty in using the historic unfiltered sample data and even the May 1997 unfiltered sample data is that the turbidity of these samples does not meet EPA Region 4 Standard Operating Procedure goal of less than 10 NTU. The results from the unfiltered

samples with high turbidity are not representative of lead concentrations in fully developed water supply wells because water supply wells in regular use do not produce water with high turbidity due to the development of a natural filter pack around the well screen (EPA 1998d). In addition, the results for MW5 presented on **Figure 2-17** indicate that recent samples do not confirm earlier sample results. Reported lead concentrations declined from 500 ug/l to 3 ug/l in seven years. This decline is difficult to explain because lead is not degradable and the source has not been removed. The lower levels present in the more recent sampling events suggest that the earlier data may not be valid.


The high turbidity associated with the unfiltered samples collected at the RM Site means that the horizontal extent of contamination remains undefined. It may be much less than the current data indicate. Field measurements collected during the 1997 sampling event suggest that measurements with acceptably low turbidity could be attained at this Site with longer development periods.

In addition, the vertical extent of groundwater contamination has not been determined since there are no deep wells or cluster wells at the Site which could be used to determine the vertical hydraulic gradient. Without this information, vertical extent of contamination cannot be defined. It is important to have an understanding of the vertical extent of contamination to effectively evaluate potential remedial alternatives to use in the remediation of the contamination.

Based on the groundwater information, EPA has divided the Site into Operable Units with the source materials being the first Operable Unit and the groundwater being the second. Additional data will be necessary for defining the nature and extent of groundwater contamination.

### **2.5.7.3 Surface Water**

Analytical results of surface water samples revealed concentrations of several inorganic compounds that exceeded background concentrations. Significant inorganic contaminants included antimony,



ADND FILE NUMBER

Ross Metals Site  
Rossville, Tennessee  
COM Federal Programs Corporation  
A subsidiary of Energy Services & Supply, Inc.

Total Lead Concentrations - Water


arsenic, cadmium, iron, lead, and manganese. **Figure 2-17 and 2-18** illustrate lead concentrations in surface water.

#### **2.5.7.4 Contaminant Fate And Transport**

Metals, notably lead, are the primary contaminants of concern (COC) associated with the Site; these contaminants are found in soils, structures, groundwater, and surface water. These contaminants are not typically highly mobile in the environment and move primarily by soil/sediment or wind transport.


Primary mechanisms available for contaminant transport away from the RM Site are rainwater runoff, rainwater infiltration to groundwater, and windblown dust movement. A conceptual site model is presented in **Figure 2-19**. The following transport mechanisms have affected contaminants at the RM Site:

- **Rainwater Infiltration to Groundwater:** Rain falling directly on Site or as runoff to the Site moves through contaminated soils and structures. This water picks up soluble contaminants, such as metals, and during periods of heavy rainfall, moves sediments containing contaminants. Most of the area is paved and a concrete curb, which was built some years after the facility began operation, extends around most of the old fenced area. However, much of the pavement is in poor condition, allowing water seepage at the pavement discontinuities and infiltration to groundwater. A storm water collection sump located in the northeast corner of the old fenced area, apparently overflows during rain events creating runoff flow at the northeast corner of the property. Runoff appears to continue to migrate east and northeast of the old fenced area, where it enters the groundwater by infiltration. Within the landfill area, water flowing through contaminated material (buried slag) infiltrates into groundwater.
- **Windblown Dust Movement:** The old fenced portion of the RM Site is essentially devoid of vegetative cover. During dry periods, high winds could transport contaminants away from the Site with windblown dust. When the facility was in operation, wind could have transported contaminants in air coming from the exhaust stack away from the Site.



AC-140 FILE: ROSS/LEADS.W

<p><b>Ross Metals Site</b>  <b>Rossville, Tennessee</b></p>	<p><b>Lead Results in Surface Water</b>  <b>(TAL Analysis -</b>  <b>Ecological Investigation)</b></p>	<p><b>Figure No.</b>  <b>2-18</b></p>
<p><b>CDM Federal Programs Corporation</b>  <i>A subsidiary of Camp Dresser &amp; McKee Inc.</i></p>		<p><b>8/98</b></p>



ACAD FILE: ROSS\CONCEPT

- **Transport by Rainwater Runoff:** During rainfall, water moves through contaminated media on the Site. Much of the storm-water runoff within the fenced portion of the Site is routed to the collection sump in the northeast corner and discharges off Site at this location. In addition, no stormwater collection facilities exist for the landfill area, and stormwater either infiltrates to groundwater or is routed north and east of the landfill. Runoff to the west is prevented due to the presence of the City of Rossville wastewater treatment ponds. These ponds are bermed, and runoff towards this area is routed north of the Site. Runoff from the Site may carry contaminated soils, as well as dissolved contaminants, into the Wolf River located about 0.5 miles north of the Site, although no data have been collected to support this conclusion. The Wolf River flows west, through Memphis, and into the Mississippi River.

The RM facility likely released lead in spills of battery acid, metallic or oxidized lead from improper storage or disposal of battery plates or casings, airborne fallout from the smelter, and the smelter slag.

The solubility of lead minerals and complexes increases as pH decreases (Lindsay 1979). No specific pH data for Site soils are available; however, a sustained leak of battery acid would neutralize soil alkalinity, lowering the soil pH and increasing lead mobility in the soil. At the RM Site, spills of battery acid may have transported lead deep into the soil profile and to the aquifer.

Lead was released to the environment as metallic lead or lead oxide. Metallic lead oxidizes slowly to lead oxide, and lead from airborne fallout is probably released to the environment as lead oxide. Lead oxides are relatively soluble when compared to lead sulfates, phosphates, and carbonates. The smelter slag contained very high concentrations of lead; however, the slag is relatively inert.

Metal mobility in soil-waste systems is determined by the type and quantity of soil surfaces present, contaminant concentrations, concentrations of competing ions and ligands, pH, and redox status. For this reason, the use of literature or laboratory data that do not mimic the specific Site soil and waste system are not generally adequate to describe or predict the behavior of the contaminant. In order to help determine the fate of lead contamination at the RM Site, several Site fate and transport models



were completed as part of the EE/CA completed for the Site.

A one-dimensional geochemical model was used to evaluate (1) the migration of lead in soil beneath the smelter slag (2) the migration of lead below the contaminated soil near the wrecker building, and (3) a subsurface soil removal action level. The model suggested that the slag material is a potential source of contamination to groundwater; because it predicted that lead will migrate to groundwater in six years and the concentration of lead in groundwater will exceed 15 ug/l in 55 years. In addition the geochemical model suggested that soils near the wrecker building are acting as a continuing source of contamination to groundwater and that lead concentration in groundwater will continue to increase (reaching a maximum of 23,600 ug/l in 57 years) unless the source is removed.

A Hydrologic Evaluation of Landfill Performance (HELP) quasi-two-dimensional hydrologic model of water movement across, into, through, and out of landfills, coupled with the results of the geochemical modeling suggest that the construction of a geosynthetic cap will effectively eliminate the potential for future groundwater contamination.

Finally, a Random-Walk model was completed to simulate the progress of remediation for the various remediation scenarios developed for the WHPA modeling. The Random-Walk modeling suggested that a 15 ug/l groundwater action level for lead cannot be attained under a "no action" scenario. However, the results of the Random-Walk modeling must be considered cautiously.

While the modeling efforts completed for the EE/CA and the RI/FS provide more Site-specific information regarding the fate and transport of lead contamination, the results should be used cautiously. The completed modeling applications are considered interpretive. Interpretive models are useful as a framework for studying system dynamics and for analyzing flow and transport in hypothetical or assumed hydrogeologic systems.

In addition to lead, other inorganics also were identified as human health or ecological COCs. Aluminum's behavior in the environment depends on its chemistry and surrounding conditions. In soils, a low pH generally results in an increase in aluminum mobility. Plants vary in their ability to remove aluminum from soils. Biomagnification of aluminum in terrestrial food chains does not appear to occur (ASTDR 1990).

Antimony's adsorption to soil and sediment is primarily correlated with iron, manganese, and aluminum content (ASTDR 1991). Antimony can be reduced and methylated by microorganisms in anaerobic sediment, releasing volatile methylated antimony compounds into water (ASTDR 1991).

Arsenic has four valence states (-3, 0, +3, +5) but rarely occurs in its free state in nature. Inorganic arsenic is more mobile than organic arsenic and poses greater problems by leaching into surface waters and groundwaters.

Lead does not magnify to a great extent in food chains. Older organisms typically contain the highest tissue lead levels (Eisler 1988). Plants can uptake lead through surface deposition in rain, dust, and soil, or by uptake through roots. A plant's ability to uptake lead from soils is inversely related to soil pH and organic matter content.

## **2.5.8 Treatability Studies**

### **2.5.8.1 Dewatering Study, December 1997**

A bench-scale dewatering treatability study on sediment was performed to evaluate different methods of reducing the water content of the untreated sediments and identify a treatment which would improve the material handling qualities of the sediment such that free liquids are not released during transport and disposal.

The results of the initial dewatering tests determined that it would be difficult to effectively dewater these sediments. Silty materials have finer particle sizes resulting in less free drainage when dewatering. The gravity drainage test clearly demonstrated the difficulty encountered when attempting to use gravity to dewater these sediments. The silt fines prohibited the drainage of significant quantities of water from the sediments.

The most effective dewatering technique tested in terms of increasing the total solids in the sediment and removing the largest quantity of liquid, was filter press. The cake that resulted from the filter press test demonstrated why dewatering would not be the most effective treatment method for these sediments. The bottom layer (closest to the filtration device) was most effectively dewatered. Sediment above this layer had much higher water contents and would not have passed the liquid release test. This was a demonstration that the high fines in the silty material prohibit effective dewatering. In addition, the dewatering process took more than two hours using the filter press dewatering method.

The Buchner funnel test demonstrated that moderate success could likely be achieved using a belt filter press. However, the percent solids in the sediment only increased to 56 percent using this technique (untreated sediment 46 percent solids).

If dewatering is to be considered for sediment, additional testing using conditioning agent such as diatomaceous earth which would enhance the dewatering process would need to be used. While diatomaceous earth will not reduce leachability of the lead, it should enhance the release of free liquids from the sediments.

Given the high silt contents of these sediments, consideration of stabilization of these sediments is recommended. The stabilization process can be designed to improve the material handling characteristics of the sediment and reduce leachability of the sediment. Additional testing would be

required to identify effective stabilization reagents(s).

#### **2.5.8.2 Stabilization Study, March 1998**

A stabilization study was performed to evaluate stabilization reagents that would 1) reduce the leachability of lead in treated sediment and 2) improve the material handling qualities of the sediment so that free liquids are not released during transport or disposal. The results of the treatability study have determined that sediment can be treated using biosolids reagent N-Viro or phosphoric acid to reduce the leachability of lead. Treatment using N-Viro material absorbed free liquids after curing for 5 days and resulted in a material that could be excavated and transported for disposal.

Treatment using phosphoric acid, while reducing the leachability of lead, resulted in a material with free liquids and a noxious sulfide odor. Reduction in the addition rate of phosphoric acid did not reduce the sulfide odor.

The leachability of lead was decreased when the lower addition rates of CKD, LKD, and Fly Ash/PC were added to the sediment. Given the amphoteric nature of lead, it is possible that the solubility of lead in the sediment increased with the higher reagent addition rates. It is possible that the leachability would be reduced further if a 5 percent or lower addition rate was used. With the high water content in the sediment, an inert absorbent would be required along with the stabilization reagent to improve the handling characteristics.

The results of the stabilization study have demonstrated that this treatment process will effectively reduce the leachability of lead and improve the handling characteristics of the sediment. Considerations should be given to the method which the reagent is added to the sediment (in-situ or ex-situ) and the ultimate deposition of the treated sediment.

### **2.5.8.3 Biosolids Study, November 1998**

The bench-scale column treatability study was performed to evaluate different methods of reducing lead contamination by adding biosolids material. Results indicate the lead concentration in the liquid fraction decreased from 5,400 to 2,100 ppb with an increase of biosolids to sediment ratio. Greater than 61.1 percent of lead concentration was reduced from biosolids to sediment ratios of 0:5 and 1:4 which is less than the TCLP regulatory level [5.0 ppm]. The lead concentration remained the same (2,100 ppb) for biosolids to sediment ratios of 1:4 and 2:3. For another sample, the results indicate the lead concentrations in the liquid fraction were 230, 530, and 440 ppb for biosolids to sediment ratios of 0:5, 1:4, and 2:3, respectively. Based on this data and the 800 ppm goal, application of biosolids on the sediments appears to be feasible to sorb lead that may leach from the contaminated wetlands. Additional studies and tests will be required for confirmation.

## **2.6 SUMMARY OF SITE RISKS**

### **2.6.1 Human Health Risk Assessment Summary**

The primary purpose of this baseline risk assessment (BRA) is to provide a quantitative and qualitative understanding of the actual and potential risks to human health posed by the Ross Metals (RM) Site if no further remediation or institutional controls are applied. The BRA consists of both a human health evaluation and an ecological risk assessment.

#### **2.6.1.1 Data Evaluation**

Data used in this risk assessment were obtained from the following sources: May and November 1990, Environmental Services Division (ESD) Resource Conservation and Recovery Act (RCRA) investigations; 1994 Emergency Response and Removal Branch (ERRB) investigation during a time-

critical removal action; 1995 Black & Veatch pre-remedial investigation; November 1996 ESD investigation; May 1997 PRC investigation; and 1997 Emergency Response Team Center (ERTC) investigation. These data were evaluated by ESD personnel and determined to be of acceptable quality for use in a Baseline Risk Assessment.

Because of the nature of the plant's operations, the majority of the samples were analyzed for Target Analyte List (TAL) parameters (inorganics) only. Two samples collected by ERTC were analyzed for the entire Target Compound List/Target Analyte List (TCL/TAL) parameters.

The laboratory results were validated by EPA Region 4 ESD personnel using standard data validation procedures. They concluded that with the exception of a small percentage of the data that were rejected for a variety of technical reasons, the overall data package can be accepted with confidence.

The data were then summarized to show all inorganic and organic chemicals that were positively identified in at least one sample. Included in this group were unqualified results and results that were qualified with a "J" which means the chemical was present but the concentration was estimated. These values were listed as actual detected concentrations which may have the effect of under- or over-estimating the actual concentration. Tentatively identified compounds (qualified with an "N") were included if there was reason to believe that they were present. For example, if a compound was positively identified in other locations, the tentative identification was considered sufficient.

These positively identified chemicals were then screened to exclude chemicals that, although present, are not important in terms of potential health effects. The screening criteria fall into three categories:

- (1). Inorganics whose maximum detected concentration did not exceed two times the average background concentration were excluded;


- (2). Inorganics that are essential nutrients or are normal components of human diets were excluded. Calcium, magnesium potassium, and sodium were excluded because they are essential nutrients, with no known toxic effects at any relevant dosage level; and
- (3). Inorganic and organic chemicals whose maximum concentration was lower than a risk-based concentration corresponding to an excess cancer risk level of  $1 \times 10^{-6}$  or a Hazard Quotient (HQ) level of 0.1, as determined by EPA Region 3 toxicologists using residential land use assumptions, were excluded (EPA 1998b).

Since the overall site risk is the sum of risks from all relevant exposure routes (inadvertent ingestion of soil, dermal contact with soil, inhalation of dust, and ingestion of groundwater), eliminating one or more routes has the effect of reducing the apparent risk. The groundwater data that were used in this assessment contribute a significant degree of uncertainty to the overall assessment. Among the factors that should be considered is the substantial difference between the filtered and unfiltered samples (taken at the same location and time). This difference adds to the uncertainty in the exposure concentration and subsequent risk estimates. If this difference is due to turbidity, then the concentration of lead and other COPCs would change as the turbidity changes. This would result in an increase or decrease in the exposure concentration and resultant risk.

#### **2.6.1.2 Exposure Pathways**

The conceptual site model for this assessment is presented in **Figure 2-20**. As seen in this figure, metals, notably lead, are the primary contaminants of concern (COC) associated with the Site; these contaminants are found in soils, structures, groundwater, and surface water. These contaminants are not typically highly mobile in the environment and move primarily by sediment or wind transport. No specific pH data for Site soils are available; however, low pH will, in general, make metals more soluble and, therefore, more easily transportable from the Site, and more bioavailable.

Figure 2-20  
Conceptual Site Model  
Ross Metals Site  
Rossville, Tennessee





Based on this understanding of the fate and transport of contaminants, and the potential for human contact, the following media/receptors were examined:

- (1) Surficial soil/sediment in the Landfill Area and Wetland/Woodland Area. Potential receptors are Site visitors. In the future, residents and/or workers are potential receptors in the Process Area and Landfill Area.
- (2) Surface water in the Wetland/Woodland Area. Potential receptors Site visitors.
- (3) Groundwater beneath the Process Area and the Landfill Area. Potential receptors are future residents and/or workers.

Potentially complete exposure pathways examined in the risk assessment are:

- (4) inadvertent ingestion of soil,
- (5) dermal contact with soil,
- (6) inhalation of dust,
- (7) inadvertent ingestion of surface water,
- (8) dermal contact with surface water, and
- (9) ingestion of groundwater.

Reasonable maximum exposure (RME) point concentrations for soil/sediment, and surface water were calculated according to EPA Region 4 guidance using the lesser of the 95 percent upper confidence limit (UCL) on the arithmetic average for a lognormal distribution or the maximum detected value (EPA 1992a and 1995a). Where a chemical of concern was not detected at a given location, one-half the sample quantitation limit was used as a proxy concentration; however, if both the proxy concentration and the upper confidence limit exceeded the maximum detected value, the maximum detected value was used as the RME concentration. The RME concentrations for chemicals of concern are presented in **Table 2-3**.

Table 2-3						
Summary of Chemicals of Concern						
Media	Chemical of Concern	Concentration Detected (in ppm)		Frequency of Detection	Exposure Point Concentration (in ppm)	Statistical Measure
		Min	Max			
Process Area						
Soil	Antimony	7	730	21/21	217	95% UCL
	Arsenic	3	479	25/26	99	95% UCL
	Barium	19	790	21/21	157	95% UCL
	Cadmium	0.1	99	16/26	99	Max
	Copper	6	712	18/21	238	95% UCL
	Lead	6	97,700	29/29	97,700	Max
	Selenium	1	48	7/21	8	95% UCL
Landfill Area						
Soil	Antimony	75	75	1/4	75	Max
	Arsenic	8	76	4/4	76	Max
	Cadmium	1	22	3/4	22	Max
	Lead	35	42,400	11/11	42,400	Max
	Manganese	380	1,100	4/4	1,100	Max
Wetland/Woodland Area						
Soil	Aluminum	3,390	24,000	46/46	13,331	95% UCL
	Antimony	1	1,350	14/42	32	95% UCL
	Arsenic	4	681	46/46	41	95% UCL
	Barium	53	610	46/46	147	95% UCL
	Cadmium	1	18	28/46	6	95% UCL
	Copper	8	465	45/46	43	95% UCL
	Iron	4,790	40,000	46/46	19,576	95% UCL
	Lead	67	98,100	52/52	5,827	95% UCL
	Manganese	25	1,500	46/46	752	95% UCL
	Selenium	2	84	13/46	4	95% UCL
	Vanadium	10	63	46/46	31	95% UCL

Table 2-3						
Summary of Chemicals of Concern						
Media	Chemical of Concern	Concentration Detected (in ppm)		Frequency of Detection	Exposure Point Concentration (in ppm)	Statistical Measure
		Min	Max			
Process Area						
Surface Water	Aluminum	168	1,300	7/10	1,300	Max
	Antimony	8	150	7/10	150	Max
	Arsenic	18	554	9/10	554	Max
	Cadmium	6	120	6/10	120	Max
	Copper	6	140	9/10	140	Max
	Iron	313	42,700	10/10	42,700	Max
	Lead	36	16,000	10/10	16,000	Max
	Manganese	229	5,520	10/10	5,520	Max
	Mercury	0.2	0.4	4/10	0.4	Max
	Selenium	7	11	2/10	7	95% UCL
	Thallium	13	13	3/10	13	Max
	Zinc	39	568	7/10	568	Max
Groundwater	Aluminum	380	23,000	9/14	2,608	Ave
	Arsenic	21	40	2/24	20	Ave
	Barium	11	380	14/14	90	Ave
	Cadmium	5	7	3/14	2	Ave
	Chromium	39	39	1/14	6	Ave
	Iron	1,300	64,000	10/14	12,126	Ave
	Lead	3	1,600	18/24	196	Ave
	Manganese	130	5,600	10/14	1,472	Ave
	Nickel	45	160	4/14	24	Ave
	Vanadium	7	49	3/14	6	Ave

UCL: Upper Confidence Limit

Max: The highest detected concentration

Ave: Average concentration within the plume

### 2.6.1.3 Toxicity Values

The RfDs and CSFs used in this assessment were primarily obtained from EPA's IRIS database (EPA 1998c). Values that appear in IRIS have been extensively reviewed by EPA work groups and thus represent Agency consensus. If no values for a given compound and route of exposure were listed in IRIS, then EPA's HEAST (EPA 1995b) were consulted. Where no value was listed in either IRIS or HEAST, EPA's National Center for Environmental Assessment (formerly the Environmental Criteria and Assessment Office) was consulted. **Tables 2-4** and **2-5** summarize the toxicity values for carcinogenic and non-carcinogenic COCs, respectively.

Neither a CSF nor an RfD is available for lead. Instead, blood lead concentrations have been accepted as the best measure of exposure to lead. Because children are the most vulnerable to lead toxicity, EPA has developed an integrated exposure uptake biokinetic model (IEUBK) to assess chronic, non-carcinogenic exposures of children to lead. When this model is used, and the detected concentrations are shown to be acceptable to the most vulnerable group in the population (children), it is not necessary to address adult exposure.

To characterize risk associated with dermal exposure, the toxicity values presented in Tables 2-4 and 2-5 were adjusted from administered to absorbed toxicity factors according to the method described in Appendix A to RAGS (EPA 1989a). The following oral absorption percentages were employed: 80 percent for VOCs, 50 percent for semi-volatile organics, and 20 percent for inorganics (EPA

Table 2-4 Cancer Slope Factor						
Chemical of Concern	CsFo	ABSeff	CSFd	CSFi	Tumor Site	EPA Class
Aluminum	NA	20%	NA	NA	NA	D
Antimony	NA	20%	NA	NA	NA	D
Arsenic	1.5E+00 i	100%	NA	NA	Skin	A
Barium	NA	20%	NA	NA	NA	D
Cadmium	NA	20%	NA	6.3E+00 i	Lung	B1
Chromium	NA	20%	NA	4.2E+01 i	Lung	A
Copper	NA	20%	NA	NA	NA	D
Iron	NA	20%	NA	NA	NA	D
Lead	NA	20%	NA	NA	Kidney	B2
Manganese	NA	20%	NA	NA	NA	D
Mercury	NA	20%	NA	NA	NA	D
Selenium	NA	20%	NA	NA	NA	D
Thallium	NA	20%	NA	NA	NA	D
Vanadium	NA	20%	NA	NA	NA	D
Zinc	NA	20%	NA	NA	NA	D

Source:

i - IRIS

CSFo - Cancer Slope Factor (oral), (mg/kg/day)-1

CSFd - Cancer Slope Factor (dermal), (mg/kg/day)-1

ABSeff - Absorption efficiency: 20% inorganics, 50% semivolatiles, 80% volatiles. Based on RIV policy.

CSFi - Cancer Slope Factor (inhalation), (mg/kg/day)-1

NA - Not Applicable

EPA Cancer Classes

A - Human carcinogen

B - Probable human carcinogen

C - Possible Human carcinogen

D - Not classifiable as a human carcinogen

<b>Table 2-5 Reference Dose</b>					
Chemical of Concern	RfDo	ABSeff	RfDd	RfDi	Target Sites/Effects
Aluminum	1E+00 n	20%	2E-01	NA	Not specified
Antimony	4E-04 i	20%	8E-05	NA	Longevity, blood glucose
Arsenic	3E-04 i	100%	3E-04	NA	Hyperpigmentation
Barium	7E-02 i	20%	1E-02	NA	Incr. blood pressure
Cadmium (water)	5E-04 i	20%	1E-04	NA	Proteinuria
Cadmium (food)	1E-03 i	20%	2E-04	NA	Proteinuria
Chromium	5E-03 i	20%	1E-03	4.2E+01 i	NOAEL
Copper	4E-02 n	20%	8E-03	NA	Not specified
Iron	3E-01 n	20%	6E-02	NA	NOAEL
Lead	NA	20%	NA	NA	CNS effects, blood
Manganese (soil)	7E-02 IV	20%	1E-02	1.43E-05	NOAEL
Manganese (water)	2.4E-02 IV	20%	NA	NA	Neurotoxicity
Mercury	3E-04 i	20%	6E-05	NA	Neurotoxicity
Selenium	5E-03 i	20%	1E-03	NA	Clinical selenosis
Thallium	9E-05 i	20%	2E-05	NA	Incr. SGOT and LDH
Vanadium	7E-03 i	20%	1E-03	NA	Decr. hair cystine
Zinc	3E-01 i	20%	6E-02	NA	Decr. ESOD

Sources:

i - IRIS

n - NCEA (National Center for Environmental Assessment)

IV - The RfDo for manganese in IRIS is 1.4E-1 mg/kg/day based on the NOAEL of 10 mg/day. For soil exposure, Region IV policy is to subtract the average daily dietary exposure (5 mg/d) from the NOAEL to determine a "soil" RfDo. When this is done, a "soil" RfDo of 7E-2 mg/kg/day results. For water exposure, a neonate is considered a sensitive receptor for the neurological effects of manganese. Thus caution, (in the form of a modifying factor) is warranted until more data are available. Using a modifying factor of 3 results in a "water" RfDo of 2.4E-2 mg/kg/day.

RfDo - Reference Dose (oral), (mg/kg/day)

RfDd - Reference Dose (dermal), (mg/kg/day)

ABSeff - Absorption efficiency: 20% inorganics, 50% semivolatiles, 80% volatiles. Based on RIV policy.

RfDi -Reference Dose (inhalation), (mg/kg/day)

NA - Not Applicable

1995a). The only exception to this was for arsenic. According to recently released EPA Region 4 guidance, the gastrointestinal absorption rate of arsenic may be considered 100 percent (Koporec 1998). Thus, when considering dermal exposure to arsenic, no adjustment is necessary.

#### **2.6.1.4 Risk Characterization**

The final step of the baseline risk assessment is the risk characterization. Human intakes for each exposure pathway are integrated with EPA reference toxicity values to characterize risk. Carcinogenic, non-carcinogenic, and lead effects are estimated separately.

To characterize the over all potential for non-carcinogenic effects associated with exposure to multiple chemicals, EPA uses a Hazard Index (HI) approach. This approach assumes that simultaneous subthreshold chronic exposures to multiple chemicals that affect the same target organ are additive and could result in an adverse health effect. The HI is calculated as follows:

$$\text{Hazard Index} = \text{ADD}_1/\text{RfD}_1 + \text{ADD}_2/\text{RfD}_2 + \dots \text{ADD}_i/\text{RfD}_i$$

where:  $\text{ADD}_i$  = Average Daily Dose (ADD) for the  $i$ th toxicant

$\text{RfD}_i$  = Reference Dose for the  $i$ th toxicant

The term  $\text{ADD}_i/\text{RfD}_i$  is referred to as the Hazard Quotient (HQ).

Calculation of an HI in excess of unity indicates the potential for adverse health effects. Indices greater than one will be generated anytime intake for any of the Chemicals of Potential Concern (COPC). However, given a sufficient number of chemicals under consideration, it is also possible to generate an HI greater than one even if none of the individual chemical intakes exceeds its respective RfD.

Carcinogenic risk is expressed as a probability of developing cancer as a result of lifetime exposure. For a given chemical and route of exposure, excess lifetime cancer risk is calculated as follows:

$$\text{Risk} = \text{Lifetime Average Daily Dose (LADD)} \times \text{Carcinogenic Slope Factor (CSF)}$$

These risks are probabilities that are generally expressed in scientific notation (i.e.,  $1 \times 10^{-6}$  or 1E-6). An incremental lifetime cancer risk of  $1 \times 10^{-6}$  indicates that, as a plausible upper-bound, an individual has a one-in-one-million chance of developing cancer as a result of Site-related exposure to a carcinogen over a 70-year lifetime under the specific exposure conditions at the Site. For exposures to multiple carcinogens, EPA assumes that the risk associated with multiple exposures is equivalent to the sum of their individual risks.

#### ***Process Area: Current Use Risk Summary***

The Process Area presents physical and chemical risks to human health. The Site contains numerous unstable structures that pose physical risks to trespassers. Incidents involving unstable structures are potentially fatal and represent significant risk associated with the Site. The condition of the structures will worsen over time, with a corresponding increase in associated hazards.

Apart from the physical hazards noted above, exposure to contaminants in soil in the Process Area is curtailed by the asphalt pavement that covers the great majority of the Site and exposure to contaminated soils is not possible. Also, there are no groundwater wells in use that tap the contaminated zone of the aquifer. Thus, for these reasons, current exposure routes are incomplete.

#### ***Process Area: Future Use Risk Summary***

In the future, the Site may be redeveloped for either residential or commercial/industrial use based



on dialogue with local land use planning officials and citizens. Such redevelopment would expose the contaminated soils that exist beneath the pavement. Potential receptors would be Site visitors, Site workers, child residents, adult residents, and lifetime residents. Exposure routes potentially complete in such a scenario are:

- inadvertent ingestion of soil;
- dermal contact with soil; and
- inhalation of dust
- ingestion of groundwater

**Table 2-6** summarizes the cancer and noncancer risks for these receptors. The total incremental lifetime cancer risk estimates range from  $3 \times 10^{-9}$  for the Site visitor to  $5 \times 10^{-4}$  for the lifetime resident. In addition to the lifetime resident, risk estimates for the child resident and adult resident are above EPA's target range for Superfund sites. Arsenic in groundwater accounts for the excess cancer risk. Noncancer effects are possible for Site workers, child, adult, and lifetime residents based on HIs of 2, 25, 7, and 10 respectively. Exposure to antimony, arsenic, and iron, and manganese in groundwater account for the majority of the potential non-cancer effects. **Table 2-7** summarizes the cancer and noncancer risks for these receptors when the ingestion of groundwater route is eliminated.

***Process Area: Exposure to Lead***

In the future, the Site may be redeveloped for either residential or commercial/industrial use. Such redevelopment would expose the contaminated soils that exist beneath the pavement. Potential receptors would be Site visitors, Site worker, child residents, adult residents, and lifetime residents. In this future scenario, ingestion of groundwater from wells developed from within the contaminant plume is considered as an additional exposure route for Site workers, child residents, adult residents, and lifetime resident. Exposure routes potentially complete in such a scenario are:

**Table 2-6**  
**Summary of Cancer and Noncancer Risks by Exposure Route**  
**Future Use Scenario**  
**Process Area**  
**Ross Metals site**  
**Rossville, Tennessee**

<b>Exposure Route</b>	<b>Site Visitor</b>		<b>Site Worker</b>		<b>Child Resident</b>		<b>Adult Resident</b>		<b>Lifetime Resident</b>	
	<b>Cancer</b>	<b>HI</b>	<b>Cancer</b>	<b>HI</b>	<b>Cancer</b>	<b>HI</b>	<b>Cancer</b>	<b>HI</b>	<b>Cancer</b>	<b>HI</b>
Ingestion Groundwater	NA	NA	1E-004	2	2E-004	12	3E-004	5	5E-004	7
Inadvertent Ingestion Soil	NA	0.3	NA	0.5	NA	13	NA	1	NA	4
Dermal Contact Soil	NA	0.1	NA	0.2	NA	1	NA	0.3	NA	0.3
Inhalation Dust	3E-009	0.0001	3E-008	0.0004	3E-008	1.001	4E-008	0.001	7E-008	0.001
<b>TOTAL RISK</b>	<b>3E-009</b>	<b>0.4</b>	<b>1E-004</b>	<b>2</b>	<b>2E-004</b>	<b>25</b>	<b>3E-004</b>	<b>7</b>	<b>5E-004</b>	<b>10</b>

Cancer: Excess cancer risk level

HI: Hazard index (non-cancer risk)

NA: not applicable

**Table 2-7**  
**Summary of Cancer and Noncancer Risks by Exposure Route**  
**Future Use Scenario (w/o Groundwater Pathway)**  
**Process Area**  
**Ross Metals site**  
**Rossville, Tennessee**

<b>Exposure Route</b>	<b>Site Visitor</b>		<b>Site Worker</b>		<b>Child Resident</b>		<b>Adult Resident</b>		<b>Lifetime Resident</b>	
	<b>Cancer</b>	<b>HI</b>	<b>Cancer</b>	<b>HI</b>	<b>Cancer</b>	<b>HI</b>	<b>Cancer</b>	<b>HI</b>	<b>Cancer</b>	<b>HI</b>
Inadvertent Ingestion Soil	NA	0.3	NA	0.5	NA	13	NA	1	NA	4
Dermal Contact Soil	NA	0.1	NA	0.2	NA	1	NA	0.3	NA	0.3
Inhalation Dust	3E-009	0.0001	3E-008	0.0004	3E-008	0.001	4E-008	0.001	7E-008	0.001
<b>TOTAL RISK</b>	<b>3E-009</b>	<b>0.4</b>	<b>3E-008</b>	<b>1</b>	<b>3E-008</b>	<b>13</b>	<b>4E-008</b>	<b>2</b>	<b>7E-008</b>	<b>4</b>

Cancer: Excess cancer risk level

HI: Hazard index (non-cancer risk)

NA: not applicable

- inadvertent ingestion of soil,
- dermal contact with soil,
- inhalation of dust, and
- ingestion of groundwater.

Lead was detected in all Process Area soil samples at concentrations ranging from 6 to 97,700 ppm; the average concentration was 8,788 ppm. Lead was also detected in Site groundwater at concentrations of 3 to 1,600 µg/l; the average concentration was 196 µg/l. These values were input into version 0.99d of the IEUBK model. The results are summarized in **Table 2-8**. An additional model run was conducted with a default value of 4 µg/l for groundwater as an input. The results are summarized in **Table 2-9**. EPA uses a level of 10 µg lead per deciliter (dl) blood as the benchmark to evaluate lead exposure. As can be seen, the projected blood lead levels exceeded this threshold for all age groups, indicating that lead concentrations are above the acceptable range.

#### ***Landfill Area: Future Risk Summary***

In the future, the Landfill Area may be redeveloped for commercial/industrial use or it may be converted to residential use. Ingestion of groundwater is an additional exposure route that may exist in a future use scenario. **Table 2-10** summarizes the cancer and noncancer risks for the Site visitor, Site worker, child resident, adult resident, and lifetime resident. The total incremental lifetime cancer risk estimates range from  $8 \times 10^{-10}$  for the Site visitor to  $5 \times 10^{-4}$  for the lifetime resident. In addition to the lifetime resident, the risk estimate for the adult resident is above EPA's target range for Superfund sites. Arsenic in groundwater accounts for the excess cancer risk. Noncancer effects are possible for Site workers, and child, adult, and lifetime residents based on HIs of 2, 18, 6, and 8, respectively. Exposure to arsenic, antimony, and cadmium in soil and arsenic, iron, and manganese in groundwater account for the majority of the potential non-cancer effects. **Table 2-11** summarizes the cancer and noncancer risks excluding the groundwater pathway.

**Table 2-8**  
**Projected Blood Lead Levels by Age Group**  
**Process Area**  
**Ross Metals Site**  
**Rossville, Tennessee**

<b>Blood Lead Levels (ug/dl)</b>						
<b>Year 0.5-1</b>	<b>Year 1-2</b>	<b>Year 2-3</b>	<b>Year 3-4</b>	<b>Year 4-5</b>	<b>Year 5-6</b>	<b>Year 6-7</b>
40.5	47.4	45.7	45.4	41.4	38	35.4

Source: Integrated Exposure Uptake Biokinetic Model for Lead in Children, version 0.99d.

Assumptions:

Air concentration: 0.200 ug Pb/m<sup>3</sup> (default)

Diet (default)

Soil and dust: 8,788 ug/g (average lead concentration in soil); Multiple Source Analysis

Drinking water: 196 ug/l (average concentration in plume)

Paint intake: 0.00 ug Pb/day (default)

Maternal contribution: Infant model (default)

**Table 2-9**  
**Projected Blood Lead Levels by Age Group**  
**Process Area (w/o Groundwater Pathway)**  
**Ross Metals Site**  
**Rossville, Tennessee**

<b>Blood Lead Levels (ug/dl)</b>						
<b>Year 0.5-1</b>	<b>Year 1-2</b>	<b>Year 2-3</b>	<b>Year 3-4</b>	<b>Year 4-5</b>	<b>Year 5-6</b>	<b>Year 6-7</b>
38.4	43.9	42.0	41.7	37.2	33.3	30.5

Source: Integrated Exposure Uptake Biokinetic Model for Lead in Children, version 0.99d.

Assumptions:

Air concentration: 0.200 ug Pb/m<sup>3</sup> (default)

Diet (default)

Soil and dust: 8,788 ug/g (average lead concentration in soil); Multiple Source Analysis

Drinking water: 4 ug/l (default)

Paint intake: 0.00 ug Pb/day (default)

Maternal contribution: Infant model (default)

**Table 2-10**  
**Summary of Cancer and Noncancer Risks by Exposure Route**  
**Future Use Scenario**  
**Landfill Area**  
**Ross Metals Site**  
**Rossville, Tennessee**

Exposure Route	Site Visitor		Site worker		Child Resident		Adult Resident		Lifetime Resident	
	Cancer	HI	Cancer	HI	Cancer	HI	Cancer	HI	Cancer	HI
Ingestion Groundwater	NA	NA	1E-004	2	2E-004	12	3E-004	5	5E-004	7
Inadvertent Ingestion Soil	NA	0.1	NA	0.2	NA	6	NA	1	NA	2
Dermal Contact Soil	NA	0.02	NA	0.1	NA	0.2	NA	0.1	NA	0.1
Inhalation Dust	8E-010	0.003	7E-009	0.01	6E-009	0.04	1E-008	0.02	2E-008	0.02
<b>TOTAL RISK</b>	<b>8E-010</b>	<b>0.2</b>	<b>1E-004</b>	<b>2</b>	<b>2E-004</b>	<b>18</b>	<b>3E-004</b>	<b>6</b>	<b>5E-004</b>	<b>8</b>

Cancer: Excess cancer risk level

HI: Hazard index (non-cancer risk)

NA: not applicable

**Table 2-11**  
**Summary of Cancer and Noncancer Risks by Exposure Route**  
**Future Use Scenario (w/o Groundwater Pathway)**  
**Landfill Area**  
**Ross Metals Site**  
**Rossville, Tennessee**

Exposure Route	Site Visitor		Site worker		Child Resident		Adult Resident		Lifetime Resident	
	Cancer	HI	Cancer	HI	Cancer	HI	Cancer	HI	Cancer	HI
Inadvertent Ingestion Soil	NA	0.1	NA	0.2	NA	6	NA	1	NA	2
Dermal Contact Soil	NA	0.02	NA	0.1	NA	0.2	NA	0.1	NA	0.1
Inhalation Dust	8E-010	0.003	7E-009	0.01	6E-009	0.04	1E-008	0.02	2E-008	0.02
<b>TOTAL RISK</b>	<b>8E-010</b>	<b>0.2</b>	<b>7E-009</b>	<b>0</b>	<b>6E-009</b>	<b>6</b>	<b>1E-008</b>	<b>1</b>	<b>2E-008</b>	<b>2</b>

Cancer: Excess cancer risk level

HI: Hazard index (non-cancer risk)

NA: not applicable



### ***Landfill: Exposure to Lead***

Lead was detected in all Landfill Area soil samples at concentration ranging from 35 - 42,400 ppm; the average concentration was 5,964 ppm. Lead was also detected in Site groundwater at concentrations of 3 to 1,600 F g/l; the average concentration was 196 F g/l. These values were input into version 0.99d of the IEUBK model. The results are summarized in **Table 2-12**. Also, a default value of 4 F g/l for groundwater was input into the model. The results are summarized in **Table 2-13**. EPA uses a level of 10 F g lead per deciliter (dl) blood as the benchmark to evaluate lead exposure. As can be seen, the projected blood lead levels exceeded this threshold for all age groups, indicating that lead concentrations are above the acceptable range.

### ***Wetland/Woodland Area***

Future development in the Wetland/Woodland Area is unlikely due to its location in a 100-Year Floodplain and wetlands. Therefore, the only receptors that may come into contact with contaminants are Site visitors. Exposure routes potentially complete are:

- inadvertent ingestion of soil,
- dermal contact with soil,
- inhalation of dust, and
- inadvertent ingestion of surface water

### ***Wetland/Woodland Area: Exposure to Lead***

Due to the intermittent exposure to lead in the Wetland/Woodland Area, the IEUBK model cannot be directly used to estimate blood lead levels. However, if a child were to visit this area as little as once per week (the same exposure frequency assumed for the Site visitor), the child would establish

**Table 2-12**  
**Projected Blood Lead Levels by Age Group**  
**Landfill Area**  
**Ross Metals Site**  
**Rossville, Tennessee**

<b>Blood Lead Levels (ug/dl)</b>						
<b>Year 0.5-1</b>	<b>Year 1-2</b>	<b>Year 2-3</b>	<b>Year 3-4</b>	<b>Year 4-5</b>	<b>Year 5-6</b>	<b>Year 6-7</b>
33.4	39.6	38.3	38.1	34.9	32.1	29.9

Source: Integrated Exposure Uptake Biokinetic Model for Lead in Children, version 0.99d.

Assumptions:

Air concentration: 0.200 ug Pb/m<sup>3</sup> (default)

Diet (default)

Soil and dust: 5,964 ug/g (average lead concentration in soil); Multiple Source Analysis

Drinking water: 196 ug/l (average concentration in plume)

Paint intake: 0.00 ug Pb/day (default)

Maternal contribution: Infant model (default)

**Table 2-13**  
**Projected Blood Lead Levels by Age Group**  
**Landfill Area (w/o Groundwater Pathway)**  
**Ross Metals Site**  
**Rossville, Tennessee**

<b>Blood Lead Levels (ug/dl)</b>						
<b>Year 0.5-1</b>	<b>Year 1-2</b>	<b>Year 2-3</b>	<b>Year 3-4</b>	<b>Year 4-5</b>	<b>Year 5-6</b>	<b>Year 6-7</b>
30.9	35.4	33.9	33.6	29.7	26.4	24.0

Source: Integrated Exposure Uptake Biokinetic Model for Lead in Children, version 0.99d.

Assumptions:

Air concentration: 0.200 ug Pb/m<sup>3</sup> (default)

Diet (default)

Soil and dust: 8,788 ug/g (average lead concentration in soil); Multiple Source Analysis

Drinking water: 4 ug/l (default)

Paint intake: 0.00 ug Pb/day (default)

Maternal contribution: Infant model (default)

a steady state blood lead level, and the risk to this child would be over EPA's acceptable level. This is because the lead concentration in the Wetland/Woodland Area (average concentration 4,555 mg/kg) is more than seven times the IEUBK-based residential remedial level for lead (400 mg/kg).

### **2.6.2 Ecological Risk Assessment Summary**

An ecological risk assessment was conducted to determine the potential for ecological risk at the Site. This section summarizes the approach that was followed and the conclusions that were drawn.

The risk assessment was designed to evaluate the potential threats to ecological function from exposure to Site contaminants and to establish Site-specific clean-up levels for the contaminants of concern (COCs). The problem formulation process included the identification of COPCs, the identification of exposure pathways, a determination of the assessment endpoints for the Site, the formulation of testable hypotheses, the development of a conceptual model, and the determination of the measurement endpoints.

#### **2.6.2.1 Identification of Chemicals of Concern**

A screening-level risk assessment was conducted in which the maximum concentrations of contaminants detected in the surface water and sediment at the Site were compared to various benchmark values in order to identify chemical of potential concern (COPCs). Metals had previously been identified as contaminants at the Site, based on knowledge of the industrial history of the facility, as well as the results from a variety of United States Environmental Protection Agency (U.S. EPA) sampling investigations. The metals and organics data were screened using a risk characterization process that relates exposure concentrations to concentrations that potentially cause adverse effects. The exposure concentrations were the highest concentration detected for each contaminant in the sediment and surface water samples collected on Site (not including the reference samples). The

benchmark concentrations used in the screening-level risk assessment were the U.S. EPA Region 4 Waste Management Division Screening Values for Hazardous Waste Sites. If a Region 4 screening value was not available for a particular contaminant, the U.S. EPA Region 3 Screening Level, if available, was used (U.S. EPA 1995).

An elevated hazard quotient (greater than one) resulting from the screening-level risk assessment indicates that exposure to the contaminant may cause an adverse effect. However, more assessment is needed to determine if the contaminants exceeding the benchmark values pose a risk to ecological receptors at the Site. The contaminants for which maximum concentrations of compounds exceeded benchmarks for water and/or sediment at the Ross Metals Superfund Site are summarized next and in **Table 2-14**.

Many inorganic compounds exceeded the benchmark values for surface water and/or sediment. The maximum surface water concentrations recorded at the Site exceeded the benchmark values for the following compounds: aluminum, antimony, cadmium, copper, iron, lead, thallium, and zinc. The maximum sediment concentrations recorded at the Site exceeded the benchmark values for the following compounds: antimony, arsenic, cadmium, copper, lead, mercury, nickel, silver, and zinc. In addition, twelve inorganic compounds for which no sediment benchmark exists were detected in sediment. These compounds are aluminum, barium, beryllium, calcium, cobalt, iron, magnesium, potassium, selenium, sodium, thallium, and vanadium (Table 2-14).

The listing of COPC was further refined by conducting a Site-specific ecological risk assessment.

<p><b>Table 2-14</b></p> <p><b>COCs Distribution and Hazard Quotient Calculations</b></p>										
Contaminant	Maximum Concentrations in Sediment					Maximum Concentrations in Water (Filtered)				
	Maximum Sediment Concentration	Detection s/Samples	Screening Value	Reference Source	HQ	Maximum Water Concentration	Detections/Samples	Screening Value	Reference Source	HQ
Metals mg/kg (dry weight)						ug/l				
Aluminum	17,800	21/21	NB	NB	NB	506	5/5	87	d	6
Antimony	1,350	18/21	12	d	113	31.1	5/5	160	d	0.19
Arsenic	681	21/21	7.24	d	94	165	4/5	190	d	0.9
Cadmium	99.1	14/21	1	d	99	5.9	2.5	0.66	d	9
Copper	712	21/21	18.7	d	38	226	5/5	6.54	d	35
Iron	32,300	21/21	NB	NB	NB	17,600	5/5	1,000	d	18
Lead	98,100	21/21	30.2	d	3,248	924	5/5	1.32	d	700
Mercury	1.1	4/21	0.13	d	8	U	0/5	0.012	d	0
Nickel	127	21/21	15.9	d	8	34	4/5	87.81	d	0.4
Silver	2.1	2/21	0.733	d	3	U	0/5	0.012	d	0
Thallium	5.5	1/21	NB	NB	NB	18	2/5	4	d	45
Zinc	629	21/21	124	d	5	783	5/5	58.91	d	13

### 2.6.2.2 Ecological Exposure Assessment

#### **Setting**

The wetlands delineated on the Site were both naturally formed and human-made. Wetlands on the landfill and within the RM Site boundary are considered human-made. The remaining wetlands identified and delineated are considered natural systems.

Four wetland areas were identified and delineated at the RM Site. Two of the wetland areas were isolated emergent wetlands delineated on the landfill in the northern portion of the RM Site. One isolated emergent wetland was identified in the southwest portion of the RM Site. The areas to the east and north of the RM Site are classified as wetland. This wetland complex included an emergent wetland located in the southeastern portion of the landfill. Wetlands east of the Site consisted of emergent wetlands that were replaced in succession by broad-leaved deciduous scrub/shrub and broad-leaved deciduous forested wetlands as you proceeded north and east. Wetlands north of the Site consisted of broad-leaved deciduous forested wetlands. Needle-leaved deciduous (baldcypress) forested wetlands replaced the broad-leaved deciduous forested wetlands as you proceeded north and northeast from the study area. These wetlands are part of a large wetland complex associated with the Wolf River floodplain.

#### ***Vegetation***

Five vegetation types/communities (was one upland community and four wetland) were identified in the investigation area. The classification of wetlands followed Cowardin et al. (1979).

- 1) Upland field
- 2) Palustrine emergent (PEM)

- 3) Palustrine broad-leaved deciduous scrub/shrub (PSS1)
- 4) Palustrine broad-leaved deciduous forested (PFO1)
- 5) Palustrine needle-leaved deciduous (baldcypress) forested (PFO2)

Note that the survey was conducted after fall dieback of vegetation. Therefore, the identification of herbaceous species was limited.

#### Upland field

The southern/southeastern portion of the RM Site contained an area of open field. Common species included *Poa spp.*, broomsedge (*Andropogon spp.*) and foxtail (*Setaria spp.*).

#### Palustrine emergent wetland

Four separate emergent wetland areas were identified at the Site. Three were isolated wetlands. Two of these are located on the landfill. The third isolated wetland is located within the southeastern portion of the RM Site. The fourth emergent wetland is located to the east of the RM facility area and is part of a large wetland complex associated with the Wolf River.

Dominant plant species for these areas included soft rush (*Juncus effusus*), cattail (*Typha spp.*), cutgrass (*Leersya spp.*) and a variety of sedges, grasses and herbaceous species, most of which could not be identified due to the time of the Site visit (following fall dieback of vegetation).

#### Palustrine broad-leaved deciduous scrub/shrub (PSS1)

This wetland type was found east and northeast of the RM Site, and was a transition between



the PEM and forested wetlands within the study area.

Common sapling species include green ash ( *Fraxinus pennsylvanica*), willow oak (*Quercus phellos*), sweet gum (*Liquidambar styraciflua*), red maple (*Acer rubrum*) and box elder (*Acer negundo*). Common shrub species included buttonbush ( *Cephalanthus occidentalis*) and Rubus species (*Rubus spp.*). Understory species included most of those identified in the PEM wetlands. Other common species included Japanese honeysuckle ( *Lonicera japonica*), field garlic ( *Allium spp.*) and unidentified grasses and asters.

#### Palustrine broad-leaved deciduous forested (PFO1)

This wetland type was identified to the north of the landfill and to the east and north of the PSS1 wetlands. Common tree species included sweet gum, willow oak, overcup oak (*Quercus lyrata*), American elm (*Ulmus americana*), river birch ( *Betula nigra*), and red maple. Common shrub species included common winterberry (*Ilex verticillata*), and a honeysuckle species (*Lonicera spp.*). The sparse groundcover included numerous seedlings, birdbill spikegrass ( *Chasmanthium ornithorhynchum*), sensitive fern ( *Onoclea sensibilis*), and nettles. Greenbriars ( *Smilax spp.*) were a common woody vine.

#### Palustrine needle-leaved deciduous (baldcypress) forested (PFO2)

This wetland type was located north of the PFO1 wetlands. Baldcypress (*Taxodium distichum*) was the only tree species in this wetland type. Virginia willow ( *Itea virginica*) was the only shrub species found, and was restricted to elevated mounds scattered in the wetland area. Herbaceous species were lacking.

### ***Soils***

Soil color was generally a reliable indicator of wetland (hydric) and nonwetland areas at the Site and adjacent areas. Gleying, oxidized root channels, and accumulation of organic matter in the top 12 inches of the soil surface were all positive indicators of hydric soils in wetland areas. The soil profiles suggested alluvial soils. This is consistent with the Fayette County soil survey mapping for the area (Flowers 1964)

Upland soils lacked mottles and hydric color, and were generally a brighter color than hydric soils in wetlands.

### ***Hydrologic Conditions***

Direct evidence of wetland hydrologic conditions in the form of standing water, and soil saturation or free water within twelve inches of the soil surface in soil borings, was recorded at the wetland sample stations during Site visits. Emergent wetlands contained standing water and saturation to the soil surface. The scrub/shrub and deciduous forested wetlands generally had saturation and/or free water within 10 inches of the soil surface. The baldcypress wetlands contained standing water.

Indirect indicators of wetland hydrologic conditions included a lack of accumulated litter in forested wetland areas and water stained leaves. This suggests that the area may be flooded by the Wolf River.

### ***Other Waters***

Two drainage features were identified within the study area. One of these is a drainage swale (slough) north of the Site that conveys surface water to the north into a baldcypress swamp.

It is associated with an area of emergent wetland. This drainage feature likely receives runoff from the RM Site that gathers in the northeast corner of the Site and from portions of the landfill that slope towards the east and northeast.

The second drainage feature, a ditch located north of the Site, is the remnant of an historic stream that was originally located along the western edge of the Site, and may have been part of the Site. There are no defined channels connecting this ditch with the RM Site.

Another ditch is located east of the Site, just to the east of the boundary of the PFO1 wetland along the eastern edge of the study area. The ditch bends towards the west as it proceeds north, eventually discharging into the baldcypress swamp north of the RM Site. No defined channels from the RM Site discharge into this ditch.

These three drainage features join in the baldcypress swamp north of the RM Site, and eventually discharge into the Wolf River, which is a tributary of the Mississippi River.

### **Exposure Pathways**

Prior to the initiation of the ecological risk assessment, it was known that elevated levels of contaminants were present in the sediment, water, and possibly the biota on and adjacent to the Site. The contamination was not only present within the facility boundaries, but also extended approximately 300 feet east and 200 feet north of the facility boundaries. The degree of contamination further away from the facility was not known prior to conducting this risk assessment. A drainage ditch flows from a stormwater collection sump in the northeast corner of the facility area into the wetland area approximately 380 feet due northeast. This ditch could act as a pathway for contamination to continue migration northeast of the facility, especially during heavy rain events. It was also not known whether the contamination had migrated into the Wolf River, approximately 1/2-mile north of the facility. Therefore, the wetlands north and east of the facility, the Wolf River, and

the facility itself were identified as areas of concern prior to this risk assessment.

Chemical analyses of sediment, water, and biota were used to determine the levels of contaminants in each area. The maximum concentration and the arithmetic mean of each contaminant concentration were calculated from the resulting analytical data and used in the risk assessment to represent the conditions of Site-specific exposure.

On-Site receptors are potentially exposed to contaminants in abiotic matrices through direct contact, intentional ingestion (e.g., consumption of water and food items), and incidental ingestion (e.g., sediment adhered to food items). Transfer of the contaminants to receptors could also occur through processes of bioaccumulation through the food chain, whereby higher trophic level receptors are exposed to Site contaminants through the ingestion of contaminated prey items.

***Summary of field studies and modeling:*** A field investigation was conducted to obtain Site-specific contaminant concentrations in water, sediment, and biological tissue that would provide data necessary for the completion of the Site risk assessment. Surface water and sediment samples were collected along a suspected contamination gradient (based on XRF data) in the adjacent wetlands and submitted for Target Analyte List (TAL) metals analysis. The sediment samples were also submitted for toxicity evaluations. Analytical data from the Wolf River, a water body connected to the wetland system, was collected to assess potential risk to that system. Three locations were identified along the Wolf River, “upstream,” “midstream” and “downstream,” from which sediment samples were collected and submitted for TAL metals analysis. Site-specific tissue concentrations were also obtained for use in food chain modeling. Plant, grasshopper, and frog samples were collected and submitted for tissue analysis of TAL metals. These Site-specific tissue residue levels were used to predict the amount of contaminant transfer through trophic levels and subsequently, to the ecological functioning of the system.

Solid-phase toxicity evaluations were conducted to determine the effects of direct contact with Site

contaminants to aquatic organisms. The underlying premise of these toxicity evaluations was that the organism response can be associated with the contaminant levels determined by the chemical analyses. The endpoints for these evaluations were survival and growth (measured as body length for *H. azteca* and body weight for *C. tentans*). The methods used to conduct these studies are described in the final toxicological evaluation reports. In addition, measured concentrations of each contaminant of concern in surface water were compared to literature-based values on the toxicity to early life stages of amphibians. This provided a qualitative assessment of the risk of the Site contamination to amphibians.

Finally, the results of the analyses of water, sediment, and tissue (food items) were used in a food chain model to predict exposure dosages for each contaminant of concern to upper trophic levels. For the purposes of the model, it was assumed that the food of herbivorous species (meadow vole) comprised 100 percent soft rush, the food of insectivorous species (red-winged blackbird, short-tailed shrew) comprised 100 percent grasshoppers, and the food of carnivorous species (green heron, mink) comprised 100 percent green tree frogs, since these were the food items collected from the Site and analyzed. The resulting exposure dosages were divided by an effect concentration derived from the literature to provide a hazard quotient for each contaminant of concern and each receptor species.

#### **2.6.2.3 Ecological Effects Assessment**

A review of the wetland and surrounding habitats provided information for the selection of assessment endpoints. A variety of invertebrates, vertebrates, and plants inhabit the wetland. In addition, many birds and mammals from adjacent habitats could prey on the wetland flora and fauna. Therefore, the assessment endpoints will focus on these biological groups. The assessment endpoints relate specifically to viability of avian, mammalian, and wetland invertebrate, vertebrate and plant populations as well as organism survivability were selected as assessment endpoints for this risk assessment. Listed next and summarized in **Table 2-15** are the specific assessment endpoints selected followed by the supporting measurement endpoint:

**Table 2-15**  
**Ecological Exposure Pathways of Concern**

Exposure Media	Exposure Routes	Assessment Endpoints	Measurement Endpoints	Receptor	Endangered or Threatened Species
Sediment/Surface Water	Incidental sediment ingestion Direct contact with sediment Accumulation in forage Direct contact with surface water	Protection of benthic invertebrate community structure and function.	Toxicity of sediments to <i>Chironomus tentans</i> and <i>Hyalella azteca</i>	<i>Chironomus tentans</i> and <i>Hyalella azteca</i>	No
Sediment/Surface Water	Incidental sediment ingestion Direct contact with sediment Accumulation in forage Direct contact with surface water	Protection of amphibians from adverse effects on growth, survival, and/or reproductive success.	Comparisons with literature-based values on the toxicity of surface water concentrations to early life stages of amphibians	Green tree frog, <i>Hyla cinerea</i>	No
Soil/Sediment/Surface Water	Incidental soil/sediment ingestion Direct contact with soil/sediment Accumulation in forage Ingestion of surface water	Protection of insectivorous birds from adverse effects on growth, survival, and/or reproductive success.	Dietary exposure studies were selected to evaluate risk to insectivorous bird species that use the site.	Red-winged blackbird, <i>Agelaius phoeniceus</i>	No
Sediment/Surface Water	Incidental soil/sediment ingestion Direct contact with soil/sediment Accumulation in forage Ingestion of surface water	Protection of carnivorous birds from adverse effects on growth, survival, and/or reproductive success.	Dietary exposure studies were selected to evaluate risk to carnivorous bird species that use the site.	Green heron, <i>Butorides Striatus</i>	No
Soil/Sediment/Surface Water	Incidental soil/sediment ingestion Direct contact with soil/sediment Accumulation in plant forage Ingestion of surface water	Protection of herbivorous mammals from adverse effects on growth, survival, and/or reproductive success.	Dietary exposure studies were selected to evaluate risk to herbivorous mammals that use the site.	Meadow vole, <i>Microtus pennsylvanicus</i>	No
Soil/Sediment/Surface Water	Incidental soil/sediment ingestion Direct contact with soil/sediment Accumulation in forage Ingestion of surface water	Protection of insectivorous mammals from adverse effects on growth, survival, and/or reproductive success.	Dietary exposure studies were selected to evaluate risk to insectivorous mammals that use the site.	Short-tailed shrew, <i>Blarino breviceauda</i>	No
Soil/Sediment/Surface Water	Incidental soil/sediment ingestion Direct contact with soil/sediment Accumulation in forage Ingestion of surface water	Protection of carnivorous mammals from adverse effects on growth, survival, and/or reproductive success.	Dietary exposure studies were selected to evaluate risk to carnivorous mammals that use the site.	Mink, <i>Mustela vison</i>	No

- , Protection of benthic invertebrate community structure and function.

Toxicity evaluations using sediment and benthic invertebrate species were conducted to determine if contaminant levels in the sediment have an adverse effect on survival and growth, measured as body weight and body length. The midge, *Chironomus tentans*, and the amphipod, *Hyalella azteca*, were selected to represent benthic invertebrates.

- , Protection of amphibians from adverse effects on growth, survival, and/or reproductive success.

Comparisons with literature-based values on the toxicity of surface water concentrations to early life stages of amphibians were used to evaluate risk to amphibian species that use the Site. The green tree frog, *Hyla cinerea*, was selected to represent an amphibian.

- , Protection of insectivorous birds from adverse effects on growth, survival, and/or reproductive success.

Dietary exposure studies were selected to evaluate risk to insectivorous bird species that use the Site. The red-winged blackbird, *Agelaius phoeniceus*, was selected to represent an insectivorous bird. Appropriate food items were identified and a contaminant dose calculated based on the ingestion of contaminated prey (grasshoppers) and water.

- , Protection of carnivorous birds from adverse effects on growth, survival, and/or reproductive success.

Dietary exposure studies were selected to evaluate risk to carnivorous bird species that use the Site. The green heron, *Butorides striatus*, was selected to represent a carnivorous bird. Appropriate food items were identified and a contaminant dose calculated based on the ingestion of contaminated prey (frogs), sediment, and water.

- , Protection of herbivorous mammals from adverse effects on growth, survival, and/or reproductive success.

Dietary exposure studies were selected to evaluate risk to herbivorous mammal species that use the Site. The meadow vole, *Microtus pennsylvanicus*, was selected to represent a herbivorous mammal. Appropriate food items were identified and a contaminant dose calculated based on the ingestion of contaminated food (plants), sediment, and water.

- , Protection of insectivorous mammals from adverse effects on growth, survival, and/or reproductive success.

Dietary exposure studies were selected to evaluate risk to insectivorous mammals that use the Site. The short-tailed shrew, *Blarina brevicauda*, was selected to represent an insectivorous mammal. Appropriate food items were identified and a contaminant dose calculated based on the ingestion of contaminated prey (grasshoppers), sediment, and water.

- , Protection of carnivorous mammals from adverse effects on growth, survival, and/or reproductive success.

Dietary exposure studies were selected to evaluate risk to carnivorous mammals that use the Site. The mink, *Mustela vison*, was selected to represent a carnivorous




mammal. Appropriate food items were identified and a contaminant dose calculated based on the ingestion of contaminated prey (frogs), sediment, and water.

**Summary of Toxicity Tests:** The results of the 10-day sediment toxicity test using the amphipod, *Hyalella azteca*, are summarized in the Ecological Risk Assessment. Survival was significantly reduced in only the treatment for Location 3 (see **Figure 2-21**) when compared to both the laboratory control and Reference 1. There were no significant reductions in growth for any location compared to either Reference 1 or the laboratory control. Therefore, sediment from Location 3 was acutely toxic to *Hyalella*, but no chronic toxicity was detected in any of the locations. The final report for this test can be found in the Ecological Risk Assessment.

The results of the 10-day sediment toxicity test using the midge, *Chironomus tentans*, are summarized in the Ecological Risk Assessment. When compared to the reference, survival was significantly reduced only in the treatments for Location 3. When compared to the laboratory control, survival in the treatments for Locations 2, 3, and 12 were significantly reduced. Since this Risk Assessment is based on comparisons to the reference area, it can be concluded that only the sediment from Location 3 was acutely toxic to *Chironomus tentans*. The final reports for these tests can be found in the Ecological Risk Assessment.

**Summary of Food Chain Model Results:** The hazard quotient method (Barnthouse et al. 1986; U.S. EPA 1989) was employed to predict the effects of surface water and sediment contamination at the Site with regard to assessment endpoints. The hazard quotient method compares exposure concentrations to ecological endpoints such as reproductive failure or reduced growth. The comparisons are expressed as ratios of potential intake values to population effect levels. In addition, due to the magnitude of the concentrations of lead in sediment and water collected at the Ross Metals Site, an acute hazard quotient was also calculated for lead using an acute toxicity value. The effect level values are based on studies published in the literature. The exposure concentrations were



estimated by employing a food chain model for each receptor species. In these food chain models, ingestion rates of each contaminant of concern for each receptor species are determined based on known or estimated water, sediment, and food ingestion rates and body weights of each receptor species, as well as the measured concentrations of each contaminant in water, sediment, and food items collected at the Site. The exposure concentrations and toxicity values are entered into the hazard quotient equation, and a hazard quotient is calculated. If the hazard quotient for a particular contaminant is greater than one based on an acute value, this indicates that there is an acute risk from that contaminant to the ecological receptor in question. If the hazard quotient is greater than one based on a No Observed Adverse Effects Level (NOAEL), this indicates that there is a potential chronic risk from that contaminant to the ecological receptor in question. If the hazard quotient is greater than one based on a Lowest Observed Adverse Effects Level (LOAEL) for a particular contaminant, this indicates a more serious risk in that the Site levels of that contaminant have the potential to produce an actual adverse effect on survival, reproduction, or growth of the ecological receptor in question. The hazard quotient should be interpreted based on the severity of the effect reported.

In addition to determining whether each contaminant poses a risk to the selected assessment endpoints, preliminary ecotoxicologically-based remedial goals were established for those contaminants which were determined to be risks. These remedial goals are for sediment, and they are based on the premise that if the concentration of a contaminant is decreased in sediment, its concentration would subsequently decrease in surface water and biota. The characteristics of the Site were such that the surface water above the sediment was only a few centimeters deep. This would presumably allow for rapid equilibrium of contaminants between the sediment and water at the Site. Using these assumptions, a water:sediment contaminant ratio and a biota:sediment contaminant ratio were calculated for the Site based on mean concentrations of each contaminant at the Site. The sump area was excluded from the sediment denominator in the water:sediment and plant:sediment ratios, because no water or plant samples were collected from the sump area. The ratios were applied to the food chain model described previously, and the sediment concentration in the model was changed,

thus changing the water and biota concentrations according to the calculated ratios until the hazard quotient was just less than one. This calculation was performed for both the NOAEL and LOAEL values, thus providing a preliminary ecotoxicologically based remedial goal for each contaminant presenting a risk and for each assessment endpoint.

#### Results and Conclusions of the Acute Risk Characterization for Lead

The food chain model and acute hazard quotient calculations for lead and the five assessment endpoints evaluated using this model are presented in the Ecological Risk Assessment. Using the mean and maximum lead concentrations in sediment, no acute risk from lead to insectivorous birds, carnivorous birds, or carnivorous mammals was calculated. However, for insectivorous mammals, both the mean and maximum lead concentrations in sediment calculated an acute risk from lead. In addition, an acute risk to herbivorous mammals was calculated when the maximum lead concentration in sediment was used, but not when the mean concentration was used. These results indicate that an acute risk is posed to herbivorous and insectivorous mammals from the lead contamination at the Ross Metals Superfund Site.

When the sediment concentration of lead was adjusted so that the acute hazard quotient was just less than one, as described previously, a lead concentration of 9310 mg/kg in sediment was calculated for herbivorous mammals and 2160 mg/kg for insectivorous mammals. Therefore, a lead concentration of less than 2160 mg/kg in sediment at the Ross Metals Superfund Site is expected to be protective of an acute threat to the avian and mammalian receptors evaluated in this risk assessment.

#### Results and Conclusions of the Chronic Risk Characterization for Insectivorous Birds

The food chain model and chronic hazard quotient calculations for insectivorous birds are presented in the Ecological Risk Assessment. Using the maximum concentrations for each contaminant of concern and the NOAEL, it was determined that a potential risk is associated with lead at the Ross

Metals Superfund Site. Additionally, the mean contaminant concentrations and the NOAEL also calculated a potential risk from lead at the Site. When the maximum contaminant concentrations and the LOAEL were used in the model, a risk was still calculated from lead. However, when the mean contaminant concentrations and the LOAEL were used in the model, no risk was calculated from any contaminant.

When the sediment concentration of lead was adjusted so that the hazard quotient was just less than one, as described previously, a NOAEL of 933 mg/kg and a LOAEL of 9330 mg/kg were determined. Therefore, a preliminary ecotoxicologically-based target remedial goal of 933 mg/kg - 9330 mg/kg for lead in sediment was determined for the protection of insectivorous birds.

#### Results and Conclusions of the Chronic Risk Characterization for Carnivorous Birds

The food chain model and chronic hazard quotient calculations for carnivorous birds are presented in the Ecological Risk Assessment. Using the maximum concentrations for each contaminant of concern and the NOAEL, it was determined that lead poses a potential risk at the Ross Metals Superfund Site. The mean contaminant concentrations and the NOAEL also calculated a potential risk from lead at the Site. When both the maximum and the mean contaminant concentrations were used with the LOAEL in the model, a risk was still calculated from lead.

When the sediment concentration of lead was adjusted so that the hazard quotient was just less than one, as described previously, a NOAEL of 133 mg/kg and a LOAEL of 1330 mg/kg were determined. Therefore, a preliminary ecotoxicologically-based remedial goal of 133 mg/kg - 1330 mg/kg for lead in sediment was determined for the protection of carnivorous birds.

#### Results and Conclusions of the Chronic Risk Characterization for Herbivorous Mammals

The food chain model and chronic hazard quotient calculations for herbivorous mammals are

presented in the Ecological Risk Assessment. Using the maximum concentrations for each contaminant of concern and the NOAEL, it was determined that aluminum, arsenic, cadmium, lead, and nickel pose a potential risk at the Ross Metals Superfund Site. When the mean contaminant concentrations and the NOAEL were used in the model, no risk from nickel was calculated, but a potential risk was still calculated from aluminum, arsenic, cadmium, and lead. When the maximum contaminant concentrations and the LOAEL were used in the model, a risk was still calculated from aluminum, arsenic, cadmium, and lead. When the mean contaminant concentrations and the LOAEL were used in the model, no risk was calculated from arsenic or cadmium, but a risk was still evident from aluminum and lead.

When the sediment concentration of aluminum was adjusted so that the hazard quotient was just less than one, as described previously, a NOAEL of 123 mg/kg and a LOAEL of 1230 mg/kg were determined. Therefore, a preliminary ecotoxicologically-based remedial goal of 123 mg/kg - 1230 mg/kg for aluminum in sediment was determined for the protection of herbivorous mammals.

When the sediment concentration of arsenic was adjusted so that the hazard quotient was just less than one, as described previously, a NOAEL of 0.16 mg/kg and a LOAEL of 1.6 mg/kg in sediment were established. Therefore, a preliminary ecotoxicologically-based remedial goal of 0.16 mg/kg - 1.6 mg/kg for arsenic in sediment was determined for the protection of herbivorous mammals.

When the sediment concentration of cadmium was adjusted so that the hazard quotient was just less than one, as described previously, a NOAEL of 0.25 mg/kg and a LOAEL of 2.5 mg/kg in sediment were established. Therefore, a preliminary ecotoxicologically-based remedial goal of 0.25 mg/kg - 2.5 mg/kg for cadmium in sediment was determined for the protection of herbivorous mammals.

When the sediment concentration of lead was adjusted so that the hazard quotient was just less than one, as described previously, a NOAEL of 556 mg/kg and a LOAEL of 5560 mg/kg were determined. Therefore, a preliminary ecotoxicologically-based remedial goal of 556 mg/kg - 5560 mg/kg for lead

in sediment was determined for the protection of herbivorous mammals.

When the sediment concentration of nickel was adjusted so that the hazard quotient was just less than one, as described previously, a NOAEL of 1.5 mg/kg in sediment was established. A LOAEL for nickel in sediment was not determined because when the mean and maximum nickel concentrations and a LOAEL were used in the original model, no risk was established. Therefore, the preliminary ecotoxicologically-based remedial goal is an unbounded NOAEL of 1.5 mg/kg of nickel in sediment for the protection of herbivorous mammals.

#### Results and Conclusion Of the Chronic Risk Characterization for Insectivorous Mammals

The food chain model and chronic hazard quotient calculations for insectivorous mammals are presented in the Ecological Risk Assessment. Using the maximum concentrations for each contaminant of concern and the NOAEL, it was determined that aluminum, arsenic, cadmium, lead, and nickel pose a potential risk at the Ross Metals Superfund Site. When the mean contaminant concentrations and the NOAEL were used in the model, no risk from cadmium or nickel was calculated, but a potential risk from aluminum, arsenic, and lead was still evident. When both the mean and maximum contaminant concentrations and the LOAEL were used in the model, a risk was still evident from aluminum, arsenic, and lead.

When the sediment concentration of aluminum was adjusted so that the hazard quotient was just less than one, as described previously, a NOAEL of 53.3 mg/kg and a LOAEL of 533 mg/kg were determined. Therefore, a preliminary ecotoxicologically-based remedial goal of 53.3 mg/kg - 533 mg/kg for aluminum in sediment was determined for the protection of insectivorous mammals.

When the sediment concentration of arsenic was adjusted so that the hazard quotient was just less than one, as described previously, a NOAEL of 0.14 mg/kg and a LOAEL of 1.4 mg/kg were determined. Therefore, a preliminary ecotoxicologically-based remedial goal of 0.14 mg/kg - 1.4

mg/kg for arsenic in sediment was determined for the protection of insectivorous mammals.

When the sediment concentration of cadmium was adjusted so that the hazard quotient was just less than one, as described previously, a NOAEL of 0.46 mg/kg in sediment was established. A LOAEL for cadmium in sediment was not determined because when both the mean and maximum cadmium concentrations and a LOAEL were used in the original model, no risk was established. Therefore, the preliminary ecotoxicologically-based remedial goal is an unbounded NOAEL of 0.46 mg/kg of cadmium in sediment for the protection of insectivorous mammals.

When the sediment concentration of lead was adjusted so that the hazard quotient was just less than one, as described previously, a NOAEL of 129 mg/kg and a LOAEL of 1290 mg/kg were determined. Therefore, a preliminary ecotoxicologically-based remedial goal of 129 mg/kg - 1290 mg/kg for lead in sediment was determined for the protection of insectivorous mammals.

When the sediment concentration of nickel was adjusted so that the hazard quotient was just less than one, as described previously, a NOAEL of 1.40 mg/kg in sediment was established. A LOAEL for nickel in sediment was not determined because when the mean and maximum nickel concentrations and a LOAEL were used in the original model, no risk was established. Therefore, the preliminary ecotoxicologically-based remedial goal is an unbounded NOAEL of 1.40 mg/kg of nickel in sediment for the protection of insectivorous mammals.

#### Results and Conclusions of the Chronic Risk Characterization for Carnivorous Mammals

The food chain model and chronic hazard quotient calculations for carnivorous mammals are presented in the Ecological Risk Assessment. Using the maximum concentrations for each contaminant of concern and the NOAEL, it was determined that aluminum, arsenic, and lead pose a potential risk at the Ross Metals Superfund Site. When the mean contaminant concentrations and the NOAEL were used in the model, a potential risk was still calculated from aluminum, arsenic, and



lead. When the maximum contaminant concentrations and the LOAEL were used in the model, a risk was still calculated from arsenic and lead. When the mean and LOAEL were used, no risk to carnivorous mammals was evident from any of the contaminants.

When the sediment concentration of aluminum was adjusted so that the hazard quotient was just less than one, as described previously, a NOAEL of 321 mg/kg in sediment was established. A LOAEL for aluminum in sediment was not determined because when the mean and maximum aluminum concentrations and a LOAEL were used in the original model, no risk was established. Therefore, the preliminary ecotoxicologically-based remedial goal is an unbounded NOAEL of 321 mg/kg of aluminum in sediment for the protection of carnivorous mammals.

When the sediment concentration of arsenic was adjusted so that the hazard quotient was just less than one, as described previously, a NOAEL of 0.31 mg/kg and a LOAEL of 3.1 mg/kg in sediment were established. Therefore, the preliminary ecotoxicologically-based remedial goal of 0.31 - 3.1 mg/kg of arsenic in sediment was determined for the protection of carnivorous mammals.

When the sediment concentration of lead was adjusted so that the hazard quotient was just less than one, as described previously, a NOAEL of 4490 mg/kg and a LOAEL of 44,900 mg/kg in sediment were established. Therefore, the preliminary ecotoxicologically-based remedial goal for lead in sediment is 4490 - 44,900 mg/kg for the protection of carnivorous mammals.

#### **2.6.2.4 Conclusions**

The results of the analyses of the samples collected at the Site indicated that it has been heavily contaminated with metals. Contamination extends both north and east of the Site and into the adjacent wetlands. Of all the metals calculated to pose a potential risk, lead was determined to pose the highest risk to ecological receptors. It was also determined that organic contaminants are present at the Site; however, the magnitude and extent of this contamination remains uncertain because of

the small sample size. Site-related contaminants have not been detected in the Wolf River.

The following sections present the conclusions that were drawn regarding the viability of avian, mammalian, and wetland invertebrate, vertebrate and plant populations, as well as organism survivability. NOAEL and LOAEL ranges for each receptor group are presented in **Table 2-16**.

## **2.7 REMEDIATION OBJECTIVES**

### **2.7.1 Remedial Goals**

For the protection of human health and ecological receptors, those COCs that are related to past operations at the facility have been considered in the development of a soil/sediment remedial alternative. These COCs include aluminum, antimony, arsenic, barium, cadmium, copper, iron, lead, manganese, selenium, and vanadium. For ecological receptors, COCs include aluminum antimony, arsenic, cadmium, copper, iron, lead, mercury, nickel and zinc.

Development of a remedial effort specifically for contaminated surface water is not recommended if the contaminant source is remediated. That is, if contaminated sediments are removed, surface water would be remediated. Surface water quality could be monitored to determine the effectiveness of the contaminant source remediation.

The geochemical model mention previously in Section 2.5.7.4 indicated that removal of lead to 100 ppm left a residual soil lead concentration of 31.71 ppm, which is near background levels. It predicts that removal of 100ppm. would be protective or groundwater for at least 90 years. However, the conservative nature of this number, along with the uncertainty surrounding the modeling effort, make it inappropriate to use as a subsurface soil cleanup goal.

The 100 ppm. goal is based on the assumption of a 5,000 ppm. surface load factor. However, the

<p align="center"><b>Table 2-16</b>  <b>COC Concentrations Expected to Provide Adequate Protection of Ecological Receptors</b></p>						
Habitat Type	Exposure Medium	COC	Protective Level Range	Units	Basis	Assessment Endpoint
Wetland/Creek	Sediment	Antimony Arsenic Cadmium Copper Lead Mercury	19-70 10-45 3.2-3.3 15-68 2,790-13,098 <0.14	mg/kg, ww	Site specific NOAEL to LOAEL range	Protection of benthic invertebrate community structure and function.
Wetland/Soils	Soil/Sediment	Lead	933-9330	mg/kg, ww	Site Specific NOAEL to LOAEL range	Protection of insectivorous birds from adverse effects on growth, survival, and/or reproductive success.
Wetlands/Soils	Soil/Sediment	Lead	133-1330	mg/kg, ww	Site specific NOAEL to LOAEL range	Protection of carnivorous birds from adverse effects on growth, survival, and/or reproductive success.
Wetlands/Soils	Soil/Sediment	Aluminum Arsenic Cadmium Lead Nickel	123-1230 0.16-1.6 0.25-2.5 556-5560 >1.5	mg/kg, ww	Site specific NOAEL to LOAEL range	Protection of herbivorous mammals from adverse effects on growth, survival, and/or reproductive success.
Wetlands/Soils	Soil/Sediment	Aluminum Arsenic Cadmium Lead Nickel	53.3-533 0.14-1.4 >0.46 129-1290 >1.4	mg/kg, ww	Site specific NOAEL to LOAEL range	Protection of insectivorous mammals from adverse effects on growth, survival, and/or reproductive success.
Wetlands/Soils	Soil/Sediment	Aluminum Arsenic Lead	>321 0.31-3.1 4490-44,900	mg/kg, ww	Site specific NOAEL to LOAEL range	Protection of carnivorous mammals from adverse effects on growth, survival, and/or reproductive success
Wetland/Creek	Surface Water	Aluminum Arsenic Cadmium Copper Iron Lead Zinc	50 40 30 40 30,000 40 10	ug/L	Literature based toxicity information	Protection of amphibians from adverse effects on growth, survival, and/or reproductive success.

Footnote: The units represent wet weight (ww). To convert to dry weight, a mean percent concentration (33%) should be used.

establishment of a 400 ppm risk-based surface soil clean-up goal would mean surface soil concentrations no greater than 400 ppm. With a surface soil concentration of 400 ppm and considering the nature of the contamination, clean up of surface soils to 400 ppm in the area of the wrecker building and truck wash should allow for the protection of groundwater.

**Table 2-17** presents the risk-based (human health and ecological) remedial goals for surface soil, subsurface soil, and sediment.

### **2.7.2 Remedial Action Objectives**

The remedial action objectives (RAOs) for the Ross Metals Site are as follows:

#### ***Soil***

- prevent ingestion, inhalation, or direct contact with surface soil that contain concentrations in excess of the Remedial Goals (RGs);
- prevent further migration and leaching of contaminants in surface and subsurface soil to groundwater that could result in groundwater contamination in excess of MCLs;
- prevent further migration of contaminants in surface soil/sediment to surface water that could result in groundwater contamination in excess of MCLs;
- prevent ingestion or inhalation of soil that contain concentrations in excess of the RGs;

<b>Table 2-17</b> <b>Remedial Goals</b>		
<b>Contaminant of Concern</b>	<b>Remedial Goals</b>	<b>Basis</b>
<i>Surface Soil (mg/kg)</i>		
Aluminum	11,620	Avg. Background Concentration
Antimony	3	Hazard Quotient Level = 0.1
Arsenic	5	Avg. Background Concentration
Barium	505	Hazard Quotient Level = 0.1
Cadmium	7	Hazard Quotient Level = 0.1
Copper	293	Hazard Quotient Level = 0.1
Iron	16,100	Avg. Background Concentration
Lead	400	Protection of Human Health
Manganese	559	Avg. Background Concentration
Selenium	37	Hazard Quotient Level = 0.1
Vanadium	51	Hazard Quotient Level = 0.1
<i>Subsurface Soil (mg/kg)</i>		
Lead	400	Protection of groundwater
<i>Wetlands Sediment (mg/kg)</i>		
Aluminum	8,860	Avg. Background Concentration
Antimony	28.4 - 104	Protection of Ecological Receptors
Arsenic	5.58	Avg. Background Concentration
Cadmium	0.37 - 3.73	Protection of Ecological Receptors
Copper	22.4 - 101.5	Protection of Ecological Receptors
Lead	192 - 1,925	Protection of Ecological Receptors
Mercury	ND - 0.21	Protection of Ecological Receptors
Nickel	9.10	Avg. Background Concentration

Footnote: Values for protection of ecological receptors were obtained by using a mean percent moisture concentration (33%) to convert NOAEL/LOAEL ranges (wet weight basis) to a dry weight range.

ND - Not Detected

### ***Wetlands***

- reduce potential for exposure of contaminated sediments/soils and surface waters to ecological receptors;
- prevent transport and migration of Site contaminants to the adjacent uncontaminated wetlands and the Wolf River,
- restore impacted wetland communities; and
- prevent further degradation of the wetlands and the adjacent areas.

### **2.7.3 Extent of Source Material Contamination Above Remedial Goals**

To facilitate the evaluation of potentially applicable removal action alternatives for the Site, solid media waste can be divided into four general categories based on physical and chemical characteristics:

- Waste slag (landfilled and stockpiled on Site)
- Contaminated soil (in old fenced area and landfill area)
- Building ruins
- Demolition debris (pavement)
- Contaminated sediment (in wetlands)

Results from previous investigations suggest that lead will be the “driver” in any remediation effort conducted at the Site. The presence of lead is sufficiently widespread that gearing a remediation effort to lead will also remediate other COC contamination, meaning that the extent of lead contamination serves as a good indicator of the extent of all the COC contamination at the RM Site. In addition, the ecological risk assessment concluded that of all the metals calculated to pose a

potential risk, lead was determined to pose the highest risk to the ecological receptors at the Site.

### ***Contaminated Solid Media in Old Fenced Area and Landfill***

Based on excavations performed in the landfill at the north end of the Site in November 1996, an estimated 10,000 CY of buried landfill slag is present on Site. In addition, several stockpiles of waste slag are located in various on-Site buildings (see Figure 2-2). The building labeled “furnace and raw materials refinery” contains two waste slag stockpiles totaling about 700 CY. The buildings labeled “wrecker,” “slag fixation,” and “shipment” contain waste slag stockpiles of about 2,600; 700; and 2,000 CY, respectively. The total combined volume of the stockpiled waste slag is about 6,000 CY.

Lead-contaminated surface and subsurface soil is present in the landfill at depths of up to 5.5 feet bgs. Lead-contaminated surface soil is present throughout the fenced portion of the Site at depths of up to 1.5 feet beneath the pavement. Based on an area of 450 by 525 feet, the volume of waste soil is estimated as 13,125 CY.

Lead-contaminated subsurface soil was noted along the eastern edge of the wrecker building at depths up to 40 inches bgs. Lead-contaminated subsurface soil was also noted near the southeastern corner of the truck wash. Based on two 125-ft-square areas at depths from 1.5 to 3 feet, the volume of contaminated subsurface soil is estimated as 2,500 CY. Figures 7-1 and 7-2 indicate the extent of lead contamination in Site soils.

The deteriorating buildings are located within the fenced portion of the Site. The largest of the buildings is a sheet metal building labeled “furnace and raw materials refinery;” the building is roughly 25 to 30 feet high, 180 feet long, and 100 feet wide. After demolition and compaction, the combined volume of the building debris is not expected to exceed 27,000 cubic feet (CF) (1,000 CY). The buildings are in poor condition and constitute a safety hazard.

Additional demolition debris may be generated at the Site depending on the remedial action selected. About 20,000 square yards (SY) of asphalt and concrete pavement are located within the fenced portion of the Site. An 8-inch-thick concrete pad located within the landfill area covers about 1,333 SY. Therefore, the total area of pavement at the Site is about 21,333 SY (including asphalt and concrete). The volume of concrete and asphalt estimated for disposal is 3,700 CY.


Based on the estimated volumes of the landfilled and stockpiled slag, the total volume of slag is estimated to be about 16,000 CY.


### ***Contaminated Sediment in Wetlands***

In December 1997, EPA ERTC conducted sediment sampling to determine the extent of lead contamination in the wetland area adjacent to the old fenced area and landfill. Samples were collected from 0 to 6 inches in depth and analyzed at the Site by field portable X-ray fluorescence (XRF) to determine the extent of lead contamination above. Because RGOs based on protection of ecological receptors are presented as ranges, an acceptable goal within the range must be selected in order to calculate the volume of contaminated sediment in the wetlands. Because lead, as previously indicated, is so widespread and presents the highest risk to ecological receptors; a cleanup goal established for it that takes into account impact to wetlands, should also ensure cleanup of other COCs to acceptable levels. To determine an acceptable goal, a chart plotting cleanup goals versus area of wetlands to be excavated to obtain the cleanup goal was created and is shown in **Figure 2-22**. Figure 2-22 suggests that 800 mg/kg would be the most effective cleanup goal causing the least disturbance to the wetlands. Based on the XRF results, there are approximately 5.7 acres of material contaminated above 800 mg/kg lead. **Figure 2-23** illustrates the contaminated wetlands.



**Figure 2-22**  
**Cleanup Goals v. Excavation Required**





Ross Metals Site Rossville, Tennessee CDM Federal Programs Corporation 10000 Old Hickory Road Nashville, Tennessee 37204	Contaminant Contour in Wetlands March 1998	Figure No. 2-23 8/98
--	--	----------------------------

### *Summary of Contaminated Solid Media*

The total estimated volume of contaminated solid media includes the following components:

- Waste Slag

Landfill:	10,000 CY
Surface Slag:	6,000 CY

- Lead-contaminated Surface Soil (volume includes areas contaminated with other COCs)

Wetlands (sediment):	9,300 CY (at 800 ppm level)
Old Facility Fenced Area:	13,125 CY (at 400 ppm level)
Landfill Area:	8,750 CY (at 400 ppm level)

- Lead-contaminated Subsurface Soil 2,500 CY (at 400 ppm level)
- Lead-contaminated Buildings 1,000 CY (at 10 ug/dl level)
- Demolition Debris 3,700 CY

The contaminated solid media at the RM Site can be considered source material because it includes or contains hazardous substances, pollutants or contaminants that act as a reservoir for migration of contamination to groundwater, to surface water, to air, or acts as a source for direct exposure. Because the contaminated solid media is considered source material, the concept of principal threat and low level threat wastes should be applied to the RM Site.

Principal threat wastes are those source materials considered to be highly toxic or highly mobile that cannot be reliably contained or would present a significant risk to human health or the environment should exposure occur. Although no “threshold level” of risk has been established to identify principal threat waste, source materials with toxicity and mobility characteristics that pose a potential risk several orders of magnitude greater than the acceptable risk level for current or future land use can be considered principal threat wastes. For the RM Site, this would conservatively encompass solid

media with lead concentrations ranging from 40,000 ppm, since the RGO for lead is 400 ppm in soil, and wetland sediment with lead concentrations ranging from 1,900 mg/kg upward since acute risk occurs at the LOAEL which is equal to 1,920 mg/kg.

Low level threat wastes are those source materials that generally can be reliably contained and that would present only a low risk in the event of a release. They include source materials that exhibit low toxicity, low mobility in the environment, or are near health-based levels.

The identification of principal threat and low level threat wastes is important because their presence influences the development of appropriate remedial alternatives. Although exceptions apply, EPA generally expects to use treatment to address the principal threats posed by a Site, wherever practicable. On the other hand, the use of institutional controls, such as containment, is expected for wastes that pose a relatively low long-term threat or where treatment is impracticable (EPA 1991).

A review of the sampling results suggests that some of the contaminated solid media present at the RM Site can be considered principal threat waste based on the lead concentrations present. Waste sample SL-01 and Site surface soil samples T4-LF/B12, 008SLA, and 013SLA all had lead concentrations greater than 40,000 ppm. In addition, the soil associated with sample 020SLA could be considered principal threat waste based on an arsenic concentration of 40 ppm.

Assuming an excavation depth of 1.5 ft bgs with a 50 foot x 50 foot excavation grid centered on each of the Site soil samples exceeding 40,000 ppm lead, and each of the wetland sediment samples exceeding 1,900 ppm lead, results in a volume of approximately 600 CY of contaminated soil and 8,200 CY of wetland sediment. Adding the 6,000 CY of stockpiled slag to this volume (based on the results of waste sample WS-01), and the 10,000 CY of landfilled slag (based on similarity to the stockpiled slag) results in a total volume of approximately 24,800 CY of the 53,275 CY of total contaminated solid media that could be considered principal threat waste.

## **2.8 DESCRIPTION OF SOURCE MATERIAL ALTERNATIVES**

A summary of source material alternatives is provided in **Table 2-18**.

### **2.8.1 Alternative S-1 -- No Action**

#### **2.8.1.1 Description**

Under this alternative, no action would be taken to remedy the contaminated surface soil, slag, sediment, or other solid media at the Site. The alternative would only involve the continued monitoring of structures, surface soil, slag, sediment, and surface water quality at the Site. Approximately five wipe samples (from buildings) and ten surface soil and fifteen surface water/sediment samples would be collected from the affected areas and analyzed for the PCOCs found in each medium every five years for 30 years. Public health evaluations would be conducted every five years and would allow EPA to assess the ongoing risks to human health and the environment posed by the RM Site. The evaluations would be based on the data collected from media monitoring.

#### **2.8.1.2 Overall Protection of Human Health and the Environment**

The no action alternative does not eliminate any exposure pathways or reduce the level of risk of the existing soil contamination.

**Table 2-18**  
**Summary of Soil Alternatives Evaluation**

Remedial Alternative	Threshold Criteria		Balancing Criteria					
	Overall Protection of Human Health and the Environment	Compliance with ARARs	Long-Term Effectiveness and Permanence	Reduction of M/T/V Through Treatment	Short-Term Effectiveness	Implementability		Cost Approx. Total Present Worth
						Technical/Engineering Considerations	Estimated Time for Implementation (years)	
1 - No Action	Does not eliminate exposure pathways or reduce the level of risk. Does not limit migration of or remove contaminants.	Chemical-specific ARARs are not met. Location- and action-specific ARARs do not apply.	The contaminated material is a long-term impact. The remediation goals are not met.	No reduction of M/T/V is realized.	Level D protective equipment is required during sampling.	None	<1	\$100,247
2 - Capping	Eliminates exposure pathways and reduces the level of risk. Isolates contamination and minimizes further migration.	All action-specific ARARs are expected to be met. Location-specific ARARs are applicable and would need to be met.	Long-term public health threats associated with surface soil and sediment are greatly reduced. No residual risks from the alternative. Long-term effectiveness requires cap maintenance.	Reduction of mobility is realized but contaminant volume or toxicity are not reduced. For the principle threat waste at the Site, does not meet EPA's expectation to treat principle threat waste.	Level C and D protective equipment required during Site activities. Excavating and grading may result in potential release of dust. Noise nuisance from use of heavy equipment.	Capping in a floodplain.	<1	Opt. 1-\$1,735,804 Opt. 2-\$1,712,412
3 - Capping With Pavement In Place	Eliminates exposure pathways and reduces the level of risk. Isolates contamination and minimizes further migration.	All action-specific ARARs are expected to be met. Location-specific ARARs are applicable and would need to be met.	Long-term public health threats associated with surface soil and sediment are greatly reduced. No remedial risks from the alternative. Long-term effectiveness requires cap maintenance.	Reduction of mobility is realized but contaminant volume or toxicity are not reduced. For the principle threat waste at the Site, does not meet EPA's expectation to treat principle threat waste.	Level C and D protective equipment required during Site activities. Excavating and grading may result in potential release of dust. Noise nuisance from use of heavy equipment.	Capping in a floodplain.	<1	Opt. 1-\$1,453,803 Opt. 2-\$1,430,411
4 - Capping With Construction of Above-Ground Disposal Cell	Eliminates exposure pathways and reduces the level of risk. Isolates contamination and minimizes further migration.	All action-specific ARARs are expected to be met. Location-specific ARARs are applicable and would need to be met.	Long-term public health threats associated with surface soil and sediment are greatly reduced. No residual risks from the alternative. Long-term effectiveness requires cap maintenance.	Reduction of mobility is realized but contaminant volume or toxicity are not reduced. For the principle threat waste at the Site, does not meet EPA's expectation to treat principle threat waste.	Level C and D protective equipment required during Site activities. Excavating and grading may result in potential release of dust. Noise nuisance from use of heavy equipment.	Capping in a floodplain.	<1	Opt. 1-\$1,506,847 Opt. 2-\$1,481,865

Note: Option 1 includes excavated wetland sediment; Option 2 does not.

Table 2-18 (cont)

Remedial Alternative	Threshold Criteria		Balancing Criteria					
	Overall Protection of Human Health and the Environment	Compliance with ARARs	Long-Term Effectiveness and Permanence	Reduction of M/T/V Through Treatment	Short-Term Effectiveness	Implementability		Cost Approx. Total Present Worth
						Technical/Engineering Considerations	Estimated Time for Implementation (years)	
5A - Excavation and Onsite Treatment With Solidification/Stabilization and Onsite Disposal	Eliminates exposure pathways and reduces the level of risk immobilizes contamination and eliminates further migration.	Chemical-specific ARARs are met. Location- and action-specific ARARs are applicable and would need to be met.	Long-term public health threats associated with surface soil and sediment are eliminated. No residual risks from the alternative. Requires effective cap maintenance.	Mobility and toxicity are reduced, however, treatment process will increase volume. Meets EPA expectation to treat principle threat waste, but also treats (rather than contains) low-level threat wastes.	Level C and D protective equipment required during Site activities. Excavating and grading may result in potential release of dust. Noise nuisance from use of heavy equipment.	Capping in a floodplain.	<1	Opt. 1-\$4,907,274 Opt. 2-\$4,244,992
5B - Excavation and Onsite Treatment with Solidification/Stabilization and Offsite Disposal	Eliminates exposure pathways and greatly reduces the level of risk. Removes contamination and mitigates further migration.	ARARs are met through onsite treatment and offsite disposal.	Long-term public health threats associated with surface soil and sediment are eliminated. No residual risks from the alternative.	Mobility and toxicity are reduced, however, treatment process will increase volume. Meets EPA expectation to treat principle threat waste, but also treats (rather than contains) low-level threat wastes.	Level C and D protective equipment required during Site activities. Excavating and grading may result in potential release of dust. Noise nuisance from use of heavy equipment.	None	<1	Opt. 1-\$7,477,199 Opt. 2-\$6,181,160
6A - Capping With Excavation and Onsite Treatment And Disposal Of Principle-Threat Waste	Eliminates exposure pathways and greatly reduces the level of risk. Removes contamination and mitigates further migration.	Chemical-specific ARARs are met. Location- and action-specific ARARs are applicable and would need to be met.	Long-term public health threats associated with surface soil and sediment are eliminated. No residual risks from the alternative. Requires effective cap maintenance.	Mobility and toxicity are reduced, however, treatment process will increase volume. Meets EPA expectation to treat principle-threat waste and contain low-level threat waste.	Level C and D protective equipment required during Site activities. Excavating and grading may result in potential release of dust. Noise nuisance from use of heavy equipment.	Capping in a floodplain.	<1	Opt. 1-\$3,175,137 Opt. 2-\$2,729,543
6B - Capping With Excavation and Onsite Treatment And Offsite Disposal Of Treated Principle-Threat Waste	Eliminates exposure pathways and greatly reduces the level of risk. Removes contamination and migrates further migration.	Chemical-specific ARARs are met. Location- and action-specific ARARs are applicable and would need to be met.	Long-term public health threats associated with surface soil and sediment are eliminated. No residual risks from the alternative. Requires effective cap maintenance.	Mobility and toxicity are reduced, however, treatment process will increase volume. Meets EPA expectation to treat principle-threat waste and contain low-level threat waste.	Level C and D protective equipment required during Site activities. Excavating and grading may result in potential release of dust. Noise nuisance from use of heavy equipment.	Capping in a floodplain.	<1	Opt. 1-\$4,936,044 Opt. 2-\$4,013,508

Note: Option 1 includes excavated wetland sediment; Option 2 does not.

### **2.8.1.3 Compliance with ARARs**

This alternative does not achieve the RAOs or chemical-specific ARARs established for surface soil. Location- and action-specific ARARs do not apply to this alternative since further remedial actions will not be conducted.

### **2.8.1.4 Long-Term Effectiveness and Permanence**

The remediation goals derived for protection of human health and the environment would not be met. Because contaminated soil remains under this alternative, a review/reassessment of the conditions at the Site would be performed at 5-year intervals to ensure that the remedy does not become a greater risk to human health and the environment.

### **2.8.1.5 Reduction of M/T/V Through Treatment**

No reductions in contaminants M/T/V are realized under this alternative.

### **2.8.1.6 Short-Term Effectiveness**

Since no further remedial action would be implemented at this Site, this alternative poses no short-term risks to onsite workers. It is assumed that Level D personnel protection would be used when sampling various media.

### **2.8.1.7 Implementability**

This alternative could be implemented immediately since monitoring equipment is readily available and procedures are in place.



#### **2.8.1.8 Cost**

Minimal costs are associated with this alternative compared to other remedial action alternatives. No capital costs are associated with this alternative. The estimated O&M costs for media sampling associated with monitoring are approximately \$100,247.

### **2.8.2 Alternative S-2 -- Capping**

#### **2.8.2.1 Description**

Capping the contaminated solid media at the RM Site would serve to prevent rainfall infiltration and future leaching into the groundwater. In addition, capping also would limit direct contact exposure to contaminated media under the cap. Varying degrees of capping can be implemented depending on the severity of contaminants in the area. Caps can range from a simple natural soil cap to a multilayer soil/synthetic cap. This alternative evaluates a geosynthetic cap for implementation. This type of cap would produce a low permeability barrier sufficient to reduce contaminant migration.

This alternative includes the demolition of most of the on-Site pavement and buildings. The main office building and the pavement immediately surrounding this building would remain on Site, and landfilled slag would remain in place. Contaminated soil beneath the pavement would be excavated up to a 3 ft maximum depth and consolidated with the stockpiled slag, pavement, and building debris. This waste material would be disposed in an on-Site excavation that would extend from the existing landfill to about 375 feet south of the landfill. This disposal area would be about 400 feet wide and 8 feet deep, although could be enlarged somewhat if necessary. A geosynthetic cap and underlying 1.5-ft soil cushion layer would be added above the waste and existing landfill to cover about 6.7 acres. A 1.2-ft soil cover and 6-inch topsoil layer would be placed over the entire Site. These components are outlined as follows:

- Demolition of pavement and buildings;
- Excavation of onsite contaminated soil (15,625 CY);
- Excavation of an on-Site disposal area (375 ft long by 400 ft wide by 8 ft deep; approximately 36,200 CY subsurface soil);
- Compaction of 26,325 CY of waste material (15,625 CY of waste soil; 6,000 CY of stockpiled slag; 3,700 CY of pavement; and 1,000 CY of building debris ) into disposal area (Compaction of 35,625 CY of waste material if excavated wetland sediment is consolidated with surface soil for final disposition);
- Installation of 1.5-ft-deep soil cushion over the waste and existing landfill (20,300 CY);
- Installation of geomembrane liner and geotextile over soil cushion (6.7 acres);
- Soil cover (1.2 ft deep), topsoil cover (6 inches deep), and grass seeding over the Site (8 acres); and
- Land/deed use restrictions and fencing.

The topsoil layer of the cap would be graded to a minimum slope of 3% and a maximum of 5% to promote surface drainage away from the waste cell and reduce infiltration. Surface drainage controls would be constructed around the perimeter of the cap to collect surface water runoff.


Alternative S-2 would eliminate direct contact with contaminated media, eliminate on-Site physical hazards, minimize contaminant migration to groundwater, and eliminate contaminant migration to surface water from the Site. **Figure 2-24** illustrates the components of the cap included in this alternative as they would be applied to the RM Site.

#### **2.8.2.2 Overall Protection of Human Health and the Environment**

Successful implementation of this, alternative would reduce risks to human health and the environment and meet the removal action objectives by (1) eliminating exposure of residents and trespassers to

SOUTH

NORTH



APPROXIMATE DIMENSIONS OF EXCAVATION: TOTAL DEPTH - 8 FT.  
LENGTH - 175 FT.  
WIDTH - 400 FT.

NOT TO SCALE

Ross Metals Site  
Rossville, Tennessee

CDM Federal Programs Corporation  
*A subsidiary of Camp Dresser & McKee Inc.*

Figure No.  
2-24

Alternative 2 - Capping

8/98

NOTE: Conceptual design. Federal, state, and local requirements regarding construction in a floodplain must be considered and may affect design. Representation of waste material includes excavated wetland sediments.

waste material by direct contact and airborne migration, (2) eliminating exposure of trespassers to direct contact with on-Site physical hazards, and (3) minimizing the migration of contaminants to groundwater and eliminating the migration of contaminants to surface water. Consolidation and isolation of the waste material beneath a geomembrane cap would eliminate receptor routes of exposure through ingestion and inhalation. Structures throughout the Site would be demolished and disposed of in an excavated disposal area beneath the existing pavement. As a result, physical hazards associated with deteriorating structures would be eliminated. In addition, geomembrane capping would eliminate infiltration of precipitation and surface water that contributes to the migration of contaminants to groundwater. However, because the waste material will remain on Site, contaminant migration to groundwater cannot be discounted as an adverse effect. Nevertheless, the elimination of surface water infiltration makes this scenario unlikely, and contaminant migration through surface water runoff to the adjacent wetlands and the Wolf River would be eliminated.

The threat of direct human exposure to contaminated waste and physical hazards would be practically eliminated by this alternative; however, the threat could return over the long term if cap integrity was compromised. The potential for ingestion, dermal contact, and inhalation of soil containing metals would be eliminated by successfully placing the geomembrane cap over the waste material.

### **2.8.2.3 Compliance with ARARs**

The RCRA hazardous waste disposal facility requirements are potentially applicable. The RM Site is located in a 100-year floodplain within a zone designated as A3, indicating that base flood elevations and flood hazard factors have been determined for this area. The ARAR (40 CFR 264) requires that disposal facilities be designed to withstand a 100-year flood. In addition, EPA's regulations (40 CFR Part 6, Appendix A) for implementing Executive Order 11988 (Floodplains Management) requires federal agencies to avoid or minimize adverse impacts of Federal actions upon floodplains, and to preserve and enhance the natural values of floodplains. Specifically, when it is apparent that a proposed or potential Agency action is likely to impact a floodplain or wetlands, the

public should be informed through appropriate public notice processes. Furthermore, if a proposed action is located in or affects a floodplain or wetlands, a floodplain/wetlands assessment shall be undertaken, and a statement of findings explaining why the proposed action must be located in or affect the floodplain or wetlands.

Regarding construction activities related to implementing the alternative, 40 CFR 6 Appendix A requires that EPA-controlled structures and facilities must be constructed in accordance with existing criteria and standards set forth under the National Flood Insurance Program (NFIP) and must include mitigation of adverse impacts wherever feasible, including the use of accepted floodproofing and/or other flood protection measures. To achieve flood protection, EPA shall wherever practicable, elevate structures above the base flood level rather than filling land. In addition, the capped area may be classified as a Tennessee Solid Waste Processing and Disposal (SWPD) Class II disposal facility. If so, the substantive requirements of the SWPD rule regarding Class II disposal facilities (e.g., siting) would apply to the Site. The SWPD rule (Rule 1200-1-7) and the Criteria for Classification of Solid Waste Disposal Facilities and Practices (40 CFR 257) require that disposal facilities must not be located in a 100-year floodplain, unless both of the following can be demonstrated:

- ! Location in the floodplain will not restrict the flow of the 100-year flood nor reduce the temporary water storage capacity of the floodplain; and
- ! The facility is designed, constructed, operated, and maintained to prevent washout of any solid waste.

Wetlands are located to the north and northeast of the facility and landfill, although these locations are not identified on National Wetland Inventory (NWI) maps. The Protection of Wetlands Order (40 CFR 6) requires that no adverse impacts to wetlands result from a remedial action. With appropriate stormwater runoff and runoff controls, the substantive requirements of this ARAR are expected to be met. The SWPD rule requires that new landfills and lateral expansions shall not be located in a wetlands, unless the owner or operator can make the following demonstrations:

- the presumption of a practicable alternative that does not involve wetlands is clearly rebutted;
- the construction/operation of the landfill will not cause or contribute to violations of applicable State water quality standards, any applicable toxic effluent standard or prohibition under Section 307 of the Clean Water Act (CWA), and will not cause or contribute to the taking of any endangered or threatened species or result in the destruction or adverse modification of critical habitat of endangered or threatened species;
- the landfill will not cause or contribute to significant degradation of wetlands;
- to the extent required under Section 404 of the CWA or Tennessee Water Pollution Control Act (TWPCA), steps have been taken to attempt to achieve no net loss of wetlands (as defined by acreage and function); and
- sufficient information is available to make a reasonable determination with respect to these demonstrations.

The substantive requirements for stormwater discharges during construction activities as outlined by the CWA are relevant and appropriate. However, a specific NPDES permit is not required for this remedial action.

All action-specific ARARs are expected to be met. The Tennessee Air Pollution Control Regulations (TAPCR) dust suppression and control requirements (Rule 1200-3-8) apply to earth-moving activities associated with this alternative. ARARs for the control of fugitive dust emissions would be met by applying water to roads receiving heavy vehicular traffic and to excavation areas, as necessary.

#### **2.8.2.4 Long-Term Effectiveness and Permanence**

Under this alternative, the cap would have to be maintained to ensure that it continues to perform as designed; consequently, long-term monitoring, inspection, and maintenance would be required. The cap would be susceptible to settlement, ponding of surface water, erosion, and disruption of cover integrity by deep-rooting vegetation and burrowing animals. The cover would need to be periodically

inspected, and required maintenance would need to be implemented in order to maintain effectiveness.

The long-term effectiveness of capping the waste would be enhanced by selecting the proper cover design and grading layout. In addition, access restrictions such as land use controls and fencing would be required to prevent land uses incompatible with the Site; specifically, land uses that would compromise the cap should be precluded.

#### **2.8.2.5 Reduction of M/T/V Through Treatment**

The primary objective of this alternative is to reduce contaminant mobility by isolating contaminants from receptor contact; contaminant volume or toxicity would not be reduced. Contaminant mobility would be reduced by installing an impermeable cap liner. The liner would eliminate surface water or precipitation infiltration and would greatly reduce contaminant migration to groundwater in conjunction with the existing clay unit beneath the Site. Consolidation and capping would isolate waste source areas and would reduce contaminant mobility resulting from surface water transport and wind erosion. Contaminant mobility is expected to be reduced to an extent that would result in overall risk reduction from all pathways and exposure routes.

This alternative would not meet EPA's expectation to use treatment to address the principal threats posed by a site, although in some situations, containment of principal threats is warranted (EPA 1991). Based on sample results collected during previous Site investigations, 600 CY of surface soil and 16,000 CY of stockpiled and land filled slag would be considered "principal-threat" waste.

Containment of principal threats may be warranted where treatment technologies are not technically feasible or available within a reasonable time frame; or where the volume of materials or complexity of the site makes implementation of treatment technologies infeasible; or where implementation of a treatment-based remedy would result in greater overall risk to human health and the environment or cause severe effects across environmental media. A review of currently available technologies and

Site conditions does not suggest that these situations would apply to the RM Site.

#### **2.8.2.6 Short-Term Effectiveness**

The construction phase of this alternative would likely be accomplished within one field season; therefore, impacts associated with construction would likely be short term and minimal. Short-term impacts are associated with excavation and consolidation of waste soil and slag; however, these potential, short-term impacts would be mitigated during the construction phase.

If the excavated material is dry, on-Site workers will be exposed to waste soil and slag dust during excavation and consolidation activities. Additional exposure to lead dust may occur during the demolition of building structures and pavement. Ingestion of dust could involve some health effects because of the high level of metals in waste soil and slag.

On-Site workers would be adequately protected from short-term risks by using appropriate personal protective equipment and by following proper operating and safety procedures. However, short-term air quality impacts to the surrounding environment may occur during waste consolidation and grading. Dust emissions would be monitored at the property boundaries. Fugitive dust emissions would be controlled by applying water as needed to surfaces receiving heavy vehicular traffic or in excavation areas. A measurable, short-term impact to the surrounding area would include increased vehicular traffic and associated safety hazards, potential dust generation, and noise.

#### **2.8.2.7 Implementability**

Construction of a geomembrane surface cap is a standard construction practice. Other than the capping of contaminated material in a floodplain, no significant construction issues are expected to be encountered.



No state or federal permits are expected to be required; however, advance consultation should occur while planning the action to ensure that all involved agencies are allowed to provide input.

All services and materials for this alternative are readily available.

#### **2.8.2.8 Cost**

The total present worth for S-2 is approximately \$1,735,804 for Option 1, which includes the excavated wetlands sediment, and \$1,712,412 for Option 2, which does not include the wetland sediment. For Option 1, the estimated capital cost is approximately \$1,575,908, and the estimated O&M cost is approximately \$159,895. For Option 2, the estimated capital cost is approximately \$1,552,516, and the estimated O&M cost is approximately \$159,895.

### **2.8.3 Alternative S-3 -- Capping With Pavement in Place**

#### **2.8.3.1 Description**

Alternative S-3 differs from Alternative S-2 in that the waste is not disposed of in an excavation, but rather spread over the existing pavement and capped in place with the existing landfill. Alternative S-3 includes the demolition of most of the on-Site buildings. The main office building would remain on Site, and the landfilled slag would remain in place. Contaminated soil from areas not covered by pavement would be excavated and consolidated with the stockpiled slag and building debris, and excavated wetland sediment. This waste material would be spread above the pavement that extends from the existing landfill to about 375 feet south of the landfill. A geosynthetic cap and underlying 1.5-ft soil cushion layer would be added above the waste and existing landfill and would cover about 6.7 acres. The total height of the capped area would be and existing landfill and would cover approximately 6.7 acres. The total height of the capped area would be approximately 5 feet. A 1-ft soil cover and 6-inch topsoil layer would be placed over the entire Site. The components of this

alternative are outlined as follows:


- Demolition of buildings;
- Excavation of contaminated soil in southeastern corner of the Site (2,800 CY);
- Compaction of 9,800 CY of waste material above pavement and landfill (2,800 CY of waste soil; 6,000 CY of stockpiled slag; and 1,000 CY of building debris) (Compaction of 19,100 CY of waste material if excavated wetlands sediment is consolidated with surface soil for final disposition);
- Installation of 1.5-ft-deep soil cushion over waste and existing landfill (20,300 CY);
- Installation of geomembrane liner and geotextile over soil cushion (6.7 acres);
- Soil cover (1 ft deep), topsoil cover (6 inches deep), and grass seeding over Site (8 acres); and
- Land use/deed restrictions and fencing.

The topsoil layer of the cap would be graded to a minimum slope of 3% and a maximum of 5% to promote surface drainage away from the waste cell and reduce infiltration. Surface drainage controls would be constructed around the perimeter of the cap to collect surface water runoff.

Alternative S-3 would eliminate direct contact with contaminated media, eliminate on-Site physical hazards, further minimize contaminant migration to groundwater, and eliminate contaminant migration to surface water from the Site. **Figure 2-25** illustrates the components of the cap included under this alternative as applied to the RM Site.

### **2.8.3.2 Overall Protection of Human Health and the Environment**

Successful implementation of this alternative would reduce risks to human health and the environment and meet the removal action objectives by (1) eliminating exposure of residents and trespassers to



NCAP FILE: ROSS\CAPAL13

Figure No.  
2-25

8/98

Alternative 3 - Capping With  
Pavement in Place

Ross Metals Site  
Rossville, Tennessee

**CDM Federal Programs Corporation**  
*A subsidiary of Camp Dresser & McKee Inc.*

waste material by direct contact and airborne migration, (2) eliminating exposure of trespassers to direct contact with on-Site physical hazards, and (3) further reduce the migration of contaminants to groundwater over Alternative S-2 and eliminate the migration of contaminants to surface water. Consolidation and isolation of the waste material beneath a geomembrane cap would eliminate receptor routes of exposure through ingestion and inhalation. Structures throughout the Site would be demolished and disposed of in the disposal area above the existing pavement and landfill area. The waste material would be spread and compacted throughout the Site. Physical hazards associated with deteriorating structures would be eliminated. In addition, geomembrane capping would eliminate infiltration of precipitation and surface water that contributes to the migration of contaminants to groundwater. However, because the waste material will remain on Site, contaminant migration to groundwater cannot be discounted as an adverse effect. Nevertheless, the elimination of surface water infiltration makes this scenario unlikely, and contaminant migration through surface water runoff to the adjacent wetlands and the Wolf River would be eliminated.

The threat of direct human exposure to contaminated waste and physical hazards would be practically eliminated by this alternative; however, the threat could return over the long term if cap integrity was compromised. The potential for ingestion, dermal contact, and inhalation of soil containing metals would be eliminated by successfully placing the geomembrane cap over the waste material.

### **2.8.3.3 Compliance with ARARs**

The RCRA hazardous waste disposal facility requirements are potentially applicable. The RM Site is located in a 100-year floodplain within a zone designated as A3, indicating that base flood elevations and flood hazard factors have been determined for this area. The ARAR (40 CFR 264) requires that disposal facilities be designed to withstand a 100-year flood. In addition, EPA's regulations (40 CFR Part 6, Appendix A) for implementing Executive Order 11988 (Floodplains Management) requires federal agencies to avoid or minimize adverse impacts of Federal actions upon floodplains, and to preserve and enhance the natural values of floodplains. Specifically, when it is

apparent that a proposed or potential Agency action is likely to impact a floodplain or wetlands, the public should be informed through appropriate public notice processes. Furthermore, if a proposed action is located in or affects a floodplain or wetlands, a floodplain/wetlands assessment shall be undertaken, and a statement of findings explaining why the proposed action must be located in or affect the floodplain or wetlands.

Regarding construction activities related to implementing the alternative, 40 CFR 6 Appendix A requires that EPA-controlled structures and facilities must be constructed in accordance with existing criteria and standards set forth under the NFIP and must include mitigation of adverse impacts wherever feasible, including the use of accepted floodproofing and/or other flood protection measures. To achieve flood protection, EPA shall wherever practicable, elevate structures above the base flood level rather than filling land. In addition, the capped area maybe classified as a Tennessee SWPD Class II disposal facility. If so, the substantive requirements of the SWPD rule regarding Class II disposal facilities (e.g., siting) would apply to the Site. The SWPD rule (Rule 1200-1-7) and the Criteria for Classification of Solid Waste Disposal Facilities and Practices (40 CFR 257) require that disposal facilities must not be located in a 100-year floodplain, unless both of the following can be demonstrated:

- Location in the floodplain will not restrict the flow of the 100-year flood nor reduce the temporary water storage capacity of the floodplain; and
- The facility is designed, constructed, operated, and maintained to prevent washout of any solid waste.

Wetlands are located to the north and northeast of the facility and landfill, although these locations are not identified on NWI maps. The Protection of Wetlands Order (40 CFR 6) requires that no adverse impacts to wetlands result from a remedial action. With appropriate stormwater runoff and runoff controls, the substantive requirements of this ARAR are expected to be met. The SWPD rule requires that new landfills and lateral expansions shall not be located in a wetlands, unless the owner

or operator can make the following demonstrations:

- the presumption of a practicable alternative that does not involve wetlands is clearly rebutted;
- the construction/operation of the landfill will not cause or contribute to violations of applicable State water quality standards, any applicable toxic effluent standard or prohibition under Section 307 of the CWA, and will not cause or contribute to the taking of any endangered or threatened species or result in the destruction or adverse modification of critical habitat of endangered or threatened species;
- the landfill will not cause or contribute to significant degradation of wetlands;
- to the extent required under Section 404 of the CWA or Tennessee Water Pollution Control Act, steps have been taken to attempt to achieve no net loss of wetlands (as defined by acreage and function); and
- sufficient information is available to make a reasonable determination with respect to these demonstrations.

The substantive requirements for stormwater discharges during construction activities as outlined by the CWA are relevant and appropriate. However, a specific NPDES permit is not required for this remedial action.

All action-specific ARARs are expected to be met. The TAPCR dust suppression and control requirements (Rule 1200-3-8) apply to earth-moving activities associated with this alternative. ARARs for the control of fugitive dust emissions would be met by applying water to roads receiving heavy vehicular traffic and to excavation areas, as necessary.

#### **2.8.3.4 Long-Term Effectiveness and Permanence**

Under this alternative, the cap would have to be maintained to ensure that it continues to perform as designed; consequently, long-term monitoring, inspection, and maintenance would be required. The

cap would be susceptible to settlement, ponding of surface water, erosion, and disruption of cover integrity by deep-rooting vegetation and burrowing animals. The cover would need to be periodically inspected, and required maintenance would need to be implemented.

The long-term effectiveness of capping the waste would be enhanced by selecting the proper cover design and grading layout. In addition, access restrictions such as land use controls and fencing would be required to prevent land uses that are incompatible with the Site; specifically, land uses that would compromise the cap should be precluded.

#### **2.8.3.5 Reduction of M/T/V Through Treatment**

The primary objective of this alternative is to reduce contaminant mobility by isolating contaminants from receptor contact; contaminant volume or toxicity would not be reduced. Contaminant mobility would be reduced by installing an impermeable cap liner. The liner would eliminate surface water or precipitation infiltration and would greatly reduce contaminant migration to groundwater in conjunction with the existing clay unit beneath the Site. Consolidation and capping would isolate waste source areas and reduce contaminant mobility resulting from surface water transport and wind erosion. Contaminant mobility is expected to be reduced to an extent that would result in overall risk reduction from all pathways and exposure routes.

This alternative would not meet EPA's expectation to use treatment to address the principal threats posed by a site, although in some situations, containment of principal threats is warranted (EPA 1991). Based on sample results collected during previous Site investigations, 600 CY of surface soil and the 16,000 CY of stockpiled and landfilled slag would be considered "principal-threat" waste.

Containment of principal threats may be warranted where treatment technologies are not technically feasible or available within a reasonable time frame; or where the volume of materials or complexity of the site makes implementation of treatment technologies infeasible; or where implementation of

a treatment-based remedy would result in greater overall risk to human health and the environment or cause severe effects across environmental media. A review of currently available technologies and Site conditions does not suggest that these situations would apply to the RM Site.

#### **2.8.3.6 Short-Term Effectiveness**

The construction phase of this alternative would likely be accomplished within one field season; therefore, impacts associated with construction would likely be short-term and minimal. Short-term impacts are associated with excavation and consolidation of waste soil and slag; however, these potential, short-term impacts would be mitigated during the construction phase.

If the excavated material is dry, on-Site workers will be exposed to waste soil and slag dust during excavation and consolidation activities. Additional exposure to lead dust may occur during building structure and pavement demolition. Ingestion of dust could involve some health effects because of the high level of metals in waste soil and slag.

On-Site workers would be adequately protected by using appropriate personal protective equipment and by following proper operating and safety procedures. However, short-term air quality impacts to the surrounding environment may occur during waste consolidation and grading. Dust emissions would be monitored at the property boundaries. Fugitive dust emissions would be controlled by applying water to surfaces receiving heavy vehicular traffic or in excavation areas, as needed. A measurable, short-term impact to the surrounding area would include increased vehicular traffic and associated safety hazards, potential dust generation, and noise.

#### **2.8.3.7 Implementability**

Construction of a geomembrane surface cap is a standard construction practice. Other than capping contaminated material in a floodplain, no significant construction issues are expected to be



encountered.

No state or federal permits are expected to be required; however, advance consultation should occur while planning the action to ensure that all involved agencies are allowed to provide input.

All services and materials for this alternative are readily available.

#### **2.8.3.8 Cost**

The total present worth for Alternative S-3 is approximately \$1,453,803 for Option 1, which includes the excavated wetlands sediment, and \$1,430,411 for Option 2, which does not include the wetland sediment. For Option 1, the estimated capital cost is approximately \$1,293,907, and the estimated O&M cost is approximately \$159,895. For Option 2, the estimated capital cost is approximately \$1,270,515, and the estimated O&M cost is approximately \$159,895.

### **2.8.4 Alternative S-4 -- Capping With Construction of Above-Ground Disposal Cell**

#### **2.8.4.1 Description**

Alternative S-4 differs from Alternatives S-2 and S-3 in that waste is not disposed of in the area of the existing pavement; instead, it is consolidated over the surface of the existing landfill and capped in place. This method would result in a disposal cell approximately 15 feet high throughout the landfill area. This alternative includes the demolition of most of the on-Site pavement and buildings. The main office building and the pavement immediately surrounding this building would remain on Site, and landfilled slag would remain in place. Contaminated soil beneath the pavement would be excavated up to a 3 ft maximum depth and consolidated with the stockpiled slag, pavement, and building debris. This alternative includes the following components:

- Demolition of pavement and buildings;
- Excavation of onsite contaminated soil (15,625 CY);
- Compaction of 26,325 CY of waste material (15,625 CY of waste soil; 6,000 CY of stockpiled slag; 3,700 CY of pavement; and 1,000 CY of building debris) in existing landfill area with a cell height of about 12 to 13 feet (Compaction of 35,625 CY of waste material, with a cell height of 15 feet if excavated wetlands sediment are consolidated with surface soils for final disposition;
- Installation of 1.5-ft-deep soil cushion over the waste and existing landfill (7,600 CY);
- Installation of geomembrane liner and geotextile over soil cushion (2.5 acres);
- Soil cover (1 ft deep), topsoil cover (6 inches deep), and grass seeding over the Site (8 acres); and
- Land use restrictions and security fencing.

Surface drainage controls would be constructed around the perimeter of the cap to collect surface water runoff.

Alternative S-4 would eliminate direct contact with contaminated media, eliminate on-Site physical hazards, minimize contaminant migration to groundwater, and eliminate contaminant migration to surface water from the Site. **Figure 2-26** illustrates the components of the cap included under this alternative as applied to the RM Site.

#### **2.8.4.2 Overall Protection of Human Health and the Environment**

Successful implementation of this alternative would reduce risks to human health and the environment and meet the removal action objectives by (1) eliminating exposure of residents and trespassers to waste material by direct contact and airborne migration, (2) eliminating exposure of trespassers to direct contact with on-Site physical hazards, and (3) further reduce the migration of contaminants to




Figure No.  
2-26

8/98

Alternative 4 - Capping With  
Construction of Above Ground  
Disposal Cell

Ross Metals Site  
Rossville, Tennessee  
**CDM Federal Programs Corporation**  
*A subsidiary of Camp Dresser & McKee Inc.*

NOTE: Conceptual design. Federal, state, and local requirements regarding construction in a floodplain must be considered and may affect design. Representation of waste material includes excavated wetland sediments.

groundwater over Alternative S-2 and eliminate the migration of contaminants to surface water. Consolidation and isolation of the waste material beneath a geomembrane cap would eliminate receptor routes of exposure through ingestion and inhalation. Structures throughout the Site would be demolished and disposed of in the disposal area above the existing pavement and landfill area. The waste material would be spread and compacted over the landfill area. Physical hazards associated with deteriorating structures would be eliminated. In addition, geomembrane capping would eliminate infiltration of precipitation and surface water that contributes to the migration of contaminants to groundwater. However, because the waste material will remain on Site, contaminant migration to groundwater cannot be discounted as an adverse effect. Nevertheless, the elimination of surface water infiltration makes this scenario unlikely, and contaminant migration through surface water runoff to the adjacent wetlands and the Wolf River would be eliminated.

The threat of direct human exposure to contaminated waste and physical hazards would be practically eliminated by this alternative; however, the threat could return over the long term if cap integrity was compromised. The potential for ingestion, dermal contact, and inhalation of soil containing metals would be eliminated by successfully placing the geomembrane cap over the waste material.

#### **2.8.4.3 Compliance with ARARs**

The RCRA hazardous waste disposal facility requirements are potentially applicable. The RM Site is located in a 100-year floodplain within a zone designated as A3, indicating that base flood elevations and flood hazard factors have been determined for this area. The ARAR (40 CFR 264) requires that disposal facilities be designed to withstand a 100-year flood. In addition, EPA's regulations (40 CFR Part 6, Appendix A) for implementing Executive Order 11998 (Floodplains Management) requires federal agencies to avoid or minimize adverse impacts of Federal actions upon floodplains, and to preserve and enhance the natural values of floodplains. Specifically, when it is apparent that a proposed or potential Agency action is likely to impact a floodplain or wetlands, the public should be informed through appropriate public notice processes. Furthermore, if a proposed

action is located in or affects a floodplain or wetlands, a floodplain/wetlands assessment shall be undertaken, and a statement of findings explaining why the proposed action must be located in or affect the floodplain or wetlands.

Regarding construction activities related to implementing the alternative, 40 CFR 6 Appendix A requires that EPA-controlled structures and facilities must be constructed in accordance with existing criteria and standards set forth under the NFIP and must include mitigation of adverse impacts wherever feasible, including the use of accepted floodproofing and/or other flood protection measures. To achieve flood protection, EPA shall wherever practicable, elevate structures above the base flood level rather than filling land. In addition, the capped area may be classified as a Tennessee SWPD Class II disposal facility. If so, the substantive requirements of the SWPD rule regarding Class II disposal facilities (e.g., siting) would apply to the Site. The SWPD rule (Rule 1200-1-7) and the Criteria for Classification of Solid Waste Disposal Facilities and Practices (40 CFR 257) require that disposal facilities must not be located in a 100-year floodplain, unless both of the following can be demonstrated:

- ! Location in the floodplain will not restrict the flow of the 100-year flood nor reduce the temporary water storage capacity of the floodplain; and
- ! The facility is designed, constructed, operated, and maintained to prevent washout of any solid waste.

Wetlands are located to the north and northeast of the facility and landfill, although these locations are not identified on NWI maps. The Protection of Wetlands Order (40 CFR 6) requires that no adverse impacts to wetlands result from a remedial action. With appropriate stormwater runoff and runoff controls, the substantive requirements of this ARAR are expected to be met. The SWPD rule requires that new landfills and lateral expansions shall not be located in a wetlands, unless the owner or operator can make the following demonstrations:

- the presumption of a practicable alternative that does not involve wetlands is clearly rebutted;
- the construction/operation of the landfill will not cause or contribute to violations of applicable State water quality standards, any applicable toxic effluent standard or prohibition under Section 307 of the CWA, and will not cause or contribute to the taking of any endangered or threatened species or result in the destruction or adverse modification of critical habitat of endangered or threatened species;
- the landfill will not cause or contribute to significant degradation of wetlands;
- to the extent required under Section 404 of the CWA or Tennessee Water Pollution Control Act, steps have been taken to attempt to achieve no net loss of wetlands (as defined by acreage and function); and
- sufficient information is available to make a reasonable determination with respect to these demonstrations.

The substantive requirements for stormwater discharges during construction activities as outlined by the CWA are relevant and appropriate. However, a specific NPDES permit is not required for this remedial action.

All action-specific ARARs are expected to be met. The TAPCR dust suppression and control requirements (Rule 1200-3-8) apply to earth-moving activities associated with this alternative. ARARs for the control of fugitive dust emissions would be met by applying water to roads receiving heavy vehicular traffic and to excavation areas, as necessary.

#### **2.8.4.4 Long-Term Effectiveness and Permanence**

Under this alternative, the cap would have to be maintained to ensure that it continues to perform as designed; consequently, long-term monitoring, inspection, and maintenance would be required. The cap would be susceptible to settlement, ponding of surface water, erosion, and disruption of cover integrity by deep-rooting vegetation and burrowing animals. The cover would need to be periodically

inspected, and required maintenance would need to be implemented.

The long-term effectiveness of capping the waste would be enhanced by selecting the proper cover design and grading layout. In addition, access restrictions such as land use controls and fencing would be required to prevent land uses that are incompatible with the Site; specifically, land uses that would compromise the cap should be precluded.

#### **2.8.4.5 Reduction of M/T/V Through Treatment**

The primary objective of this alternative is to reduce contaminant mobility by isolating contaminants from receptor contact; contaminant volume or toxicity would not be reduced. Contaminant mobility would be reduced by installing an impermeable cap liner. The liner would eliminate surface water or precipitation infiltration and would greatly reduce contaminant migration to groundwater in conjunction with the existing clay unit beneath the Site. Consolidation and capping would isolate waste source areas and reduce contaminant mobility resulting from surface water transport and wind erosion. Contaminant mobility is expected to be reduced to an extent that would result in overall risk reduction from all pathways and exposure routes.

Based on sample results collected during previous Site investigations, 600 CY of surface soil and the 16,000 CY of stockpiled and landfilled slag would be considered “principal-threat” waste. This alternative would not meet EPA’s expectation to use treatment to address the principal threats posed by a site, although in some situations, containment of principal threats is warranted (EPA 1991).

Containment of principal threats may be warranted where treatment technologies are not technically feasible or available within a reasonable time frame; or where the volume of materials or complexity of the site makes implementation of treatment technologies infeasible; or where implementation of a treatment-based remedy would result in greater overall risk to human health and the environment or cause severe effects across environmental media. A review of currently available technologies and

Site conditions does not suggest that these situations would apply to the RM Site.

#### **2.8.4.6 Short-Term Effectiveness**

The construction phase of this alternative would likely be accomplished within one field season; therefore, impacts associated with construction would likely be short-term and minimal. Short-term impacts are associated with excavation and consolidation of waste soil and slag; however, these potential, short-term impacts would be mitigated during the construction phase.

If the excavated material is dry, on-Site workers will be exposed to waste soil and slag dust during excavation and consolidation activities. Additional exposure to lead dust may occur during building structure and pavement demolition. Ingestion of dust could involve some health effects because of the high level of metals in waste soil and slag.

On-Site workers would be adequately protected by using appropriate personal protective equipment and by following proper operating and safety procedures. However, short-term air quality impacts to the surrounding environment may occur during waste consolidation and grading. Dust emissions would be monitored at the property boundaries. Fugitive dust emissions would be controlled by applying water to surfaces receiving heavy vehicular traffic or in excavation areas, as needed. A measurable, short-term impact to the surrounding area would include increased vehicular traffic and associated safety hazards, potential dust generation, and noise.

#### **2.8.4.7 Implementability**

Construction of a geomembrane surface cap is a standard construction practice. Other than capping contaminated material in a floodplain, no significant construction issues are expected to be encountered.



No state or federal permits are expected to be required; however, advance consultation should occur while planning the action to ensure that all involved agencies are allowed to provide input.

All services and materials for this alternative are readily available.

#### **2.8.4.8 Cost**

The total present worth for Alternative S-4 is approximately \$1,506,847 for Option 1, which includes the excavated wetlands sediment, and \$1,481,865 for Option 2, which does not include the wetland sediment. For Option 1, the estimated capital cost is approximately \$1,346,951, and the estimated O&M cost is approximately \$159,895. For Option 2, the estimated capital cost is approximately \$1,321,970, and the estimated O&M cost is approximately \$159,895.

### **2.8.5A Alternative S-5 -- Excavation And Onsite Treatment With Solidification/Stabilization Option A - Onsite Disposal of Treated Waste**

#### **2.8.5A.1 Description**

Option A for Alternative S-5 includes the decontamination and demolition of most of the on-Site pavement and buildings. The main office building and the pavement immediately surrounding this building would remain on Site. The building debris and pavement would be decontaminated by steam/pressure cleaning. Contaminated soil throughout the Site, and buried slag in the landfill would be excavated and consolidated with the stockpiled slag. Contaminants within soil and slag would be physically bound or enclosed within a stabilized mass (solidification), or chemical reactions would be induced between a stabilizing agent and the contaminant to reduce its mobility (stabilization). Solidification/stabilization treatment technologies include the addition of cement, lime, pozzolan, or silicate-based additives or chemical reagents that physically or chemically react with the contaminant.

Once treated and confirmed to be nonhazardous, the soil and slag would be consolidated with the pavement debris and disposed of in an on-Site, unlined excavation. The decontaminated building debris would be taken off Site to a metal recycling facility. The onsite disposal area would extend from the northern boundary of the existing landfill to about 100 feet north of the Site entrance and would be about 700 feet long, 250 feet wide and 8 feet deep. A 3.0-ft soil cover consisting of uncontaminated soil excavated from the disposal area and a 6-inch topsoil layer would be placed over the entire Site. The total height of the, capped area would be approximately 4.5 feet. The components of this alternative are outlined as follows:

- Decontamination and demolition of pavement and buildings;
- Recycling of metal building debris;
- Excavation of contaminated soil (21,875 CY) and landfilled slag (10,000 CY);
- Stabilization or solidification of contaminated soil, stockpiled slag, and landfilled slag (about 60,150 tons or 78,750 tons if excavated wetlands sediment are consolidated with surface soil for final disposition);
- Excavation of on-Site disposal area (700 ft long by 250 ft wide by 8 ft deep);
- Compaction of 40,817 CY of waste material (52,771 CY of waste material if wetland sediment is included); assuming a 5% increase in volume due to stabilization/solidification;
- Soil cover (3.0 ft deep), topsoil cover (6 inches deep), and grass seeding over Site (8 acres),
- Land use restrictions and security fencing.

Alternative S-5 would eliminate direct contact with contaminated media, eliminate on-Site physical hazards, and eliminate contaminant migration to groundwater and surface water from the Site. The final treatment system would depend upon the outcome of treatability testing and would be determined during the remedial design phase. The fixed material would be subjected to TCLP testing to determine if treatment has been effective, prior to placement in the excavated disposal area.


**Figure 2-27** illustrates the component of the on-Site disposal area included under Alternative S-5A.

Treatability testing may be required to demonstrate contaminant immobilization for this treatment process and to help determine the volume increase caused by the solidification/stabilization process. One treatability study to evaluate stabilization reagents that would 1) reduce the leachability of lead in treated woodland sediment and 2) improve the material handling qualities of the sediment so that, free liquids are not released during transport or disposal was completed in March 1998 (EPA 1998). The results of that study demonstrated that a biosolid product produced by N-Viro effectively reduced the leachability of lead, absorbed free liquids and resulted in a material that could be excavated and transported for disposal.

Deed restrictions may be placed on the Site while the remedial action takes place. Monitoring would be required to assess the effectiveness of the remedial action.

#### **2.8.5A.2 Overall Protection of Human Health and the Environment**

Successful implementation of this alternative would eliminate risks to human health and the environment and meet the removal action objectives by (1) eliminating exposure of residents and trespassers to waste material by direct contact and airborne migration, (2) eliminating exposure of trespassers to direct contact with on-Site physical hazards, and (3) eliminating the migration of contaminants to groundwater and surface water. The threat of direct human exposure to contaminated waste and physical hazards would be eliminated by this alternative. Treatment of the waste material would eliminate contaminant exposure through the receptor routes of ingestion and inhalation. Contaminated soil and slag would be treated and converted to a nonhazardous material. Structures throughout the Site would be demolished and either disposed of in an excavated disposal area beneath the existing pavement or recycled. As a result, physical hazards associated with deteriorating structures would be eliminated. Waste immobilized by treatment or removed by



ACAD FILE: ROSS\CAPALISA

NOTE: Conceptual design. Federal, state, and local requirements regarding construction in a floodplain must be considered and may affect design. Representation of waste material includes excavated wetland sediments.

Ross Metals Site  
 Rossville, Tennessee  
 CDM Federal Programs Corporation  
*A subsidiary of Camp Dresser & McKee Inc.*

Alternative 5A  
 Treatment and Onsite Disposal

Figure No.  
 2-27  
 8/98

APPROXIMATE DIMENSIONS OF EXCAVATION:  
 TOTAL DEPTH (BELOW GROUND SURFACE) - 8 FT.  
 TOTAL HEIGHT (ABOVE GROUND SURFACE) - 4.5 FT.  
 LENGTH - 700 FT.  
 WIDTH - 250 FT.

NOT TO SCALE

decontamination would eliminate contaminant migration from the Site.

### **2.8.5A.3 Compliance with ARARs**

The State of Tennessee SWPD rules are potentially applicable. The State may classify the on-Site disposal area for treated waste as a Class II (industrial waste) landfill facility. Class II facilities must meet the same requirements as Class I (solid waste) disposal facilities unless a waiver of one or more of the standards is obtained as set forth in SWPD Rule 1200-1-7-.01(5). Class I standards include requirements for landfill liners, geologic buffers, leachate collection systems, and other requirements that may not be necessary for the RM Site to be protective of human health and the environment. The SWPD rule also includes buffer zone standards for Class II facilities. These standards require that new facilities be located so that fill areas are, at a minimum, 100 feet from all property lines and 500 feet from all residences unless the owner agrees in writing to a shorter distance. A disposal area that is constructed to be about 700 feet by 250 feet would likely meet both the buffer zone and capacity requirements for the RM Site.

The RM Site is located in a 100-year floodplain within a zone designated as A3, indicating that base flood elevations and flood hazard factors have been determined for this area. The SWPD rule (Rule 1200-1-7) and the Criteria for Classification of Solid Waste Disposal Facilities and Practices (40 CFR 257) require that disposal facilities must not be located in a 100-year floodplain, unless both of the following can be demonstrated:

- ! Location in the floodplain will not restrict the flow of the 100-year flood nor reduce the temporary water storage capacity of the floodplain; and
- ! The facility is designed, constructed, operated, and maintained to prevent washout of any solid waste.

In addition, EPA's regulations (40 CFR Part 6, Appendix A) for implementing Executive Order 11988 (Floodplains Management) requires federal agencies to avoid or minimize adverse impacts of Federal

actions upon floodplains, and to preserve and enhance the natural values of floodplains. Specifically, when it is apparent that a proposed or potential Agency action is likely to impact a floodplain or wetlands, the public should be informed through appropriate public notice processes. Furthermore, if a proposed action is located in or affects a floodplain or wetlands, a floodplain/wetlands assessment shall be undertaken, and a statement of findings explaining why the proposed action must be located in or affect the floodplain or wetlands.

Regarding construction activities related to implementing the alternative, 40 CFR 6 Appendix A requires that EPA-controlled structures and facilities must be constructed in accordance with existing criteria and standards set forth under the NFIP and must include mitigation of adverse impacts wherever feasible, including the use of accepted floodproofing and/or other flood protection measures. To achieve flood protection, EPA shall wherever practicable, elevate structures above the base flood level rather than filling land.

Wetlands are located to the north and northeast of the facility and landfill, although these locations are not identified on NWI maps. The SWPD rule requires that new landfills and lateral expansions shall not be located in a wetlands, unless the owner or operator can make the following demonstrations:

- the presumption of a practicable alternative that does not involve wetlands is clearly rebutted;
- the construction/operation of the landfill will not cause or contribute to violations of applicable State water quality standards, any applicable toxic effluent standard or prohibition under Section 307 of the CWA, and will not cause or contribute to the taking of any endangered or threatened species or result in the destruction or adverse modification of critical habitat of endangered or threatened species;
- the landfill will not cause or contribute to significant degradation of wetlands;
- to the extent required under Section 404 of the CWA or Tennessee Water Pollution Control Act, steps have been taken to attempt to achieve no net loss of wetlands (as

defined by acreage and function); and

- sufficient information is available to make a reasonable determination with respect to these demonstrations.

The Protection of Wetlands Order (40 CFR 6) also requires that no adverse impacts to wetlands result from a remedial action. Historical evidence suggests that the existing landfill was created in a wetland. However, this area was not observed to contain standing water during sampling events conducted in 1996 and 1997. It is not known whether the area of the existing landfill would be classified as a wetland area.

The substantive requirements for stormwater discharges during construction activities as outlined by the CWA are relevant and appropriate. However, a specific NPDES permit is not required for this removal action.

All action-specific ARARs are expected to be met. The Tennessee Air Pollution Air Control Regulations (TAPCR) dust suppression and control requirements (Rule 1200-3-8) apply to earthmoving activities associated with this alternative. If remedial equipment is used on Site such as a pugmill mixer or crusher, dust and vapors generated from the use of this equipment will be contained and treated before being discharged to the atmosphere, if required. ARARs for the control of fugitive dust emissions would be met by applying water to roads receiving heavy vehicular traffic and to excavation areas, as necessary.

#### **2.8.5A.4 Long-Term Effectiveness and Permanence**

If the disposal area is classified as a Class II disposal facility, the area may have to be maintained to ensure that it continues to perform as designed; consequently, monitoring, inspection, and maintenance would be required. The soil cover area would be susceptible to settlement, ponding of surface water, erosion, and disruption of cover integrity by deep-rooting vegetation and burrowing

animals. However, the cover would be periodically inspected, and required maintenance could be implemented.

If the RM Site is not classified as a Class II disposal facility; monitoring, inspection, and maintenance may not be required. Treatment reagents are typically tested by the Multiple Extraction Procedure (MEP, SW-846 Method 1320) to measure long-term stability. The test is intended to approximate leachability under acidic conditions over a 1,000-year time frame. Based on successful completion of bench-scale testing that would include MEP analysis, this alternative is expected to provide adequate long-term effectiveness and permanence. Access restrictions such as land use controls and fencing may be required to prevent land uses incompatible with the Site.

#### **2.8.5A.5 Reduction of M/T/V Through Treatment**

The primary objective of this alternative is to reduce contaminant toxicity and mobility through treatment; contaminant volume would not be reduced. Contaminant toxicity would be reduced by altering the physical or chemical structure of the contaminant into a nonhazardous material. Contaminant mobility would be reduced by binding or bonding the contaminant into a nonleachable form that would eliminate contaminant migration from the Site. Contaminant mobility is expected to be reduced to an extent that would result in overall risk reduction from all pathways and exposure routes.

Based on sample results collected during previous Site investigations, 600 CY of surface soil and the 16,000 CY of stockpiled and landfilled slag would be considered "principal-threat" waste. This alternative meets EPA's expectation to use treatment to address the principal threats posed by a site by treating all the contaminated soil, sediment, and slag. However, treatment of what would be considered low-level threat waste does not meet EPA's expectation to use containment to address such waste, although in some situations, treatment rather than containment of low-level threats is warranted (EPA 1991).



#### **2.8.5A.6 Short-Term Effectiveness**

The construction phase of this alternative would likely be accomplished within one field season; therefore, impacts associated with construction would likely be short term and minimal. Short-term impacts are associated with excavation, consolidation, and treatment of waste soil and slag; however, these potential, short-term impacts would be mitigated during the construction phase.

If the excavated material is dry, on-Site workers will be exposed to waste soil and slag dust during excavation and consolidation activities. Additional exposure to lead dust may occur during the decontamination and demolition of building structures and pavement. Ingestion of dust could involve some health effects because of the high level of metals in waste soil and slag.

On-Site workers would be adequately protected from short-term risks by using appropriate personal protective equipment and by following proper operating and safety procedures. However, short-term air quality impacts to the surrounding environment may occur during waste consolidation and grading. Dust emissions would be monitored at the property boundaries. Fugitive dust emissions would be controlled by applying water as needed to surfaces receiving heavy vehicular traffic or in excavation areas. A measurable, short-term impact to the surrounding area would include increased vehicular traffic and associated safety hazards, potential dust generation, and noise.

#### **2.8.5A.7 Implementability**

Treatment of contaminated soil and slag is offered by numerous vendors. On-Site treatment utilizes standard construction practices and material handling equipment. No significant construction issues are expected to be encountered.

Treatment of the contaminated waste will likely increase the volume of the waste soil and slag material; however, slight volume reductions may occur when some chemical reagents are used to treat

the material. Typical volume increases range from about 5 percent to as high as 100 percent, depending upon the treatment method used. An increase in the volume of the treated waste material will have an impact on the disposal volume required. Calculations used in the development of this alternative utilized a volume increase estimate of 20 percent.

The dimensions of the Site property are about 450 by 800 feet, including the existing landfill. The waste storage capacity required for this alternative is 49,150 CY assuming a 20 percent volume increase of the treated material. To meet the SWDP buffer zone siting standards, the excavation area would be 700 by 250 feet, and with an 8-ft average depth, depending on the thickness of the clay unit. The disposal area would be located beneath the existing pavement.

Wastewater may be generated during implementation of this alternative through water runoff generated as a result of dust emission control. Wastewater may also be generated as a result of decontamination activities required for equipment and on-Site workers. Containment and treatment or disposal of these wastewaters may be required. Depending upon the treatment methodology selected, the wastewater may be able to be utilized in the soils treatment process.

The on-Site disposal area for the treated waste may be classified as a Class II disposal facility. If so, the substantive requirements of the SWPD rule regarding Class II disposal facilities would apply to the Site.

All services and materials for this alternative are readily available.

#### **2.8.5A.8 Cost**

The total present worth for Alternative S-5A is approximately \$4,907,274 for Option 1, which includes the excavated wetlands sediment, and \$4,244,992 for Option 2, which does not include the wetland sediment. For Option 1, the estimated capital cost is approximately \$4,743,474, and the

estimated O&M cost is approximately \$163,799. For Option 2, the estimated capital cost is approximately \$4,081,193, and the estimated O&M cost is approximately \$163,799.

### **2.8.5B Alternative S-5 -- Excavation And Onsite Treatment With Solidification/Stabilization Option B - Offsite Disposal of Treated Material**

#### **2.8.5B.1 Description**

Option B for Alternative S-5 is similar to Option A in that it also consists of the decontamination and demolition of most of the on-Site pavement and buildings and on-Site treatment. The main office building and the pavement immediately surrounding this building would remain on Site. The building debris and pavement would be decontaminated by steam cleaning. The decontaminated building debris would be taken off Site to a metal recycling facility. Contaminated soil throughout the Site, and buried slag in the landfill would be excavated and consolidated with the stockpiled slag. Contaminants in soil and slag would be physically bound or enclosed within a stabilized mass (solidification), or chemical reactions would be induced between a stabilizing agent and the contaminants to reduce mobility (stabilization). Solidification/stabilization treatment technologies include the addition of cement, lime, pozzolan, or silicate-based additives or chemical reagents that physically or chemically react with the contaminant. Option B differs from Option A in that after treatment and confirmation that the soil is nonhazardous, the treated soil and slag would be hauled off Site to a disposal facility. A 1.0-ft soil cover and a 6-inch topsoil layer would be placed over the entire Site. These components are outlined as follows:

- Decontamination and demolition of pavement and buildings;
- Recycling of metal building debris;
- Excavation of contaminated soil (21,875 CY), and landfilled slag (10,000 CY);
- Stabilization or solidification of contaminated soil, stockpiled slag, and landfilled slag

(about 60,150 tons; or 78,750 tons if excavated wetlands sediment are consolidated with surface soil for final disposition);

- Off-Site disposal at nonhazardous disposal facility (63,158 tons assuming a 5 percent increase in volume during treatment; 82,688 tons if excavated wetland sediment is included); and
- Bacfill excavation, soil cover (1 ft deep), topsoil cover (6 inches deep), and grass seeding over Site (8 acres).

Alternative S-5B would eliminate direct contact with contaminated media, eliminate on-Site physical hazards, and eliminate contaminant migration to groundwater and surface water from the Site.

Deed restrictions maybe placed on the Site while the remedial action takes place. Monitoring would be required to assess effectiveness of the remedial action.

#### **2.8.5B.2 Overall Protection of Human Health and the Environment**

Successful implementation of this alternative would eliminate risks to human health and the environment and meet the removal action objectives by (1) eliminating exposure of residents and trespassers to waste material by direct contact and airborne migration, (2) eliminating exposure of trespassers to direct contact with on-Site physical hazards, and (3) eliminating the migration of contaminants to groundwater and surface water. The threat of direct human exposure to contaminated waste and physical hazards would be eliminated by this alternative. Treatment and removal of the waste material would eliminate contaminant exposure through the receptor routes of ingestion and inhalation. Contaminated soil and slag would be treated and converted to a nonhazardous material and transported to an off-Site disposal facility. Structures throughout the Site would be demolished and either disposed of in an excavated disposal area beneath the existing pavement or recycled. As a result, physical hazards associated with deteriorating structures would be eliminated. Removal of waste would mitigate contaminant migration from the Site.

### **2.8.5B.3 Compliance with ARARs**

All action-specific ARARs are expected to be met. The TAPCR dust suppression and control requirements (Rule 1200-3-8) apply to earth-moving activities associated with this alternative. If remedial equipment is used on Site, such as a pugmill mixer or crusher, dust and vapors generated from the use of this equipment will be contained and treated before being discharged to the atmosphere, if required. ARARs for the control of fugitive dust emissions would be met by applying water to roads receiving heavy vehicular traffic and to excavation areas, as necessary.

### **2.8.5B.4 Long-Term Effectiveness and Permanence**

Treatment and removal of the waste material would not require monitoring, inspection, or maintenance for the Site. Treatment reagents are typically tested by MEP SW-846 Method 1320 to measure long-term stability. The test is intended to approximate leachability under acidic conditions over a 1,000-year time frame. Based on successful completion of bench-scale testing that would include MEP analysis, this alternative is expected to provide adequate long-term effectiveness and permanence. Access restrictions such as land use controls and fencing would likely not be required.

### **2.8.5B.5 Reduction of M/T/V Through Treatment**

The primary objective of this alternative is to reduce contaminant toxicity and mobility through treatment; contaminant volume would not be physically reduced. Contaminant toxicity would be reduced by altering the physical or chemical structure of the contaminant into a nonhazardous material. Contaminant mobility would be reduced by binding or bonding the contaminant into a nonleachable form. Subsequent removal would mitigate contaminant migration from the Site. Contaminant volume would not be physically reduced under this alternative.

Based on sample results collected during previous Site investigations, 600 CY of surface soil and the

16,000 CY of stockpiled and landfilled slag would be considered “principal-threat” waste. This alternative meets EPA’s expectation to use treatment to address the principal threats posed by a site by treating all the contaminated soil, sediment, and slag. However, treatment of what would be considered low-level threat waste does not meet EPA’s expectation to use containment to address such waste, although in some situations, treatment rather than containment of low-level threats is warranted (EPA 1991).

#### **2.8.5B.6 Short-Term Effectiveness**

The construction phase of this alternative would likely be accomplished within one field season; therefore, impacts associated with construction would likely be short term and minimal. Short-term impacts are associated with excavation, consolidation and treatment of waste soil and slag; however, these potential, short-term impacts would be mitigated during the construction phase.

If the excavated material is dry, on-Site workers will be exposed to waste soil and slag dust during excavation and consolidation activities. Additional exposure to lead dust may occur during the decontamination and demolition of building structures and pavement. Ingestion of dust could involve some health effects because of the high level of metals in waste soil and slag.

On-Site workers would be adequately protected from short-term risks by using appropriate personal protective equipment and by following proper operating and safety procedures. However, short-term air quality impacts to the surrounding environment may occur during waste consolidation and grading. Monitoring of dust emissions would be monitored at the property boundaries. Fugitive dust emissions would be controlled by applying water as needed to surfaces receiving heavy vehicular traffic or in excavation areas. A measurable, short-term impact to the surrounding area would include increased vehicular traffic and associated safety hazards, potential dust generation, and noise.

#### **2.8.5B.7 Implementability**

Treatment of contaminated soil and slag is offered by numerous vendors. On-Site treatment utilizes standard construction practices and material handling equipment. No significant construction issues are expected to be encountered.

Treatment of the contaminated waste will likely increase the volume of waste soil and slag material; however, a slight volume reduction may occur if a chemical reagent is used to treat the material. Typical volume increases range from about 5 percent to as high as 100 percent, depending upon the treatment methodology used. An increase in the volume of the treated waste material will have an impact on the transportation costs to a disposal facility. Calculations used in the development of this alternative assume a volume increase of 20 percent.

Wastewater may be generated during implementation of this alternative through water runoff generated as a result of dust emission control. Wastewater may also be generated as a result of decontamination activities required for both equipment and on-Site workers. Containment and treatment or disposal of these wastewaters may be required. Depending upon the treatment methodology selected, the wastewater may be able to be utilized in the soils treatment process.

No state or federal permits are expected to be required; however, advance consultation should occur in planning the action to ensure that all involved agencies are allowed to provide input.

All services and materials for this alternative are readily available.

#### **2.8.5B.8 Cost**

The total present worth for Alternative S-5B is approximately \$7,477,199 for Option 1, which includes the excavated wetlands sediment, and \$6,181,160 for Option 2, which does not include the

wetland sediment. For Option 1, the estimated capital cost is approximately \$7,313,400, and the estimated O&M cost is approximately \$163,799. For Option 2, the estimated capital cost is approximately \$6,017,361, and the estimated O&M cost is approximately \$163,799.

**2.8.6A      Alternative S-6 -- Capping w/ Excavation & Onsite Treatment of  
Principal Threat Waste  
Option A - Onsite Disposal of Treated Principal Threat Waste**

**2.8.6A.1   Description**

Alternative S-6 is similar to Alternative S-5 in that it also includes the excavation and treatment of contaminated material via solidification/stabilization. However, Alternative S-6 differs from Alternative S-5 in that treatment is limited to that material that is considered principal-threat. As indicated in section 8.3, principal threat waste at the RM Site includes the landfilled and stockpiled slag, and approximately 500 CY of soil.

Option A for Alternative S-6 includes the demolition of most of the on-Site buildings. The main office building would remain on Site. The building debris and pavement would be decontaminated by steam/pressure cleaning. Onsite contaminated soil considered principal threat, and buried slag in the landfill would be excavated and consolidated with the stockpiled slag. In addition, above the RGO, contaminated soil from areas not covered by pavement, and non-principal-threat landfill soil would be excavated for placement in the excavated onsite landfill along with the treated principal-threat waste. This waste (and treated) material would be disposed in the excavated landfill area (450 x 250 ft x 5 ft deep), A geosynthetic cap and underlying 1.5-ft soil cushion layer would be added above the waste and existing landfill and would cover about 2.5 acres. A 1-ft soil cover and 6-inch topsoil layer would be placed over the entire Site. The capped disposal area would rise approximately 6 ft above ground surface.



For treatment, contaminants within soil and slag would be physically bound or enclosed within a stabilized mass (solidification), or chemical reactions would be induced between a stabilizing agent and the contaminant to reduce its mobility (stabilization). The decontaminated building debris would be taken offsite to a metal recycling facility. The components of this alternative are outlined as below:

- Decontamination and demolition of buildings;
- Recycling of metal building debris;
- Excavation of principal-threat contaminated soil (500 CY), landfilled slag (10,000 CY), and non-principal threat landfill soil (6,500 CY) to allow access to landfilled slag. (Excavation of an additional 8,200 CY of principal-threat contaminated sediment and 1,100 CY of non-principal threat contaminated sediment if contaminated wetlands sediments are excavated and consolidated with surface soils for final disposition);
- Stabilization or solidification of principal-threat contaminated soil, stockpiled slag, and landfilled slag (about 32,700 tons; 45,000 tons if principal-threat wetlands sediments are included);
- Excavation of on-Site disposal area (450 ft long by 250 ft wide by 5 ft deep) in landfill area;
- Compaction of 23,825 CY of waste material; assuming a 5% increase in volume of principal-threat material due to stabilization/solidification, and no increase in volume of non-principal threat material (33,535 CY of waste material if contaminated wetlands sediments are excavated and consolidated with surface soils for final disposition);
- Installation of 1.5-ft-deep soil cushion over waste and treated material and low-level threat material capped in place (20,300 CY);
- Installation of geomembrane liner and geotextile over soil cushion (6.7 acres);
- Soil cover (1 ft deep), topsoil cover (6 inches deep), and grass seeding over Site (8 acres); and
- Land use restrictions and security fencing.

The final treatment system would depend upon the outcome of treatability testing and would be determined during the remedial design phase. The fixed material would be subjected to TCLP testing to determine if treatment has been effective, prior to placement in the excavated disposal area. Note that the components of this alternative are considered a conceptual design, but other designs may be possible. The final design would be based on requirements regarding construction in a floodplain.

Treatability testing may be required to demonstrate contaminant immobilization for this treatment process and to help determine the volume increase caused by the solidification/stabilization process.

Land use restrictions and security fencing may be placed on the Site while the remedial action takes place. Monitoring would be required to assess the effectiveness of the remedial action.

The topsoil layer of the cap would be graded to a minimum slope of 3% and a maximum of 5% to promote surface drainage away from the waste cell and reduce infiltration. Surface drainage controls would be constructed around the perimeter of the cap to collect surface water runoff.

Option A of Alternative S-6 would eliminate direct contact with contaminated media, eliminate on-Site physical hazards, minimize contaminant migration to groundwater, and eliminate contaminant migration to surface water from the Site. **Figure 2-28** illustrates the components of the cap included under Alternative S-6A as applied to the RM Site.

#### **2.8.6A.2 Overall Protection of Human Health and the Environment**

Successful implementation of this alternative would reduce risks to human health and the environment and meet the removal action objectives by (1) eliminating exposure of residents and trespassers to waste material by direct contact and airborne migration, (2) eliminating exposure of trespassers to direct contact with on-Site physical hazards, and (3) further reduce the migration of contaminants to




Figure No.  
2-28

8/98

Alternative 6A  
Treatment w/Onsite Disposal  
of Treated Principal Threat Waste

Ross Metals Site  
Rossville, Tennessee  
CDM Federal Programs Corporation  
*A subsidiary of Camp Dresser & McKee Inc.*

NOTE: Conceptual design. Federal, state, and local requirements regarding construction in a floodplain must be considered and may affect design. Representation of waste material includes excavated wetland sediments.

groundwater over Alternative S-2 and eliminate the migration of contaminants to surface water. Consolidation and isolation of the waste material beneath a geomembrane cap would eliminate receptor routes of exposure through ingestion and inhalation. Structures throughout the Site would be demolished and disposed of in the disposal area above the existing pavement and landfill area. The waste material would be spread and compacted throughout the Site. Physical hazards associated with deteriorating structures would be eliminated. In addition, geomembrane capping would eliminate infiltration of precipitation and surface water that contributes to the migration of contaminants to groundwater. However, because the waste material will remain on Site, contaminant migration to groundwater cannot be discounted as an adverse effect. Nevertheless, the elimination of surface water infiltration makes this scenario unlikely, and contaminant migration through surface water runoff to the adjacent wetlands and the Wolf River would be eliminated.

The threat of direct human exposure to contaminated waste and physical hazards would be practically eliminated by this alternative; however, the threat could return over the long term if cap integrity was compromised. The potential for ingestion, dermal contact, and inhalation of soil containing metals would be eliminated by successfully placing the geomembrane cap over the waste material.

#### **2.8.6A.3 Compliance with ARARs**

The RCRA hazardous waste disposal facility requirements are potentially applicable. The RM Site is located in a 100-year floodplain within a zone designated as A3, indicating that base flood elevations and flood hazard factors have been determined for this area. The ARAR (40 CFR 264) requires that disposal facilities be designed to withstand a 100-year flood. In addition, EPA's regulations (40 CFR Part 6, Appendix A) for implementing Executive Order 11988 (Floodplains Management) requires federal agencies to avoid or minimize adverse impacts of Federal actions upon floodplains, and to preserve and enhance the natural values of floodplains. Specifically, when it is apparent that a proposed or potential Agency action is likely to impact a floodplain or wetlands, the public should be informed through appropriate public notice processes. Furthermore, if a proposed

action is located in or affects a floodplain or wetlands, a floodplain/wetlands assessment shall be undertaken, and a statement of findings explaining why the proposed action must be located in or affect the floodplain or wetlands.

Regarding construction activities related to implementing the alternative, 40 CFR 6 Appendix A requires that EPA-controlled structures and facilities must be constructed in accordance with existing criteria and standards set forth under the NFIP and must include mitigation of adverse impacts wherever feasible, including the use of accepted floodproofing and/or other flood protection measures. To achieve flood protection, EPA shall wherever practicable, elevate structures above the base flood level rather than filling land. In addition, the capped area may be classified as a Tennessee SWPD Class II disposal facility. If so, the substantive requirements of the SWPD rule regarding Class II disposal facilities (e.g., siting) would apply to the Site. The SWPD rule (Rule 1200-1-7) and the Criteria for Classification of Solid Waste Disposal Facilities and Practices (40 CFR 257) require that disposal facilities must not be located in a 100 -year floodplain, unless both of the following can be demonstrated:

- ! Location in the floodplain will not restrict the flow of the 100-year flood nor reduce the temporary water storage capacity of the floodplain; and
- ! The facility is designed, constructed, operated, and maintained to prevent washout of any solid waste.

Wetlands are located to the north and northeast of the facility and landfill, although these locations are not identified on NWI maps. The Protection of Wetlands Order (40 CFR 6) requires that no adverse impacts to wetlands result from a remedial action. With appropriate stormwater runoff and runoff controls, the substantive requirements of this ARAR are expected to be met. The SWPD rule requires that new landfills and lateral expansions shall not be located in a wetlands, unless the owner or operator can make the following demonstrations:

- the presumption of a practicable alternative that does not involve wetlands is clearly rebutted;
- the construction/operation of the landfill will not cause or contribute to violations of applicable State water quality standards, any applicable toxic effluent standard or prohibition under Section 307 of the CWA, and will not cause or contribute to the taking of any endangered or threatened species or result in the destruction or adverse modification of critical habitat of endangered or threatened species;
- the landfill will not cause or contribute to significant degradation of wetlands;
- to the extent required under Section 404 of the CWA or Tennessee Water Pollution Control Act, steps have been taken to attempt to achieve no net loss of wetlands (as defined by acreage and function); and
- sufficient information is available to make a reasonable determination with respect to these demonstrations.

The substantive requirements for stormwater discharges during construction activities as outlined by the CWA are relevant and appropriate. However, a specific NPDES permit is not required for this remedial action.

All action-specific ARARs are expected to be met. The TAPCR dust suppression and control requirements (Rule 1200-3-8) apply to earth-moving activities associated with this alternative. ARARs for the control of fugitive dust emissions would be met by applying water to roads receiving heavy vehicular traffic and to excavation areas, as necessary.

#### **2.8.6A.4 Long-Term Effectiveness and Permanence**

Under this alternative, the cap would have to be maintained to ensure that it continues to perform as designed; consequently, long-term monitoring, inspection, and maintenance would be required. The cap would be susceptible to settlement, ponding of surface water, erosion, and disruption of cover integrity by deep-rooting vegetation and burrowing animals. However, the cover would be

periodically inspected and maintained.

The long-term effectiveness of capping the waste would be enhanced by selecting the proper cover design and grading layout. In addition, access restrictions such as land use controls and fencing would be required to prevent land uses that are incompatible with the Site; specifically, land uses that would compromise the cap should be precluded.

#### **2.8.6A.5 Reduction of M/T/V Through Treatment**

The primary objective of this alternative is to reduce contaminant mobility by isolating contaminants from receptor contact; contaminant volume or toxicity would not be reduced. Contaminant mobility would be reduced by installing an impermeable cap liner. The liner would eliminate surface water or precipitation infiltration and would greatly reduce contaminant migration to groundwater in conjunction with the existing clay unit beneath the Site. Consolidation and capping would isolate waste source areas and reduce contaminant mobility resulting from surface water transport and wind erosion. Contaminant mobility is expected to be reduced to an extent that would result in overall risk reduction from all pathways and exposure routes.

This alternative would meet EPA's expectation to use treatment to address the principal threats posed by a site, as well as EPA's expectation to use containment to address low-level threats posed by a site. Based on sample results collected during previous Site investigations, 600 CY of surface soil and the 16,000 CY of stockpiled and landfilled slag would be considered "principal-threat" waste.

#### **2.8.6A.6 Short-Term Effectiveness**

The construction phase of this alternative would likely be accomplished within one field season; therefore, impacts associated with construction would likely be short-term and minimal. Short-term impacts are associated with excavation and consolidation of waste soil and slag; however, these

potential, short-term impacts would be mitigated during the construction phase.

If the excavated material is dry, on-Site workers will be exposed to waste soil and slag dust during excavation and consolidation activities. Additional exposure to lead dust may occur during building structure and pavement demolition. Ingestion of dust could involve some health effects because of the high level of metals in waste soil and slag.

On-Site workers would be adequately protected by using appropriate personal protective equipment and by following proper operating and safety procedures. However, short-term air quality impacts to the surrounding environment may occur during waste consolidation and grading. Dust emissions would be monitored at the property boundaries. Fugitive dust emissions would be controlled by applying water to surfaces receiving heavy vehicular traffic or in excavation areas, as needed. A measurable, short-term impact to the surrounding area would include increased vehicular traffic and associated safety hazards, potential dust generation, and noise.

#### **2.8.6A.7 Implementability**

Construction of a geomembrane surface cap is a standard construction practice. Other than capping treated and low level-threat material in a floodplain, no significant construction issues are expected to be encountered.

Treatment of contaminated soil and slag is offered by numerous vendors. On-Site treatment utilizes standard construction practices and material handling equipment. No significant construction issues are expected to be encountered.

Treatment of the contaminated waste will likely increase the volume of the waste soil and slag material; however, slight volume reductions may occur when some chemical reagents are used to treat the material. Typical volume increases range from about 5 percent to as high as 100 percent,



depending upon the treatment method used. An increase in the volume of the treated waste material will have an impact on the disposal volume required. Calculations used in the development of this alternative utilized a volume increase estimate of 5 percent.

The on-Site disposal area for the treated waste may be classified as a Class II disposal facility. If so, the substantive requirements of the SWPD rule regarding Class II disposal facilities would apply to the Site.

All services and materials for this alternative are readily available.

#### **2.8.6A.8 Cost**

The total present worth for Alternative S-6A is approximately \$3,175,137 for Option 1, which includes the excavated wetlands sediment, and \$2,729,543 for Option 2, which does not include the wetland sediment. For Option 1, the estimated capital cost is approximately \$3,015,241, and the estimated O&M cost is approximately \$159,895. For Option 2, the estimated capital cost is approximately \$2,569,647, and the estimated O&M cost is approximately \$159,895.

#### **2.8.6B Alternative S-6 -- Capping w/ Excavation & Onsite Treatment of Principal Threat Waste Option B - Offsite Disposal of Treated Principal-Threat Waste**

##### **2.8.6B.1 Description**

Option B is similar to Option A except that treated principal-threat waste is disposed offsite in a RCRA subtitle D landfill rather than being capped onsite with the low-level threat waste. Like Option A, Option B for Alternative S-6 includes the demolition of most of the on-Site buildings. The main office building would remain on Site. The building debris and pavement would be decontaminated

by steam/pressure cleaning. Onsite contaminated soil considered principal threat, and buried slag in the landfill would be excavated and consolidated with the stockpiled slag. In addition, contaminated soil from areas not covered by pavement, and non-principal-threat landfill soil would be excavated for placement in the excavated onsite landfill. This low level-threat waste material would be disposed in the excavated landfill area (450 x 250 ft x 5 ft deep). A geosynthetic cap and underlying 1.5-ft soil cushion layer would be added above the waste and existing landfill and would cover about 2.5 acres. A 1-ft soil cover and 6-inch topsoil layer would be placed over the entire Site.

For treatment, contaminants within soil and slag would be physically bound or enclosed within a stabilized mass (solidification), or chemical reactions would be induced between a stabilizing agent and the contaminant to reduce its mobility (stabilization). The decontaminated building debris would be taken offsite to a metal recycling facility. The components of this alternative are outlined as below:

- Decontamination and demolition of buildings;
- Recycling of metal building debris;
- Excavation of principal-threat contaminated soil (500 CY), landfilled slag (10,000 CY), and non-principal threat landfill soil (6,500 CY) to allow access to landfilled slag. (Excavation of an additional 8,200 CY of principal-threat contaminated wetland sediment and 1,100 CY of non-principal threat contaminated wetland sediment if contaminated wetland sediments are excavated and consolidated with surface soil for final disposition);
- Stabilization or solidification of principal-threat contaminated soil and wetland sediment, stockpiled slag, and landfilled slag (about 32,700; 45,000 tons if contaminated wetland sediments are excavated and consolidated with surface soils for final disposition);
- Excavation of on-site disposal area (450 ft long by 250 ft wide by 5 ft deep) in landfill area;
- Compaction of 6,500 CY of low-level (non-principal threat) waste material (7,600 CY if contaminated wetland sediments are excavated and consolidated with surface soil for final disposition);

- Offsite disposal of 34,335 tons of treated principal-threat waste (assuming 5% increase in volume due to treatment) in RCRA Subtitle D landfill (47,250 tons if contaminated wetlands sediment are excavated and consolidated with surface soil for final disposition);
- Installation of 1.5-ft-deep soil cushion over waste and treated material and low-level threat material capped in place (20,300 CY);
- Installation of geomembrane liner and geotextile over soil cushion (6.7 acres);
- Soil cover (1 ft deep), topsoil cover (6 inches deep), and grass seeding over Site (8 acres); and
- Land use restrictions and security fencing.

The final treatment system would depend upon the outcome of treatability testing and would be determined during the remedial design phase. The fixed material would be subjected to TCLP testing to determine if treatment has been effective, prior to placement in the excavated disposal area. Note that the components of this alternative are considered a conceptual design, but other designs may be possible. The final design would be based on requirements regarding construction in a floodplain.

Treatability testing may be required to demonstrate contaminant immobilization for this treatment process and to help determine the volume increase caused by the solidification/stabilization process.

Land use restrictions and security fencing may be placed on the Site while the remedial action takes place. Monitoring would be required to assess the effectiveness of the remedial action.

The topsoil layer of the cap would be graded to a minimum slope of 3% and a maximum of 5% to promote surface drainage away from the waste cell and reduce infiltration. Surface drainage controls would be constructed around the perimeter of the cap to collect surface water runoff.


Option B of Alternative S-6 would eliminate direct contact with contaminated media, eliminate on-

Site physical hazards, minimize contaminant migration to groundwater, and eliminate contaminant migration to surface water from the Site. **Figure 2-29** illustrates the components of the cap included under Alternative S-6B as applied to the RM Site.

#### **2.8.6B.2 Overall Protection of Human Health and the Environment**

Successful implementation of this alternative would reduce risks to human health and the environment and meet the removal action objectives by (1) eliminating exposure of residents and trespassers to waste material by direct contact and airborne migration, (2) eliminating exposure of trespassers to direct contact with on-Site physical hazards, and (3) further reduce the migration of contaminants to groundwater over Alternative S-2 and eliminate the migration of contaminants to surface water. Consolidation and isolation of low level-threat waste material beneath a geomembrane cap would eliminate receptor routes of exposure through ingestion and inhalation. Structures throughout the Site would be demolished and disposed of in the disposal area above the existing pavement and landfill area. The waste material would be spread and compacted throughout the Site. Physical hazards associated with deteriorating structures would be eliminated. In addition, geomembrane capping would eliminate infiltration of precipitation and surface water that contributes to the migration of contaminants to groundwater. However, because the waste material will remain on Site, contaminant migration to groundwater cannot be discounted as an adverse effect. Nevertheless, the elimination of surface water infiltration makes this scenario unlikely, and contaminant migration through surface water runoff to the adjacent wetlands and the Wolf River would be eliminated.

The threat of direct human exposure to contaminated waste and physical hazards would be practically eliminated by this alternative; however, the threat could return over the long term if cap integrity was compromised. The potential for ingestion, dermal contact, and inhalation of soil containing metals would be eliminated by successfully placing the geomembrane cap over the waste material.



APPROXIMATE DIMENSIONS OF EXCAVATION: TOTAL DEPTH - 5 FT.  
 LENGTH - 250 FT.  
 WIDTH - 450 FT.

NOT TO SCALE

<p>Alternative 6B          Treatment W/Offsite Disposal          of Treated Principal Threat          Waste</p>	<p>Ross Metals Site          Rossville, Tennessee</p>	<p>CDM Federal Programs Corporation  <i>A subsidiary of Camp Dresser &amp; McKee Inc.</i></p>
<p>Figure No.          2-29</p>		<p>8/98</p>

NOTE: Conceptual design. Federal, state, and local requirements regarding construction in a floodplain must be considered and may affect design. Representation of waste material includes excavated wetland sediments.

### **2.8.6B.3 Compliance with ARARs**

The RCRA hazardous waste disposal facility requirements are potentially applicable. The RM Site is located in a 100-year floodplain within a zone designated as A3, indicating that base flood elevations and flood hazard factors have been determined for this area. The ARAR (40 CFR 264) requires that disposal facilities be designed to withstand a 100-year flood. In addition, EPA's regulations (40 CFR Part 6, Appendix A) for implementing Executive Order 11988 (Floodplains Management) requires federal agencies to avoid or minimize adverse impacts of Federal actions upon floodplains, and to preserve and enhance the natural values of floodplains. Specifically, when it is apparent that a proposed or potential Agency action is likely to impact a floodplain or wetlands, the public should be informed through appropriate public notice processes. Furthermore, if a proposed action is located in or affects a floodplain or wetlands, a floodplain/wetlands assessment shall be undertaken, and a statement of findings explaining why the proposed action must be located in or affect the floodplain or wetlands.

Regarding construction activities related to implementing the alternative, 40 CFR 6 Appendix A requires that EPA-controlled structures and facilities must be constructed in accordance with existing criteria and standards set forth under the NFIP and must include mitigation of adverse impacts wherever feasible, including the use of accepted floodproofing and/or other flood protection measures. To achieve flood protection, EPA shall wherever practicable, elevate structures above the base flood level rather than filling land. In addition, the capped area may be classified as a Tennessee SWPD Class II disposal facility. If so, the substantive requirements of the SWPD rule regarding Class II disposal facilities (e.g., siting) would apply to the Site. The SWPD rule (Rule 1200-1-7) and the Criteria for Classification of Solid Waste Disposal Facilities and Practices (40 CFR 257) require that disposal facilities must not be located in a 100-year floodplain, unless both of the following can be demonstrated:

- ! Location in the floodplain will not restrict the flow of the 100-year flood nor reduce the

temporary water storage capacity of the floodplain; and

- ! The facility is designed, constructed, operated, and maintained to prevent washout of any solid waste.

Wetlands are located to the north and northeast of the facility and landfill, although these locations are not identified on NWI maps. The Protection of Wetlands Order (40 CFR 6) requires that no adverse impacts to wetlands result from a remedial action. With appropriate stormwater runoff and runoff controls, the substantive requirements of this ARAR are expected to be met. The SWPD rule requires that new landfills and lateral expansions shall not be located in a wetlands, unless the owner or operator can make the following demonstrations:

- ! the presumption of a practicable alternative that does not involve wetlands is clearly rebutted;
- ! the construction/operation of the landfill will not cause or contribute to violations of applicable State water quality standards, any applicable toxic effluent standard or prohibition under Section 307 of the CWA, and will not cause or contribute to the taking of any endangered or threatened species or result in the destruction or adverse modification of critical habitat of endangered or threatened species;
- ! the landfill will not cause or contribute to significant degradation of wetlands;
- ! to the extent required under Section 404 of the CWA or Tennessee Water Pollution Control Act, steps have been taken to attempt to achieve no net loss of wetlands (as defined by acreage and function); and
- ! sufficient information is available to make a reasonable determination with respect to these demonstrations.

The substantive requirements for stormwater discharges during construction activities as outlined by the CWA are relevant and appropriate. However, a specific NPDES permit is not required for this remedial action.

All action-specific ARARs are expected to be met. The TAPCR dust suppression and control requirements (Rule 1200-3-8) apply to earth-moving activities associated with this alternative. ARARs for the control of fugitive dust emissions would be met by applying water to roads receiving heavy vehicular traffic and to excavation areas, as necessary.

#### **2.8.6B.4 Long-Term Effectiveness and Permanence**

Under this alternative, the cap would have to be maintained to ensure that it continues to perform as designed; consequently, long-term monitoring, inspection, and maintenance would be required. The cap would be susceptible to settlement, ponding of surface water, erosion, and disruption of cover integrity by deep-rooting vegetation and burrowing animals. However, the cover would be periodically inspected, and required maintenance could be implemented.

The long-term effectiveness of capping the waste would be enhanced by selecting the proper cover design and grading layout. In addition, access restrictions such as land use controls and fencing would be required to prevent land uses that are incompatible with the Site; specifically, land uses that would compromise the cap should be precluded.

#### **2.8.6B.5 Reduction of M/T/V Through Treatment**

The primary objective of this alternative is to reduce contaminant mobility by isolating contaminants from receptor contact; contaminant volume or toxicity would not be reduced. Contaminant mobility would be reduced by installing an impermeable cap liner. The liner would eliminate surface water or precipitation infiltration and would greatly reduce contaminant migration to groundwater in conjunction with the existing clay unit beneath the Site. Consolidation and capping would isolate waste source areas and reduce contaminant mobility resulting from surface water transport and wind erosion. Contaminant mobility is expected to be reduced to an extent that would result in overall risk reduction from all pathways and exposure routes.



This alternative would meet EPA's expectation to use treatment to address the principal threats posed by a Site, as well as EPA's expectation to use containment to address low-level threats posed by a site. Based on sample results collected during previous Site investigations, 600 CY of surface soil and the 16,000 CY of stockpiled and landfilled slag would be considered "principal-threat" waste.

#### **2.8.6B.6 Short-Term Effectiveness**

The construction phase of this alternative would likely be accomplished within one field season; therefore, impacts associated with construction would likely be short-term and minimal. Short-term impacts are associated with excavation and consolidation of waste soil and slag; however, these potential, short-term impacts would be mitigated during the construction phase.

If the excavated material is dry, on-Site workers will be exposed to waste soil and slag dust during excavation and consolidation activities. Additional exposure to lead dust may occur during building structure and pavement demolition. Ingestion of dust could involve some health effects because of the high level of metals in waste soil and slag.

On-Site workers would be adequately protected by using appropriate personal protective equipment and by following proper operating and safety procedures. However, short-term air quality impacts to the surrounding environment may occur during waste consolidation and grading. Dust emissions would be monitored at the property boundaries. Fugitive dust emissions would be controlled by applying water to surfaces receiving heavy vehicular traffic or in excavation areas, as needed. A measurable, short-term impact to the surrounding area would include increased vehicular traffic and associated safety hazards, potential dust generation, and noise.

#### **2.8.6B.7 Implementability**

Construction of a geomembrane surface cap is a standard construction practice. Other than capping

low level-threat material in a floodplain, no significant construction issues are expected to be encountered.

Treatment of contaminated soil and slag is offered by numerous vendors. On-Site treatment utilizes standard construction practices and material handling equipment. No significant construction issues are expected to be encountered.

Treatment of the contaminated waste will likely increase the volume of the waste soil and slag material; however, slight volume reductions may occur when some chemical reagents are used to treat the material. Typical volume increases range from about 5 percent to as high as 100 percent, depending upon the treatment method used. An increase in the volume of the treated waste material will have an impact on the disposal volume required. Calculations used in the development of this alternative utilized a volume increase estimate of 5 percent.

All services and materials for this alternative are readily available.

#### **2.8.6B.8 Cost**

The total present worth for Alternative S-6B is approximately \$4,936,044 for Option 1, which includes the excavated wetlands sediment, and \$4,013,508 for Option 2, which does not include the wetland sediment. For Option 1, the estimated capital cost is approximately \$4,776,149, and the estimated O&M cost is approximately \$159,895. For Option 2, the estimated capital cost is approximately \$3,853,613 and the estimated O&M cost is approximately \$159,895.

### **2.9 WETLAND SEDIMENT ALTERNATIVE ANALYSIS**

The alternatives that were selected for surface soil at the RM Site include no action, institutional controls and off-Site creation of wetlands, surface water and sediment control/diversion with off-Site

creation of wetlands, composting/fixation of wetlands sediment with off-Site creation of wetlands, capping with off-Site creation of wetlands, and excavation and grading with either clean fill or composting and revegetation. **Table 2-19** is a summary of the wetland alternatives considered.

## **2.9.1 Alternative W-1 -- No Action**

### **2.9.1.1 Description**

Under this alternative, no remedial action would be taken with respect to the wetlands. A monitoring program would be implemented to address wetland sediments, surface water and associated uptake by biota utilizing the affected area. The monitoring program would be developed in order to allow for regulators to assess the migration of the contaminants from the wetlands and determine if remedial actions might be necessary in the future. The monitoring program would take place on a yearly basis with a risk evaluation conducted within 5 years to determine the effectiveness of this approach.

### **2.9.1.2 Overall Protection of Human Health and the Environment**

The no action alternative does not eliminate any exposure pathways or reduce the level of risk of the existing wetland sediment contamination.

### **2.9.1.3 Compliance with ARARs**

This alternative does not achieve the RAOs or chemical-specific ARARs established for wetland sediment. Location- and action-specific ARARs do not apply to this alternative since further remedial actions will not be conducted.

**Table 2-19**  
**Summary of Wetland Sediment Alternatives Evaluation**

Remedial Alternative	Threshold Criteria		Balancing Criteria					
	Overall Protection of Human Health and the Environment	Compliance with ARARs	Long-Term Effectiveness and Permanence	Reduction of M/T/V Through Treatment	Short-Term Effectiveness	Implementability		Cost Approx. Total Present Worth
						Technical/Engineering Consideration	Estimated Time for Implementation (years)	
1 – No Action	Does not eliminate exposure pathways or reduce the level of risk. Does not limit migration of or remove contaminants.	Chemical-specific ARARs are not met. Location- and action-specific ARARs do not apply.	The contaminated material is a long-term impact. The remediation goals are not met.	No reduction of M/T/V is realized.	Level D protective equipment is required during sampling	None	<1	\$100,247
2 – Capping w/Clean Fill and Off-Site Creation of Wetlands	Potentially eliminates multiple exposure pathways to ecological receptors. Organisms utilizing portions of the wetlands below the surface may potentially continue to be exposed.	Does not meet ARARs for protection of wetlands.	Will reduce or eliminate viable exposure pathways and prevent degradation of adjacent wetlands. No residual risks from the alternative. Long-term effectiveness requires cap maintenance	Reduction of mobility is realized but contaminant volume or toxicity are not reduced. For the principal threat waste at the Site, does not meet EPA's expectation to treat principal threat waste.	Level C and D protective equipment required during Site activities. Grading may result in potential release of dust. Noise nuisance from use of heavy equipment.	Capping in a floodplain and wetlands.	<1	\$611,762
3 A – Excavation and Revegetation/ Restoration of Wetlands and Regrading with Clean Fill	Eliminates exposure pathways and reduces the level of risk. Removes contamination and restores functional value of contaminated wetlands.	All action-specific ARARs are expected to be met. Location-specific ARARs are applicable and would need to be met.	Long-term ecological threats associated with sediment are greatly reduced. No residual risks from the alternative. Long-term effectiveness requires cap maintenance	Reduction of mobility, toxicity, and volume is achieved through removal, not treatment.	Level C and D protective equipment required during Site activities. Excavating and grading may result in potential release of dust. Short-term impacts to the wetlands from excavating activities will occur.	None	<1	\$780,071
3 B – Excavation and Revegetation/ Restoration of Wetlands and Regrading with Biosolid Compost	Eliminates exposure pathways and reduces the level of risk. Removes contamination and restores functional value of contaminated wetlands.	All action-specific ARARs are expected to be met. Location-specific ARARs are applicable and would need to be met.	Long-term ecological threats associated with sediment are greatly reduced. No residual risks from the alternative. Long-term effectiveness requires cap maintenance	Reduction of mobility, toxicity, and volume is achieved through removal, not treatment. Additionally, use of biosolid compost reduces toxicity by limiting bioavailability of contaminants.	Level C and D protective equipment required during Site activities. Excavating and grading may result in potential release of dust. Short-term impacts to the wetlands from excavating activities will occur.	None.	<1	\$699,548

#### **2.9.1.4 Long-Term Effectiveness and Permanence**

The remediation goals derived for protection of ecological receptors would not be met. Because contaminated wetland sediment remains under this alternative, a review/reassessment of the conditions at the Site would be performed at 5-year intervals to ensure that the remedy does not become a greater risk to human health and the environment.

#### **2.9.1.5 Reduction of M/T/V Through Treatment**

No reductions in contaminants M/T/V are realized under this alternative.

#### **2.9.1.6 Short-Term Effectiveness**

Since no further remedial action would be implemented at this Site, this alternative poses no short-term risks to onsite workers. It is assumed that Level D personnel protection would be used when sampling various media.

#### **2.9.1.7 Implementability**

This alternative could be implemented immediately since monitoring equipment is readily available and procedures are in place.

#### **2.9.1.8 Cost**

Minimal costs are associated with this alternative relative to other remedial action alternatives. No capital costs are associated with this alternative. The estimated O&M cost is approximately \$100,247.

## **2.9.2 Alternative W-2 – Capping with Clean Fill and Off-Site Creation of Wetlands**

### **2.9.2.1 Description**

Capping the contaminated sediment in the wetlands at the RM Site would serve to prevent rainfall infiltration and future leaching into the groundwater. In addition, capping also would limit direct contact exposure to contaminated media under the cap. Varying degrees of capping can be implemented depending on the severity of contaminants in the area. Caps can range from a simple natural soil cap to a multilayer soil/synthetic cap. For the wetlands, a foot of topsoil would be placed on the surface of the contaminated wetland sediment and graded evenly. Capping with a minimum of one foot of clean fill would be required to eliminate multiple exposure pathways as identified in the ecological risk assessment. The cap would be applied to the approximately 5.7 acres of wetlands containing sediment with lead concentrations greater than 800 mg/kg. Because this action results in a destruction of the wetlands by altering the grade and hydrology of the system, off-Site creation of wetlands is required to compensate for the loss.

Alternative W-2 would eliminate direct contact with contaminated media, minimize contaminant migration to groundwater, and eliminate contaminant migration. Land use restrictions and security fencing may be placed on the Site while the remedial action takes place. Monitoring would be required to assess the effectiveness of the remedial action.

### **2.9.2.2 Overall Protection of Human Health and the Environment**

This alternative will not remove or contain the contaminated sediments but potentially limits multiple exposure pathways to ecological receptors. Organisms utilizing portions of the wetlands below the surface may potentially continue to be exposed. The volume and concentration in the wetland will not be altered. Lead and other metals in the wetland sediment may continue to result in adverse impacts.

### 2.9.2.3 Compliance with ARARs

The RCRA hazardous waste disposal facility requirements are potentially applicable. The RM Site is located in a 100-year floodplain within a zone designated as A3, indicating that base flood elevations and flood hazard factors have been determined for this area. The ARAR (40 CFR 264) requires that disposal facilities be designed to withstand a 100-year flood. In addition, EPA's regulations (40 CFR Part 6, Appendix A) for implementing Executive Order 11988 (Floodplains Management) requires federal agencies to avoid or minimize adverse impacts of Federal actions upon floodplains, and to preserve and enhance the natural values of floodplains. Specifically, when it is apparent that a proposed or potential Agency action is likely to impact a floodplain or wetlands, the public should be informed through appropriate public notice processes. Furthermore, if a proposed action is located in or affects a floodplain or wetlands, a floodplain/wetlands assessment shall be undertaken, and a statement of findings explaining why the proposed action must be located in or affect the floodplain or wetlands.

Regarding construction activities related to implementing the alternative, 40 CFR 6 Appendix A requires that EPA-controlled structures and facilities must be constructed in accordance with existing criteria and standards set forth under the NFIP and must include mitigation of adverse impacts wherever feasible, including the use of accepted floodproofing and/or other flood protection measures. To achieve flood protection, EPA shall wherever practicable, elevate structures above the base flood level rather than filling land. In addition, the capped area may be classified as a Tennessee SWPD Class II disposal facility. If so, the substantive requirements of the SWPD rule regarding Class II disposal facilities (e.g., siting) would apply to the Site. The SWPD rule (Rule 1200-1-7) and the Criteria for Classification of Solid Waste Disposal Facilities and Practices (40 CFR 257) require that disposal facilities must not be located in a 100-year floodplain, unless both of the following can be demonstrated:

- ! Location in the floodplain will not restrict the flow of the 100-year flood nor reduce the

temporary water storage capacity of the floodplain; and

- ! The facility is designed, constructed, operated, and maintained to prevent washout of any solid waste.

The Protection of Wetlands Order (40 CFR 6) requires that no adverse impacts to wetlands result from a remedial action. With appropriate stormwater runoff and runoff controls, the substantive requirements of this ARAR are expected to be met. In addition, the off-Site creation of wetlands component of this alternative to compensate for the loss of forested and scrub/shrub wetlands is expected to meet the wetlands mitigation requirements of CWA Section 404. The SWPD rule requires that new landfills and lateral expansions shall not be located in a wetlands, unless the owner or operator can make the following demonstrations:

- the presumption of a practicable alternative that does not involve wetlands is clearly rebutted;
- the construction/operation of the landfill will not cause or contribute to violations of applicable State water quality standards, any applicable toxic effluent standard or prohibition under Section 307 of the CWA, and will not cause or contribute to the taking of any endangered or threatened species or result in the destruction or adverse modification of critical habitat of endangered or threatened species;
- the landfill will not cause or contribute to significant degradation of wetlands;
- to the extent required under Section 404 of the CWA or Tennessee Water Pollution Control Act, steps have been taken to attempt to achieve no net loss of wetlands (as defined by acreage and function); and
- sufficient information is available to make a reasonable determination with respect to these demonstrations.

The substantive requirements for stormwater discharges during construction activities as outlined by the CWA are relevant and appropriate. However, a specific NPDES permit is not required for this remedial action.



All action-specific ARARs are expected to be met. The TAPCR dust suppression and control requirements (Rule 1200-3-8) apply to earth-moving activities associated with this alternative. ARARs for the control of fugitive dust emissions would be met by applying water to roads receiving heavy vehicular traffic and to excavation areas, as necessary.

#### **2.9.2.4 Long-Term Effectiveness and Permanence**

Under this alternative, the cap would have to be maintained to ensure that it continues to perform as designed; consequently, long-term monitoring inspection, and maintenance would be required. The cap would be susceptible to settlement, ponding of surface water, erosion, and disruption of cover integrity by deep-rooting vegetation and burrowing animals. The cover would need to be periodically inspected, and required maintenance would need to be implemented in order to maintain effectiveness.

The long-term effectiveness of capping the waste would be enhanced by selecting the proper cover design and grading layout. In addition, access restrictions such as land use controls and fencing would be required to prevent land uses incompatible with the Site; specifically, land uses that would compromise the cap should be precluded.

The remedial action objectives of reduction of exposure and prevention of transport and migration of Site contaminants, and prevention of degradation of adjacent wetlands will be achieved. However, the restoration of wetland communities and elimination of further degradation of the Site wetlands will not be achieved.

#### **2.9.2.5 Reduction of M/T/V Through Treatment**

This alternative will not remove or dispose of the contamination. Contaminated sediment will be left intact but the pathway of exposure will be reduced for multiple receptors. Toxicity may be reduced by limiting bioavailability. The volume of material at the Site will not be altered.

This alternative would not meet EPA's expectation to use treatment to address the principal threats posed by a site, although in some situations, containment of principal threats is warranted (EPA 1991). Based on sample results collected during previous Site investigations, 8,700 CY of sediment would be considered "principal-threat" waste.

Containment of principal threats may be warranted where treatment technologies are not technically feasible or available within a reasonable time frame; or where the volume of materials or complexity of the site makes implementation of treatment technologies infeasible; or where implementation of a treatment-based remedy would result in greater overall risk to human health and the environment or cause severe effects across environmental media. A review of currently available technologies and Site conditions does not suggest that these situations would apply to the RM Site.

#### **2.9.2.6 Short-Term Effectiveness**

The construction phase of this alternative would likely be accomplished within one field season; therefore, impacts associated with construction would likely be short term and minimal.

On-Site workers would be adequately protected from short-term risks by using appropriate personal protective equipment and by following proper operating and safety procedures.

The wetland system would be destroyed since application of the cap will alter grade and hydrology. A measurable, short-term impact to the surrounding area would include increased vehicular traffic and associated safety hazards, potential dust generation, and noise.

#### **2.9.2.7 Implementability**

Construction of a soil cap is a standard construction practice and materials are readily available. Other than the capping of contaminated material in a floodplain and wetland, no significant

construction issues are expected to be encountered.

Army Corps of Engineers (ACOE) permits are expected to be required. Advance consultation should occur while planning the action to ensure that all involved agencies are allowed to provide input.

All services and materials for this alternative are readily available.

#### **2.9.2.8 Cost**

The total present worth for Alternative W-2 is approximately \$611,762. The estimated capital cost is approximately \$541,601, and the estimated O&M cost is approximately \$70,161.

### **2.9.3 Alternative W-3 – Excavation & Revegetation/Restoration of Wetlands**

#### **Option A - Regrading With Clean Fill**

##### **2.9.3A.1 Description**

Alternative W-3 involves the excavation of contaminated wetland sediments to a depth of one foot, and under Option A, replacing that material with clean soils. Excavated areas will be backfilled to the existing grade and revegetated according to the Wetlands Revegetation Plan developed for the RM Site wetlands (ERRT 1998). Maintenance plans to eliminate the intrusion of less desirable species and to promote success will be developed and Site monitoring would also be required. Excavated sediments would be stockpiled with contaminated surface soils and final disposition of the contaminated wetlands sediment would follow the remedial alternative selected for surface soils. Depending on contaminated levels, excavated plant material would be consolidated with excavated sediment or mulched and disposed of separately. In excavating the approximately 5.7 acres of sediment with lead concentrations greater than 800 mg/kg to a depth of one foot; approximately 9,300 CY of contaminated sediment will be generated. Approximately 8,200 CY of the excavated

sediment would be considered principal-threat waste and 1,100 CY would be considered low-level threat waste.

Treatability testing may be required to determine if pre-treatment (e.g. dewatering or stabilization) of the wetlands sediment would be required to decrease leachability of lead and improve handling characteristics of sediment prior to transport and disposal in order to implement this alternative. If pre-treatment is required, the development or selection of the process must consider the impact of the process on the wetlands community.

The revegetation of the wetlands is based on excavation of 5.7 acres where lead occurs above 800 mg/mg in sediment and which includes approximately 1.5 acres of forested and scrub/shrub wetlands. To compensate for the loss of forested and scrub/shrub wetlands; these areas will be replaced at a 2-to-1 creation-to-loss ratio. The revegetation of the wetlands is based on planting 3 acres of forested wetland and 9 acres of emergent wetlands. Forested mitigation areas would be seeded (3 lbs/acre) with a mixture of herbaceous plant species that do not form a turf and minimize competition with planted trees and shrubs. Trees and shrubs would each be planted at a density of 436 plants/acre. Emergent wetland areas would be seeded at a rate of 5 lbs/acre and planted with plugs or bare root plantings at a density of 4,840 plants/acre.

Deed restrictions may be placed on the Site while the remedial action takes place. Monitoring would be required to assess the effectiveness of the remedial action.

#### **2.9.3A.2 Overall Protection of Human Health and the Environment**

Source control of surface runoff and sediment transport will effectively eliminate a source of loading of contaminants to the adjacent wetlands. The removal of the contamination from the Site wetlands will effectively protect the environment. Removal will also reduce risk to ecological receptors.

The RAOs for reduction of risk to ecological receptors will be met and the alternative will restore the degraded wetlands' structure and function.

### **2.9.3A.3 Compliance With ARARs**

EPA's regulations (40 CFR Part 6, Appendix A) for implementing Executive Order 11988 (Floodplains Management) requires federal agencies to avoid or minimize adverse impacts of Federal actions upon floodplains, and to preserve and enhance the natural values of floodplains. In addition, EPA's regulations (40 CFR Part 6, Appendix A) for implementing Executive Order 11988 (Floodplains Management) requires federal agencies to avoid or minimize adverse impacts of Federal actions upon floodplains, and to preserve and enhance the natural values of floodplains. Specifically, when it is apparent that a proposed or potential Agency action is likely to impact a floodplain or wetlands, the public should be informed through appropriate public notice processes. Furthermore, if a proposed action is located in or affects a floodplain or wetlands, a floodplain/wetlands assessment shall be undertaken, and a statement of findings explaining why the proposed action must be located in or affect the floodplain or wetlands.

The Protection of Wetlands Order (40 CFR 6) requires that no adverse impacts to wetlands result from a remedial action. The wetlands revegetation component of this alternative includes a 2-to-1 creation-to-loss ratio to compensate for the loss of forested and scrub/shrub wetlands which is expected to meet the wetlands mitigation requirements of CWA Section 404.

The substantive requirements for stormwater discharges during construction activities as outlined by the CWA are relevant and appropriate. However, a specific NPDES permit is not required for this remedial action.

All action-specific ARARs are expected to be met. The TAPCR dust suppression and control requirements (Rule 1200-3-8) apply to earth-moving activities associated with this alternative.

ARARs for the control of fugitive dust emissions would be met by applying water to roads receiving heavy vehicular traffic and to excavation areas, as necessary.

#### **2.9.3A.4 Long-Term Effectiveness and Permanence**

This alternative provides source control and removal of contaminated sediments in the wetlands. This action would permanently remove contaminated sediments and thereby reduce risk to ecological receptors and improve water quality. The revegetation plan will restore the wetlands to a high functioning value which should support diverse ecological communities.

#### **2.9.3A.5 Reduction of M/T/V Through Treatment**

Mobility, toxicity, and volume of contaminants will be reduced through removal, not through treatment.

#### **2.9.3A.6 Short-Term Effectiveness**

The construction phase of this alternative would likely be accomplished within one field season; therefore, impacts associated with construction would likely be short-term and minimal. Short-term impacts are associated with excavation; however, these potential, short-term impacts would be mitigated during the wetlands restoration phase. The revegetation plan uses plant species which should restore the system within one growing season, thereby limiting the impacts. Controls can be implemented to reduce impacts on adjacent wetlands.

On-Site workers would be adequately protected by using appropriate personal protective equipment and by following proper operating and safety procedures. However, short-term air quality impacts to the surrounding environment may occur during waste consolidation and grading. Dust emissions

would be monitored at the property boundaries. Fugitive dust emissions would be controlled by applying water to surfaces receiving heavy vehicular traffic or in excavation areas, as needed. A measurable, short-term impact to the surrounding area would include increased vehicular traffic and associated safety hazards, potential dust generation, and noise.

Short-term impact on biological communities in the wetlands caused by excavation will be notable because of excavation of wetlands sediment. However, the goal of the wetland mitigation program is to replace lost wetland vegetation so that wetland function and values either will be present immediately following the completion of mitigation or will develop over time. In addition, a consideration of breeding seasons, and control of erosion and sedimentation in terms of scheduling activities should ease short-term impact.

#### **2.9.3A.7 Implementability**

All services and materials for this alternative are readily available. Moderate difficulty is posed by conducting operations in unstable sediment substrate. To avoid problems, excavation can be limited to dry periods. Revegetation will be performed in the spring and will require one month for completion.

#### **2.9.3A.8 Cost**

The total present worth cost for Alternative W-3, Option A is approximately \$780,071. The estimated capital cost is \$700,901. The estimated annual O&M cost is approximately \$79,170.

### **2.9.3B Alternative W-3 — Excavation & Revegetation/Restoration of Wetlands**

#### **Option B -- Regrading with Biosolid Compost Material**

##### **2.9.3B.1 Description**

Option B is similar to Option A except that excavated areas would be backfilled with a biosolid compost material rather than clean fill. The compost would serve as the fill material, a metal-binding material and as a source of fertilizer to encourage revegetation/restoration. The compost material may also serve to bind contaminated groundwater should it percolate through the wetland. As with previous alternatives, a Site monitoring program would be implemented.

As is the case for Option A, excavated sediments would be stockpiled with contaminated surface soils and final disposition of the contaminated wetlands sediment would follow the remedial alternative selected for surface soils. In excavating the approximately 5.7 acres of sediment with lead concentrations greater than 800 mg/kg to a depth of one foot; approximately 9,300 CY of contaminated sediment will be generated. Approximately 8,200 CY of the excavated sediment would be considered principal-threat waste and 1,100 CY would be considered low-level threat waste.

Treatability testing may be required to determine if pre-treatment (e.g. dewatering or stabilization) of the wetlands sediment would be required to decrease leachability of lead and improve handling characteristics of sediment prior to transport and disposal in order to implement this alternative as well as to confirm the value of using a biosolid backfill. If pre-treatment is required, the development or selection of the process must consider the impact of the process on the wetlands community.

Excavated areas will be backfilled to the existing grade and revegetated according to the Wetlands Revegetation Plan developed for the RM Site wetlands (ERRT 1998). Maintenance plans to eliminate the intrusion of less desirable species and to promote success will be developed and Site monitoring would also be required. The revegetation of the wetlands is based on excavation of 5.7



acres where lead occurs above 800 mg/mg in sediment and which includes approximately 1.5 acres of forested and scrub/shrub wetlands. To compensate for the loss of forested and scrub/shrub wetlands; these areas will be replaced at a 2-to-1 creation-to-loss ratio. The revegetation of the wetlands is based on planting 3 acres of forested wetland and 9 acres of emergent wetlands. Forested mitigation areas would be seeded (3 lbs/acre) with a mixture of herbaceous plant species that do not form a turf and minimize competition with planted trees and shrubs. Trees and shrubs would each be planted at a density of 436 plants/acre. Emergent wetland areas would be seeded at a rate of 5 lbs/acre and planted with plugs or bare root plantings at a density of 4,840 plants/acre.

Land use restrictions and security fencing may be placed on the Site while the remedial action takes place. Monitoring would be required to assess the effectiveness of the remedial action.

#### **2.9.3B.2 Overall Protection of Human Health and the Environment**

Source control of surface runoff and sediment transport will effectively eliminate a source of loading of contaminants the adjacent wetlands. The removal of the contamination from the Site wetlands will effectively protect the environment. Removal will also reduce risk to ecological receptors.

The RAOs for reduction of risk to ecological receptors will be met and the alternative will restore the degraded wetlands' structure and function.

#### **2.9.3B.3 Compliance with ARARs**

EPA's regulations (40 CFR Part 6, Appendix A) for implementing Executive Order 11988 (Floodplains Management) requires federal agencies to avoid or minimize adverse impacts of Federal actions upon floodplains, and to preserve and enhance the natural values of floodplains. Specifically, when it is apparent that a proposed or potential Agency action is likely to impact a floodplain or wetlands, the public should be informed through appropriate public notice processes. Furthermore,

if a proposed action is located in or affects a floodplain or wetlands, a floodplain/wetlands assessment shall be undertaken, and a statement of findings explaining why the proposed action must be located in or affect the floodplain or wetlands.

The Protection of Wetlands Order (40 CFR 6) requires that no adverse impacts to wetlands result from a remedial action. The wetlands revegetation component of this alternative includes a 2-to-1 creation-to-loss ratio to compensate for the loss of forested and scrub/shrub wetlands which is expected to meet the wetlands mitigation requirements of CWA Section 404.

The substantive requirements for stormwater discharges during construction activities as outlined by the CWA are relevant and appropriate. However, a specific NPDES permit is not required for this remedial action.

All action-specific ARARs are expected to be met. The TAPCR dust suppression and control requirements (Rule 1200-3-8) apply to earth-moving activities associated with this alternative. ARARs for the control of fugitive dust emissions would be met by applying water to roads receiving heavy vehicular traffic and to excavation areas, as necessary.

#### **2.9.3B.4 Long-Term Effectiveness and Permanence**

This alternative provides source control and removal of contaminated sediments in the wetlands. This action would permanently remove contaminated sediments and thereby reduce risk to ecological receptors and improve water quality. The revegetation plan will restore the wetlands to a high functioning value which should support diverse ecological communities.

#### **2.9.3B.5 Reduction of M/T/V Through Treatment**

Mobility, toxicity, and volume of contaminants will be reduced through removal, not through

treatment.

#### **2.9.3B.6 Short-Term Effectiveness**

The construction phase of this alternative would likely be accomplished within one field season; therefore, impacts associated with construction would likely be short-term and minimal. Short-term impacts are associated with excavation; however, these potential, short-term impacts would be mitigated during the wetlands restoration phase. The revegetation plan uses plant species which should restore the system within one growing season, thereby limiting the impacts. Controls can be implemented to reduce impacts on adjacent wetlands.

On-Site workers would be adequately protected by using appropriate personal protective equipment and by following proper operating and safety procedures. However, short-term air quality impacts to the surrounding environment may occur during waste consolidation and grading. Dust emissions would be monitored at the property boundaries. Fugitive dust emissions would be controlled by applying water to surfaces receiving heavy vehicular traffic or in excavation areas, as needed. A measurable, short-term impact to the surrounding area would include increased vehicular traffic and associated safety hazards, potential dust generation, and noise.

Short-term impact on biological communities in the wetlands caused by excavation will be notable because of excavation of wetlands sediment. However, the goal of the wetland mitigation program is to replace lost wetland vegetation so that wetland function and values either will be present immediately following the completion of mitigation or will develop over time. In addition, a consideration of breeding seasons, and control of erosion and sedimentation in terms of scheduling activities should ease short-term impact.

### **2.9.3B.7 Implementability**

The use of biosolid compost material to address metals contamination is an emerging technology with limited full scale application. However, all services and materials for this alternative should be readily available.

### **2.9.3B.8 Cost**

The total present worth cost for Alternative W-3, Option B is approximately \$699,548. The estimated capital cost is \$620,379. The estimated annual O&M cost is approximately \$79,170.

## **2.10 COMPARATIVE ANALYSIS OF ALTERNATIVES**

This section presents a comparative analysis of the surface soil/sediment and groundwater alternatives based on the threshold and balancing evaluation criteria. The objective of this section is to compare and contrast the alternatives.

The alternatives are presented here to give decision makers a range of potential actions that could be taken to remediate this Site. These actions include:

Soil	No Action (Alternative S-1)
	Capping (Alternatives S-2, S-3, S-4, and S-6)
	Solidification/Stabilization (Alternatives S-5 and S-6)
Wetland Sediment	No Action (Alternative W-1)
	Capping and Off-site Creation of Wetlands (Alternative W-2)
	Excavation, Regrading and Wetlands Revegetation/Restoration
	(Alternative W-3)

**Tables 2-20 through 2-21** present a summary of each remedial alternative along with ranking scores

**Table 2-20**  
**Comparative Analyses of Soil Alternatives**  
**Ross Metals Site**  
**Rossville, Tennessee**

Remedial Alternative	Criteria Reading <sup>1</sup>						Approximate Present Worth (\$)
	Overall Protection of Human Health and the Environment	Compliance with ARARs	Long-Term Effectiveness and Permanence	Reduction of M/T/V Through Treatment	Short-Term Effectiveness	Implementability	
S-1-- No Action	0	0	0	0	5	5	\$100,247
S-2 -- Capping	4	4	2	3	4	3	Opt.1-\$1,735,804 Opt.2-\$1,712,412
S-3 -- Capping With Pavement In Place	4	4	3	3	4	3	Opt.1-\$1,453,803 Opt.2-\$1,430,411
S-4 -- Capping With Construction of Above-Ground Disposal Cell	4	4	3	3	4	3	Opt.1-\$1,506,847 Opt.2-\$1,481,865
S-5A -- Excavation and Onsite Treatment With S/ S and onsite Disposal	5	4	4	5	4	3	Opt.1-\$4,907,274 Opt.2-\$4,244,992
S-5B -- Excavation and Onsite Treatment With S/S and offsite Disposal	5	5	5	5	4	4	Opt.1-\$7,477,199 Opt.2-\$6,181,160
S-6A -- Capping With Excavation & Onsite Treatment of Princ. Thrt Waste & onsite disposal	5	4	4	5	4	3	Opt.1-\$3,175,137 Opt.2-\$2,729,543
S-6B -- Capping With Excavation & Onsite Treatment and Offsite Disposal of Principal Threat Waste	5	4	4	5	4	3	Opt.1-\$4,936,044 Opt.2-\$4,013,508

<sup>1</sup>A ranking of "0" indicates noncompliance, while a ranking of "5" indicates complete compliance. Opt. 1 includes excavated wetland sediment; Opt. 2 does not.

**Table 2-21**

**Comparative Analysis of Wetland Sediment Alternatives  
Ross Metals Site  
Rossville, Tennessee**

Remedial Alternative	Criteria Rating <sup>1</sup>						Approximate Present Worth (\$)
	Overall Protection of Human Health and the Environment	Compliance with ARARs	Long-Term Effectiveness and Permanence	Reduction of M/T/V Through Treatment	Short-Term Effectiveness	Implementability	
W-1 -- No Action	0	0	0	0	5	5	\$ 100,247
W-2 -- Capping with Off-site Creation of Wetlands	3	2	2	3	3	4	\$ 611,762
W-3 A -- Excavation, Regrading with Clean Fill and Wetlands Revegetation/ Restoration	5	5	5	4	4	4	\$ 780,071
W-3 B -- Excavation, Regrading with Biosolid Compost Material and Wetlands Revegetation/ Restoration	5	5	5	5	4	3	\$ 699,548

<sup>1</sup> A ranking of "0" indicates noncompliance, while a ranking of "5" indicates complete compliance.

for each evaluation criterion. Each alternative's performance against the criteria (except for present worth) was ranked on a scale of 0 to 5, with 0 indicating that none of the criterion's requirements were met and 5 indicating all of the requirements were met. The ranking scores are not intended to be quantitative or additive, rather they are only summary indicators of each alternative's performance against the CERCLA evaluation criteria. The ranking scores combined with the present worth costs provide the basis for comparison among alternatives.

For soil, Alternatives S-2 through S-7 all rank higher than Alternative S- 1 in overall protection of human health and the environment, compliance with ARARs, long-term effectiveness and permanence, and reduction of M/T/V. The three capping alternatives, Alternatives S-2, S-3, and S-4, are ranked similarly with the exception that Alternative S-2 ranks lowest in long-term effectiveness and permanence. The two treatment alternatives receive similar ranking in all criteria with the exception Option B of Alternative S-5 ranks highest in compliance with ARARs long-term effectiveness and permanence, and implementability. A comparison of the capping alternatives to the treatment alternatives indicates that the treatment alternatives (Alternatives S-5 and S-6) rank slightly higher than the capping alternatives (Alternatives S-2, S-3, and S-4) in overall protection of human health and the environment and reduction of M/T/V, but are more costly.

For wetland sediment, both Alternatives W-2 and W-3 rank higher than Alternative W-1 in overall protection of human health and the environment, compliance with ARARs, long-term effectiveness and permanence, and reduction of M/T/V. Both options under Alternative W-3 (Excavation, Regrading and Wetlands Revegetation) rank higher than Alternative W-2 (Capping and Off-Site Creation of Wetlands) in overall protection of human health and the environment, compliance with ARARs, long-term effectiveness and permanence, and reduction of M/T/V.

EPA and the Tennessee Department of Environment and Conservation (TDEC) have cooperated throughout the RI/FS process. The State has participated in the development of the RI/FS and Proposed Plan by providing comments on planning and decision documents. EPA and TDEC are in

agreement with the selected alternatives S-5B and W-3B. Please refer to the Responsiveness Summary which contains a letter of concurrence from TDEC.

EPA received several letters from residents in the Town of Rossville which supported the selected remedy proposed by EPA. During the public meeting on November 30, 1998, town residents and local government officials expressed interest and support for the selected remedy presented by EPA. Please see the Responsiveness Summary which contains these letters and a transcript of the public meeting.

## **2.11 SELECTED REMEDY**

The EPA Selected Remedy is Source Materials Alternative S-5B and Wetlands Alternative W-3B. Based upon current information, this remedy appears to provide the best balance among the nine criteria that EPA uses to evaluate alternatives. EPA has determined that the Selected Remedy would be protective of human health and the environment; would attain the Site goals; comply with ARARs; and would be cost effective.

The Selected Remedy shall include the following:

- Demolition of most of the on-Site pavement and buildings. The main office building and the pavement immediately surrounding this building will remain on Site. The building debris, pavement, and equipment will be decontaminated by steam cleaning. The decontaminated metal debris will be taken off Site to a metal recycling facility. The equipment will be sold or donated to interested parties. All other debris will be taken off Site to a permitted disposal facility;
- Excavation of contaminated soil, landfilled slag, and contaminated wetlands sediment that exceed their corresponding cleanup standard;



- On-Site excavation areas shall be backfilled and restored to the existing grade or better. The backfill source, biosolids, may require treatability testing to confirm the value of using biosolid as a backfill;
- Stabilization/solidification/fixation of contaminated soil, stockpiled slag, landfilled slag, and wetlands sediment;
- Off-Site disposal of soils, slag, and sediment to a RCRA-disposal facility;
- Application of a layer of biosolids to the entire Ross Metals Site. Grass seeding of the facility and landfill areas; and revegetation of the Site wetlands according to the Wetlands Revegetation Plan developed by EPA, 1998.
- Development of maintenance and monitoring plan to assess the effectiveness of the cleanup action.

The total estimated construction costs associated with both alternatives are \$ 7,390,687. The estimated Operations and Maintenance costs are \$30,045. The estimated total present worth costs are \$7,420,732.

### **Performance Standards**

Demolition of most of the on-Site pavement and buildings. The main office building and the pavement immediately surrounding this building will remain on Site. Appropriate testing and any necessary decontamination of the main office building shall be performed. EPA shall have a reasonable opportunity to review and comment on the proposed sampling and decontamination program prior to implementation. The building debris, pavement, and equipment will be decontaminated by steam cleaning. The decontaminated metal debris will be taken off Site to a metal

recycling facility. The equipment will be sold or donated to interested parties. All other debris will be taken off Site to a nonhazardous disposal facility.

Soil/sediment with constituent concentrations greater than the excavation levels listed in **Table 2-22** shall be excavated and disposed in an off-Site RCRA-permitted non-hazardous waste landfill. **Figure 2-30** provides a map delineating the approximated areas where soil/sediment will be excavated based upon data obtained during the RI field investigations. An estimated 33,674 cubic yards of soil/sediment exceed the excavation standards. An estimated 16,000 cubic yards of slag exceed the excavation standards. Approximately 1,000 cubic yards of lead-contaminated buildings constitute a safety hazard. An estimated 3,700 cubic yards of demolition debris will be generated as a result of the remediation activities, of which approximately 1,500 tons of metal debris/equipment will be available for metal recycling.


Prior to excavation activities, a statistically-based sampling program shall be implemented within the areas slated for removal to further define those soils which exceed the applicable excavation standards. EPA shall have a reasonable opportunity to review and comment on the proposed statistical sampling program prior to implementation. Results of this sampling program shall be reviewed and approved by EPA prior to excavation activities.

All excavation activities shall be conducted in a manner which provides adequate short-term protection of on-Site workers, and minimizes disruptions to local businesses and adjacent residents. Air monitoring during active excavation shall be implemented for the protection of on-Site workers and to assess potential off-Site impacts. As warranted, dust and odor control measures shall be instituted to mitigate adverse impacts in the active excavation areas, haul roads and adjacent off-Site areas. An excavation confirmation sampling program shall be developed to verify that all soil, sediment, and slag have been removed to the specified excavation standards. EPA shall have reasonable opportunity to review the statistical methods employed by this confirmational sampling

Table 2-22 Excavation Standards	
Contaminant of Concern	Excavation Standard
<b>Surface Soil (mg/kg)</b>	
Aluminum	11,620
Antimony	3
Arsenic	5
Barium	505
Cadmium	7
Copper	293
Iron	16,100
Lead	400
Manganese	559
Selenium	37
Vanadium	51
<b>Subsurface Soil (mg/kg)</b>	
Lead	400*
<b>Wetlands Sediment (mg/kg)</b>	
Aluminum	8,860
Antimony	28.4 - 104
Arsenic	5.58
Cadmium	0.37 - 3.73
Copper	22.4 - 101.5
Lead	800
Mercury	ND - 0.21
Nickel	9.10
<b>Slag</b>	Since the blast slag waste has unique characteristics that make it easily identifiable, removal of the landfill area slag and stockpiled slag will be verified by visual inspection and approved by EPA or its representative.

ND - Not Detected

\* - Modeling conducted during Remedial Design may indicate a less conservative clean-up goal is sufficient for protection of groundwater.



Ross Metals Site Rossville, Tennessee CDM Federal Programs Corporation <small>A subsidiary of CDM, Inc.</small>	Excavation Contours	Figure No. 2-30 3-99
--	---------------------	----------------------------

program prior to excavation activities.

On-Site excavation shall be backfilled and restored to a condition consistent with the intended future use of the property. The backfill source must be prequalified to document its quality. Treatability testing may be required to confirm the value of using a biosolid as a backfill.

The wetlands will be revegetated according to the Wetlands Revegetation Plan (ERRT 1998). The facility area and landfill area (approximately 8 acres) will be grass seeded. Maintenance plans to eliminate the intrusion of less desirable species and to promote success shall be developed and Site monitoring will be required.

Excavated material may be stockpiled on-Site prior to off-Site transportation. All excavated material shall be transported off-Site for disposal in an approved RCRA-permitted landfill. All transportation and off-Site disposal activities shall be conducted in full accordance with all ARARs, including but not limited to, RCRA regulations. Per the requirements of Phase IV Land Disposal Restrictions (LDRs) - waste, soil, and debris classified as hazardous must be treated to Universal Treatment Standards (UTS) prior to land disposal. Treatment of these materials shall use solidification/stabilization/fixation to achieve UTS.

### **Summary of Estimated Remedy Costs**

Table 2-23 provides a cost estimate for implementing the selected remedy.

### **Expected Outcomes of the Selected Remedy**

The purpose of this response action is to eliminate and reduce risks posed by ingestion, inhalation, or direct contact with soil/sediment/slag/buildings; minimize migration of contaminants to

**Table 2-23  
Capital Costs for Selected Remedy**

**Discount Rate: 7%**

ITEM DESCRIPTION	UNITS	QUANTITY	UNIT PRICE DOLLARS	TOTAL COSTS DOLLARS
MOBILIZATION/DEMOBILIZATION	each	1	\$80,000	\$80,000
SITE DECONTAMINATION/DEMOLITION				
Building Demolition	cf	27,000	\$0.23	\$6,210
Concrete/Asphalt Demolition	sy	21,333	\$10.37	\$221,223
Building Demolition	sf	126,000	\$0.75	\$94,500
Pavement Demolition	sf	192,000	\$0.85	\$163,200
Recycling Metal Debris	ton	1,500	\$20	-\$45,000
loading and transportation	ton	1,500	\$50	
payment from recycling				
Equipment	lump sum	1	\$25,000	\$25,000
EXCAVATION				
Soil and Sediment Excavation (9,300+13,125+8,750+2,500)	cy	33,675	\$5	\$168,375
Dust Control & Placement in Staging Areas (2 water trucks - each @ \$3,500/month)	month	3	\$7,000	\$21,000
Excavation of Landfilled Slag	cy	10,000	\$2	\$20,000
Excavation Monitoring	sample	45	\$500	\$22,500
ON-SITE TREATMENT				
Treatability Study	lump sum	1	\$50,000	\$50,000
Treatment (33,675 Cy x 1.5 + 16,000 CY x 2)	ton	82,513	30	\$2,475,375
Treatment System Monitoring	sample	50	\$500	\$25,000
Off-Site Disposal of Non-hazardous Material (Assume 5% increase)	ton	86,639	\$30,000	\$2,599,160
Backfill Landfill and sub-surface areas s/Clean Fill (10,000+8,750+2,500)	cy	22,250	\$10	\$222,500
Installation of Biosolids Throughout Site	acres	14	\$12,000	\$168,000
Installation of Vegetative Cover on Facility Area	acre	8	\$2,000	\$16,000
Plant Emergent Forested Area	acre	3	\$3,500	\$10,500
Plant Forested Wetland Area	acre	3	\$5,500	\$16,500
EQUIPMENT & MATERIALS				
Erosion Control	sy	500	\$2.14	\$1,070
Health and Safety Equipment (30 people @ \$60/person/day)	day	90	\$1,800	\$162,000
Subtotal - Capital Cost				<b>\$6,523,113</b>
Engineering & Administrative (3% of Capital Cost)				\$196,693
Subtotal				\$6,718,806
Contingency (10% of Subtotal)				\$671,881
Total Construction Cost				<b>\$7,390,687</b>
Present Worth O & M Cost				\$30,045
Total Present Worth				<b>\$7,420,732</b>

**Table 2-24**  
**Operation and Maintenance Costs for Selected Remedy**

ITEM DESCRIPTION	UNITS	QUANTITY	UNIT PRICE DOLLARS	TOTAL ANNUAL COST DOLLARS	OPERATION TIME YEARS	PRESENT WORTH
Wetlands and Lawn Inspection	inspection	2/yr	\$500	\$1,000	5	\$4,100
wetlands and Lawn Maintenance						
Mowing: 8 Ac x 43,560 SF;	1,000 SF	5/yr	\$1.78	3,101	5	12,714
Fertilizing: 14 Ac x 43,560 SF	1,000 SF	2/yr	\$2.10	2,561	5	10,500
Subtotal				\$5,662		\$27,314
Contingency (10% of Subtotal				\$556		\$2,731
Total				\$6,228		\$30,045

groundwater; restore impacted wetland communities and prevent further degradation of the adjacent wetlands. The remedy shall address all soils contaminated with contaminants of concern in excess of their corresponding risk-based cleanup level. Since no Federal or State ARARS exist for soil/sediment, the action levels were determined through a Site-specific risk analysis. Remediation activities shall be monitored to ensure that clean-up levels are achieved. The Site is expected to be available for industrial/residential/recreational land use as a result of the remedy.

## **2.12 STATUTORY DETERMINATIONS**

Under CERCLA Section 121, EPA must select remedies that are protective of human health and the environment, comply with applicable or relevant and appropriate requirements (unless a statutory waiver is justified), are cost-effective, and utilize permanent solutions and alternative treatment technologies or resource recovery technologies to the maximum extent practicable. In addition, CERCLA includes a preference for remedies that employ treatment that permanently and significantly reduces the volume, toxicity, or mobility of hazardous wastes as a principal element. The following sections discuss how the selected remedy meets these statutory requirements.

### **2.12.1 Overall Protection of Human Health and the Environment**

EPA's Selected Remedy protects human health and the environment through the excavation and immobilization of lead-contaminated media followed by off-Site disposal.

Cancer risks, non-cancer risks and lead exposure to human receptors for future use at the Site will be eliminated. The exposure levels will be reduced to within EPA's acceptable risk range of  $10^{-4}$  to  $10^{-6}$  for carcinogens; below the HI of 1 for noncarcinogens; and below EPA's acceptable blood lead level of 10 ug per deciliter for lead. Protection of human health will be achieved by excavating, treating, and shipping off-Site the soils, sediments, and wastes which pose future risks to a lifetime resident, child resident, adult resident, and site worker.



Acute and chronic risks to ecological receptors are mitigated. The exposure levels will be reduced below the HI of 1 for noncarcinogens.

### **2.12.2 Compliance with Applicable or Relevant and Appropriate Requirements (ARARS)**

The selected remedy shall be in compliance with all Federal ARARS and any more stringent State ARARS. It is important to note that the Selected Remedy is the only practicable alternative outside the floodplain. Executive Order 11988 - Floodplain Management emphasizes the importance of evaluating alternatives to avoid effects and incompatible development in the floodplains; and those alternatives located in the floodplain may not be selected unless a determination is made that no practicable alternatives exist outside the floodplain. The Selected Remedy is considered a practicable alternative outside the floodplain. The selection of any other alternative would require a floodplains assessment and following methods to minimize potential harm to the floodplain.

The following ARARS will be attained by the selected remedy:

#### **Action-Specific:**

- RCRA requirements for identification, management and transportation of hazardous waste (40 CFR 261, 262 and 263).
- RCRA requirements pertaining to the land disposal of particular hazardous wastes (40 CFR 268).
- Clean Water Act exceptional quality sludge criteria (40 CFR 503) for regulating sludge and sets criteria for the safe use of sludge-derived products.

**Location-Specific**

- Protection of Wetlands and Floodplains are EPA regulations for implementing Executive Orders 11988 and 11990 (40 CFR Part 6, Appendix A).
- RCRA requirements for hazardous waste facility locations (40 CFR 264).
- Regulations Governing Solid Waste Processing and Disposal in Tennessee, Chapter 1200-1-7 establishes specific requirements for the operation and maintenance of solid waste landfill disposal sites.
- Tennessee Air Pollution Control Act, Chapter 1200-3-6 and 1200-3-8 sets nonprocess emission standards and regulates fugitive dust emissions.

**Other Criteria, Advisories, or Guidance To Be Considered (TBCs):**

- Floodplain Management Executive Order 11988 for avoiding adverse effects, minimize potential harm, and restore and preserve natural and beneficial values of the floodplain.
- Wetlands Management Executive Order 11990 for minimizing the destruction, loss or degradation of wetlands.
- Test Methods for Evaluating Solid Waste Physical/Chemical Methods, SW-846, 3<sup>rd</sup> Edition, latest update, Chapter 9.
- Methods for Evaluating the Attainment of Cleanup Standards Volume 1: Soils and Solid Media, U.S. EPA.

- Guidance for Hazardous Waste Site Investigation, EPA QA/G-4HW.

### **2.12.3 Cost-Effectiveness**

EPA's Selected Remedy is cost-effective and represents a reasonable value for the money to be spent. In making this determination, the following definition was used: "A remedy shall be cost-effective if its costs are proportional to its overall effectiveness." (40 CFR 300.430(f)(1)(ii)(D)). This was accomplished by evaluating the "overall effectiveness" of those alternatives that satisfied the threshold criteria (i.e., were both protective of human health and the environment and ARAR compliant). Overall effectiveness was evaluated by assessing three of the five balancing criteria in combination (long-term effectiveness and permanence; reduction in toxicity, mobility, and volume through treatment; and short-term effectiveness). Overall effectiveness was then compared to costs to determine cost effectiveness. The relationship of the overall effectiveness of this remedial alternative was determined to be proportional to its costs and hence represent a reasonable value for the money to be spent.

For this Site, Alternative S-1 is not cost-effective because it would not result in any reduction of the toxicity, mobility, or volume of wastes nor would it be effective in the long-term at reducing site risks in a permanent manner. Alternatives S-2, S-3, and S-4 were not considered to be cost-effective as they would not result in treatment of principal threat waste and reduction of toxicity and volume is not realized. Alternatives S-5A/B and S-6A/B were determined to be cost-effective. In evaluating the incremental cost-effectiveness of these alternatives, the decisive factors considered were the time frame required to construct the remedy, the time frame in which the remedial goals will be achieved, long-term effectiveness and compliance with ARARs. EPA believes that the additional money required to implement Alternatives S-5B merits the overall effectiveness of the remedy and represents the best value for the money to be spent.

#### **2.12.4 Utilization of Permanent Solutions and Alternative Treatment (or Resource Recovery) Technologies to the Maximum Extent Practicable**

EPA has determined that the Selected Remedy represents the maximum extent to which permanent solutions and treatment technologies can be utilized in a cost-effective manner for this Site. Of those alternatives that are protective of human health and the environment and comply with ARARs, EPA has determined that the Selected Remedy provides the best balance of tradeoffs in terms of the five balancing criteria, while also considering the statutory preference for treatment as a principal element and considering State and community preference.

The Selected Remedy treats the principal threats posed by the Site, achieving significant reductions in toxicity and mobility. Off-Site disposal will not require extensive monitoring, inspection, or maintenance for the Site as compared to the other on-Site disposal alternatives. The other alternatives considered would all require long-term monitoring, inspection and maintenance. The capping alternatives would be susceptible to settlement, ponding of surface water, erosion and disruption of cover integrity. The Selected Remedy satisfies the criteria for long-term effectiveness by removing the source materials and stabilizing lead in contaminated media.

The Selected Remedy reduces toxicity, mobility, but not volume through treatment. There are no short-term threats associated with the Selected Remedy that cannot be readily controlled. There are no special implementability issues that sets the Selected Remedy apart from any of the other alternatives evaluated. In fact, the administrative and technical issues associated with siting a landfill in a floodplain will make the other alternatives considered more difficult to implement than the Selected Remedy.

#### **2.12.5 Preference for Treatment as a Principal Element**

By treating the contaminated soils, sediment and slag through immobilization, the Selected Remedy

addresses the principal threats posed by the Site. By utilizing treatment as a significant portion of the Remedy, the statutory preference for remedies that employ treatment as principal element is satisfied.

#### **2.12.6 Five-Year Requirements**

Because this remedy will not result in hazardous substances remaining on-Site above health-based levels, a five-year review will not be required for this remedial action.

### **3.0 RESPONSIVENESS SUMMARY**

The U.S. Environmental Protection Agency (EPA) held a public comment period from November 18, 1998 to December 18, 1998. An extension to the public comment period was requested. As a result, it was extended to January 19, 1998. The public comment period was held for interested parties to comment on the Remedial Investigation/Feasibility Study (RI/FS) results and the Proposed Plan for the Ross Metals Superfund Site in Rossville, Tennessee.

The Proposed Plan included in Attachment A of this document, provides a summary of the Site's background information leading up to the public comment period.

EPA held a public meeting at 6:30 pm. on November 30, 1998 at the Rossville Christian Academy, Rossville, Tennessee to outline the RI/FS and describe EPA's proposed remedial alternative for the Ross Metals Site. All comment received during the public comment period have been considered in the final selection of the remedial alternative.

### **3.1 RESPONSIVENESS SUMMARY OVERVIEW**

During the public comment period, the Rossville community and local government officials expressed their support of the EPA Selected Remedy. Four letters by the community were received during the public comment period which supported the Selected Remedy. As evidenced in the November public meeting transcript, the community and local government officials expressed their support of the Selected Remedy during the meeting. Some of the major concerns expressed included the length of time it is taking to clean up the Ross Metals Site and the length of time it may take to negotiate with the PRPs to clean up the Site.

The PRPs submitted three different comment letters during the public comment period. In each of

these submittals, the PRPs disagreed with EPA's Selected Remedy. The main objection to EPA's Selected Remedy is off-Site disposal.

### **3.2 SUMMARY OF MAJOR QUESTIONS AND COMMENTS RECEIVED BY THE ROSSVILLE COMMUNITY**

The public comments appear in bold text and the EPA response follows.

- **EPA's Preferred Alternative, nor any of the other options, address the removal of lead-contaminated sludge from Rossville Lagoon - Cell #1.**

Comment acknowledged. EPA reviewed the waste-water treatment plant records and found sampling results from Cell #1. It was determined by the State that the sludge in Cell #1 is non-hazardous. Lead results ranged from 10 - 245 ppm. EPA's soil cleanup numbers for the Ross Metals Site are 400 ppm and 800 ppm. Lead results from the sludge are below EPA cleanup numbers.

EPA is considering the use of sludge from Cell #1 for use as backfill at the Ross Metals Site. EPA will perform comprehensive sampling of Cell # 1 to confirm the earlier lead results. Should the sludge pass appropriate lead and other criteria, EPA with the City of Rossville's permission, will use this material in the Superfund cleanup at Ross Metals. The City of Rossville would then be able to use Cell #1 in their waste-water treatment system as they deem necessary.

### **3.3 SUMMARY OF MAJOR QUESTIONS AND COMMENTS RECEIVED BY THE "GROUP"**

The Group's comments appear in bold text and the EPA response follows.

- **An RI consistent with EPA protocols (EPA/540/-G-89/004) was not conducted.**
- **EE/CA investigation did not generate data sufficient to support an adequate FS or the development of an RD.**
- **A pre-design investigation will be necessary as part of the RD stage to fill the data gaps.**
- **Existing data are not sufficient to estimate volumes of waste accurately.**

EPA disagrees with these comments. The EE/CA investigation focused on soils, slag and groundwater contamination. The EE/CA provided adequate data to support a decision for soils, slag, buildings and equipment. In addition to the EE/CA, a human health risk assessment, an ecological risk assessment which included additional soils/sediment characterization, a stabilization treatability study, a dewatering treatability study, and a biosolids treatability study were performed. The totality of this information has provided sufficient data and is consistent with the RI/FS process. As indicated in the RI/FS, additional information is needed to characterize groundwater. Volumes of waste have been accurately estimated. Graphics depicting the results of trenching operations during the November 1996 field work were inadvertently left out of the RI/FS. The graphics will be included in the next Administrative Record update. Pre-Design investigations are a routine part of the Remedial Design process.

- **The selected remedy is inconsistent with EPA policy, as defined in Land Use in Superfund Remedy Selection. Future development of the Site for residential purposes is prohibited because it is zoned light industrial. EPA should consider current zoning in the selection of remedial action levels.**

EPA does not agree with this comment. EPA has followed the Land Use Directive by considering



the information presented below.

The Site is currently zoned as general industrial. The zoning specifically states that “this district is not intended to allow uses which may be considered hazardous because of the use of, or production of, toxic or highly flammable materials.” It is important to note that Ross Metals, a secondary lead smelter, produced a hazardous waste and was located in this district.

The zoning does not prohibit residential development. The Site is currently located immediately adjacent to residences with children. The Site has been used for agriculture and a community park in the past.

The Town of Rossville has not been able to attract new industry in recent years and does not anticipate new growth patterns. The Site is also physically bound by its surroundings and location - it is located in the 100-year floodplain, adjacent to wetlands, a waste-water treatment plant, residences, and a railroad.

EPA has had discussions with local land use authorities and community members regarding future land use for the Ross Metals Site. They have strongly expressed their desire for the Site to be used in the future for the community, e.g., a park. The Town of Rossville and Fayette County officials are interested in the Town of Rossville obtaining the Site property deed.

- **EPA’s selection of a 400 ppm lead-in soil performance criterion for subsurface soil is not based on site-specific data and should instead be based upon additional studies, to be performed during the remedial design, that would determine whether 400 ppm lead leaches dissolved lead to groundwater above the action level for lead in groundwater.**

EPA acknowledges this comment and agrees that modeling conducted during the pre-design effort may indicate that a less conservative clean-up goal will be sufficient for protection of groundwater.

As indicated in the FS, a one-dimensional geochemical model was used to evaluate the migration of lead in soil beneath the smelter slag and the migration of lead below the contaminated soil near the wrecker building. The model suggested that the slag material is a potential source of contamination to groundwater. The model predicted that lead will migrate to groundwater in six years and the concentration of lead will exceed 15 ppb in 55 years. In addition, the geochemical model suggested that soils near the wrecker building are acting as a continuing source of contamination to groundwater and the lead concentration in groundwater will continue to increase unless the source is removed. Model output indicated that removal of lead to 100 ppm left a residual concentration of 3.71 ppm, which is near background levels, and predicts that a removal action level of 100 ppm would be protective of groundwater for at least 90 years. However, the conservative nature of this number, along with the uncertainty surrounding the modeling effort, make it inappropriate to use as a subsurface cleanup goal. The 100 ppm goal is based on the assumption of a 5,000 ppm surface load factor. However, the establishment of a 400 ppm risk-based surface soil clean-up goal would mean surface soil concentrations no greater than 400 ppm. With a surface soil concentration of 400 ppm, and considering the nature of contamination, clean up of subsurface soils to 400 ppm in the area of the wrecker building and track wash should allow for the protection of groundwater.

- **Have not determined conclusively whether there has been an impact to groundwater quality in the shallow aquifer resulting from the residual lead in soil or from the presence of residual slag.**

EPA agrees. Please see above comment regarding the slag and soils near the wrecker building. In addition, lead results in groundwater samples collected to date suggest that the Site has impacted groundwater quality. However, as the RI/FS indicates, recent results from MW5 do not confirm earlier (higher) sample results, and the high turbidity associated with unfiltered samples collected as the Site means the horizontal extent of contamination may be much less than the current data indicate. Further definition impact to groundwater will be completed as part of the Operable Unit No. 2 RI/FS.

- **No investigation to determine whether lead in wetlands is attributable to mobilization of dissolved lead in shallow groundwater and discharge into the wetland areas.**

EPA disagrees with this comment. As indicated in the RI/FS, primary mechanisms available for contaminant transport away from the Site are (1) transport by rainwater runoff, (2) rainwater infiltration to groundwater, and (3) windblown dust movement. Existing data in the wetlands clearly indicates the wetlands have been impacted by the Site contaminants. The Operable Unit No. 2 will provide data regarding to what extent, if any, groundwater contamination is migrating to the wetlands.

- **Remedial action objectives for surface soil containing lead and other metals should be based on exposure scenarios provided in the Risk Assessment Guidance for Superfund (EPA/540/1-89/002), and should be consistent with agency-approved cleanup goals at other secondary smelting Superfund sites in EPA Region 4, where a soil remedial action objective of 1,000 ppm has been selected (e.g., ILCO Superfund Site).**

The Risk Assessment was completed in accordance with the framework provided in the Risk Assessment Guidance for Superfund. The guidance does not provide specific site exposure scenarios to use in the completion of a site risk assessment. Cleanup goals at the Ross Metals Site are primarily a function of managing risk in consideration of site-specific characteristics, not other secondary lead smelting sites. Also note, that of the 22 sample results (within the fenced facility) illustrated on Figure 7-1 that are above 400 ppm, 18 are also above 1,000 ppm. Excavation areas and resulting volumes proposed for the various alternatives would not change because of the need to either create a sufficient excavation for on-Site disposal or adequate regrading/revegetation of the Site for off-Site disposal.

- **Selected remedy was not based on the regulatory provision that a remedial action can**

**consist of any combination of treatment, remedial action, engineering and institutional controls.**

EPA disagrees with this comment. In developing the alternatives, EPA considered a variety of technologies and process options. Please see RI/FS Section 9.0 and 10.0 which screens and evaluates technologies and process options; and develops the range of alternatives selected for the Ross Metals Site. Also, it is important to note that the Selected Remedy allows for stabilization, solidification, fixation, or composting processes. These processes may be used in any combination for the Site soils and waste to meet the land disposal regulations.

- **A floodplain assessment per OSWER Directive 9280.0-02 that requires EPA to assess the effects of proposed alternatives on floodplains and floodplain protection was not conducted as part of the EPA site investigations, nor was it considered in the FS.**

EPA acknowledges this comment. EPA believes the commenters have misunderstood the Floodplain Management Executive Order 1198. EPA's Selected Remedy will not be located in a floodplain and will therefore, not adversely effect the floodplain. An Assessment would have been necessary had the Agency chosen a remedy located in the floodplain.

- **Long-Term Effectiveness and Permanence - On-Site disposal alternative could be considered more effective because the Group will maintain specific control and management of the treated materials, whereas there would be no control for specific wastes at off-Site facilities.**

EPA disagrees with this comment. The Group proposes to maintain specific control of the treated materials by establishing a trust fund for the City to conduct O&M at the Site; yet the current status of the City's WWTP berm - as reported by the Group - has eroding banks. The Group's comment

that they will maintain specific control and then the comment that they will create a trust fund for others to implement the long-term operation and maintenance activities is a contradiction. In addition, if the Group's assertion that the preferred alternative merely transfers risks from one Site to another, then the Group's alternate remedy leaves that risk on Site, and limits rather than increases the number of options the community has in redeveloping the Site. Finally, the off-Site disposal of wastes would occur at facilities where appropriate controls are in place.

- **Short-Term Effectiveness - The short-term risk of injury or fatality to workers and community members is significant for off-Site disposal alternatives. In addition, there is an increased exposure to residents to particulates, ozone, and carcinogenic compounds known to occur in diesel fuel exhaust.**

EPA disagrees with this comment. A Site-specific Health and Safety Plan will be required before implementation of the Remedial Action. There are no short-term threats associated with the Selected Remedy that cannot be readily controlled. EPA has considered the costs for implementing dust control measures, erosion control, personal protection and off-Site disposal. Please see the cost estimates provided in RI/FS Appendix O.

- **In addition to transportation risks associated with the off-Site disposal of materials from the Site, concern exists about the future, potential long-term liabilities that would be incurred by those parties that agree to implement an off-Site disposal remedy that involves disposal of material at a facility operated and managed by an independent company.**

EPA acknowledges this comment. Pursuant to Section 107 of CERCLA, 42 U.S.C. § 9607, "any person who by contract, agreement or otherwise arranged for disposal or treatment ... " is liable as a potentially responsible party. However, mitigating factors are contemplated in Section 107 which

provides certain defenses including:

1. Act of God,
2. Act of War, and
3. An act or omission of a third party whose act or omission occurs in connection with a contractual relationship.

It appears that the Group is concerned about acts or omissions of a third party (landfill operator) who takes over custody of the waste once it is shipped off Site. In order to establish the third defense, a party must establish that (a) he exercised due care with respect to the hazardous substances concerned, and (b) he took precautions against foreseeable acts or omissions of any such third party. The risks posed by the hazardous waste in question is substantially reduced because prior to disposal the waste will be treated on Site and thereafter will be in a non-hazardous state. The act of reducing the toxicity of the contaminants is indicative of the exercise of due care. Further, if the Group carefully selects an authorized RCRA landfill that has been in operation for a respectable period of time, this should help to establish that they took precautions against foreseeable acts or omissions of the landfill operator. Regardless, some long term potential liability exists whether the waste is transported off Site or remains on Site. Given the extra precautions that will be taken and the public perception factor, disposal of the waste off Site does not necessarily pose more risk.

- **Cost - EPA's costs in the FS for off-Site disposal might be substantially underestimated. The costs for off-Site disposal will increase proportionally to the volume of material requiring transportation and disposal. The on-Site containment alternative costs do not increase directly with volume.**
- **Several on-Site disposal remedies for source materials, each of which is equally or more protective than EPA's proposed remedy, could be implemented at a lower cost than EPA's proposed remedy.**

EPA acknowledges this comment. On-Site containment alternatives are equally affected by increase in volume of material requiring disposal. The size of required excavation, amount of materials handling, and height of the required cap are all affected by volume of material requiring disposal, and therefore all affect costs. In addition, the Group's alternate remedy would include pre-design costs related to implementing a cap in a floodplain, as well as costs associated with additional engineering considerations associated with capping in a floodplain; hydrogeologic investigations to site a landfill; and long-term operations and maintenance costs into infinity.

The RI/FS report indicates that while certain onsite disposal remedies may be as effective as the preferred alternative in overall protection of human health and the environment, and could be completed at lower cost, they are not as effective as the preferred alternative in achieving compliance with long-term effectiveness, reduction in toxicity, mobility, and volume through treatment, and short-term effectiveness. Cost effectiveness is not determined merely by cost. Cost effectiveness is the costs proportionality to its overall effectiveness. Although the Selected Remedy will cost more to implement, the decisive factors considered were the time frame to implement the remedy, the time frame in which the remedial goals will be achieved, long-term effectiveness and compliance with ARARs. The additional money required to implement the Selected Remedy merits the overall effectiveness of the remedy and represents the best value for the money to be spent.

- **State Acceptance - The State would accept the alternate remedy (on Site with provisions).**
- **TDEC was prepared to approve Ross Metals request to construct an on-Site landfill while the facility was in operation.**

EPA disagrees with this comment. The commenters apparently missed portions of State and EPA

records. Ross Metals was issued a Notice of Violation for the existing disposal site on June 16, 1986. The Notice of Violation required Ross Metals to either register the Site or to close it. The facility's landfill predated RCRA Subtitle D and was therefore not subjected to its current requirements. Ross Metals chose to apply for a permit and submitted an application. As was the practice at that time, TDEC's Division Geologist conducted a preliminary Hydrogeologic Review of the Site and determined that the Site may have been suitable for a landfill. On December 20, 1988, Paul Patterson of the Memphis DSWM Office notified Ross Metals that the review of their landfill application would be suspended until the status of the slag could be determined. They filed a RCRA Part B Permit Application November 8, 1988. The Permit was never approved.

EPA disagrees with the Commenter's assertion that the State would accept the alternative remedy with provisions. As evidenced by the State's letter of concurrence, the State concurred with EPA's selected remedy. The letter is included in Appendix B.

- **The scoring approach described in the FS was used to compare the Alternative Remedial Action (ARA) and EPA's preferred remedial alternative selected in the Proposed Plan. Based on the scoring, consistent with the NCP evaluation criteria, the ARA scores higher than or equal to EPA's preferred remedial alternative for each threshold and primary balancing criterion. As a result and consistent with the NCP, on-Site placement of the treated material is the preferred remedy, which is also consistent with EPA's EE/CA, conducted in December 1997.**

EPA disagrees with this comment. Soil Alternative 6A, as presented in the FS, is the most similar to the Group's alternative remedy, with the exception of the end use of the Site. S-6A was ranked lower than the Preferred Alternative in the areas of compliance with ARARs, long-term effectiveness and permanence, and implementability. There is greater difficulty for S-6A because of capping in a floodplain. Additional ARAR requirements would need to be implemented if construction occurred



in a floodplain and siting a landfill occurred. Also, there is additional risk of leaving untreated material (low-level threat waste) on Site.

The EE/CA did not include a developed analysis of the ARAR requirements as compared to the FS. The EE/CA did not include the ecological data, treatability studies, a baseline human health risk assessment, or an ecological risk assessment. The EE/CA did not include the nine-criteria analysis as required by the NCP. The EE/CA combined with the additional studies, ARAR analysis, and nine-criteria analysis were used in the RI/FS report. The fact that the EE/CA selected remedy differs from the RI/FS selected remedy is a function of the more complete assessment that the RI/FS process requires as compared to the EE/CA process. It was during the EE/CA report preparation that the potential for selecting off-Site disposal as part of the RI/FS process became apparent. EPA recognized that the additional assessment would be necessary so that unnecessary money would not be spent performing an on-Site disposal removal, and then at a later date as a result of the remedial process, potentially performing an off-Site disposal remedy.

- **The Group's proposed alternative on-Site disposal remedy will create a public park with other environmentally beneficial features.**


EPA acknowledges this comment. EPA will support the creation of a park in addition to the Selected Remedy. EPA, DOI, and the City of Rossville are in favor of a park as future land use and will coordinate with the Group in implementing such a community benefit.

**A**



This fact sheet will provide:

- An overall review of the Site
- The results of the Remedial Investigation
- Possible health risk posed by the Site
- A summary of treatment technologies
- A summary of the Feasibility Study
- A presentation of EPA's preferred Alternative
- Announcement of Public Comment Period
- Places to get information



## PUBLIC MEETING

**DATE:** November 30, 1998  
**TIME:** 6:30 p.m.  
**LOCATION:**  
 Rossville Christian Academy  
 280 High Street  
 Rossville, Tennessee

United States  
 Environmental Protection  
 Agency

Region IV  
 61 Forsyth Street  
 Atlanta, GA 30303


Alabama, Florida, Georgia,  
 Kentucky, Mississippi,  
 North Carolina, South  
 Carolina, Tennessee

## SUPERFUND FACT SHEET

### PROPOSED PLAN FOR REMEDIAL ACTION AT THE ROSS METALS SUPERFUND SITE

Rossville, Tennessee

November 1998



## INTRODUCTION

This Proposed Plan Fact Sheet is issued to describe the alternatives that the U.S. Environmental Protection Agency (EPA) has considered for the cleanup at the Ross Metals *National Priorities List* (NPL) Site located in Rossville, Tennessee. This plan presents an evaluation of the cleanup alternatives, including the alternative preferred by EPA. The cleanup alternatives for contaminated soils, wetlands, landfill waste, and buildings are summarized in this Fact Sheet and are described in greater detail in the *Remedial Investigation (RI)* and *Feasibility Study (FS)* reports. The RI and FS reports are more complete sources of information

and are part of the *Administrative Record*. The Administrative Record consists of technical reports and reference documents used by EPA to develop the *Proposed Plan*. These documents may be found in the information repository located at the Rossville City Hall in Rossville, Tennessee.

Based on Site information, EPA has divided the Site into *Operable Units* or cleanup phases, with the source being the first Operable Unit and the ground-

Note: Words that appear in the glossary on page 10, are in *italics* the first time they appear in the body of this fact sheet.

water being the second. This has been done to begin cleanup of the contaminated source material, while continuing to evaluate potential groundwater contamination. Operable Unit No. 1 will address the contaminated soils, landfill waste, wetlands and buildings. Operable Unit No. 2 will address the potential cleanup of groundwater contamination.

The Ross Metals RI/FS was prepared by CDM Federal Programs Corporation, under contract with EPA. The alternative EPA prefers for OU #1 represents a preliminary decision, subject to public comment.

Section 117(a) of the *Comprehensive Environmental Response, Compensation and Liability Act (CERCLA) of 1980*, as amended by the *Superfund Amendments and Reauthorization Act (SARA) of 1986*, requires public notice and a brief analysis of the EPA preferred alternative for Site remediation.

EPA encourages the public to submit written comments on all alternatives presented in this plan. Please see page 9 for more information on where to submit written comments. EPA will consider public comments as part of the final decision-making process for selecting the cleanup remedy for the Site.

## **SITE BACKGROUND**

The Ross Metals Site (herein after referred to as “the RM site” or “the site”) operated as a secondary lead smelter from 1978 to 1992, during which the facility processed spent lead-acid batteries, lead dross, lead scrap, and other lead bearing material into reusable lead alloy. The 13.7 acre site is located in a rural and residential area of Rossville, Fayette County, Tennessee. An unlined landfill containing about 10,000 cubic yards (CY) of *blast slag* is located in the northern portion of the site. In addition, about 6,000 CY of stockpiled slag is stored on site in several deteriorating buildings. Lead-contaminated surface soil is located throughout the site, and lead-contaminated subsurface soil is present in isolated portions of the site.

The purpose of the Ross Metals RI/FS is to document the nature and extent of contamination to develop and evaluate remedial alternatives, as appropriate.

Results of sampling investigations were used to develop this RI/FS and show that lead-contaminated surface soil is present across the site and in the wetlands north and east of the site. Lead concentrations in most surface soil and sediment samples collected throughout the site exceeded 400

ppm. In addition, aluminum, antimony, arsenic, barium, cadmium, copper, iron, manganese, selenium, and vanadium were detected above their cleanup levels.

In addition, lead concentrations ranging from 1,000 ppm to 52,000 ppm were detected in subsurface soils in two isolated locations at the site; east of the wrecker building, and southeast of the truck wash. Blast slag samples contained total lead concentrations ranging from 18,500 to 94,800 *ppm*. Total lead and lead *leachate* concentrations in a floor wipe sample collected from the furnace and raw materials refinery building were 14,700 ppm and 574 ppm, respectively.

Sampling results of surface water samples and sediments revealed concentrations of several inorganic compounds that exceeded background concentrations. Significant inorganic contaminants included antimony, arsenic, cadmium, iron, lead, and manganese. Lead concentrations in surface water were found as high as 1,600 *ppb*. Lead concentrations in sediment were found as high as 98,100 ppm.

## **SUMMARY OF SITE RISKS**

As part of the RI/FS, an analysis was conducted to estimate the human health or environmental problems that could result if contamination at the Site is not cleaned up. This analysis, known as a Baseline Risk Assessment, focused on the current and future human health and environmental effects from long-term direct exposure to the contaminants found at the Site.

EPA has concluded that the major risks to human health at the site would be incidental ingestion of contaminated soil. The contaminant of greatest concern in these media is lead which causes well known health effects, especially in young children. At the present time, no unacceptable exposure is occurring because no one is drinking water from the contaminated aquifer and no one is in regular contact with contaminated soil.

Additional pathways were evaluated or considered, but the current and future impacts were found to be within acceptable risk levels. For example, direct contact exposure to contaminants in soil, sediment, and surface water was examined, but the risks associated with these pathways were found to be negligible. Similarly, possible exposure to surface water via inadvertent ingestion while wading and exposure to soil via inhalation to dust were examined and found to be unimportant in terms of potential health effects.

## SCOPE AND ROLE OF RESPONSE ACTION

As previously stated, this response action addresses only the cleanup of the contaminated soils, buildings, and wetlands. The cleanup of the source materials is proposed to prevent exposure to the contaminated source materials and prevent further contamination of groundwater and surface water.

The preferred alternative will address:

- Waste Slag (landfilled and stockpiled)
- Contaminated soil (in facility area and landfill area)
- Buildings
- Demolition debris (pavement)
- Contaminated sediment (in wetlands)

EPA generally expects to use treatment to address principal threats posed by a site, wherever practicable. Principal threat wastes are those source materials considered highly toxic or mobile that cannot be reliably contained or would present a significant risk to human health or the environment should exposure occur. For the Ross Metals Site, principal threat wastes would conservatively include:

- 600 cubic yards of soil
- 8,200 cubic yards of sediment
- 6,000 cubic yards of stockpiled slag
- 10,000 cubic yards of landfilled slag

Based on new information or public comments, EPA in consultation with the State of Tennessee, may modify the preferred alternative or select another response action presented in the Proposed Plan and the FS Report. The public is encouraged to review and comment on all alternatives identified.

## SUMMARY OF SOURCE MATERIAL ALTERNATIVES

This section summarizes the 6 source material alternatives that EPA evaluated.

*Institutional controls* (e.g., future land use restrictions, local zoning ordinances, or permitting requirements) and security fencing are common components to all the alternatives that include capping (S-2, S-3, S-4, S-5A, S-6A and S-6B).

The alternatives that leave contamination on Site (S-1, S-2, S-3, S-4, S-5A, S-6A, and S-6B) would involve continued monitoring of the Site. EPA would assess the risks to human health and the environment every five years.

### Alternative S-1 **No Action**

Under this alternative, no action would be taken to remedy the contaminated surface soil, slag, sediment, or other solid media.

### Alternative S-2 **Capping**

This alternative includes the demolition of most of the on-Site pavement and buildings. The main office building and the pavement surrounding this building would remain on Site, and landfilled waste would remain in place. Contaminated soil beneath the pavement would be excavated and consolidated with the stockpiled slag, pavement, and building debris. This waste material would be disposed in an on-Site excavation that would extend from the existing landfill to about 375 feet south of the landfill. This disposal area would be about 400 feet wide and 8 feet deep, although it could be enlarged somewhat if necessary. A soil cushion layer, a *geosynthetic* liner; a soil cover, and topsoil with grass seeding would be placed over the buried contaminated material. The new landfill would cover about 6.7 acres.

### Alternative S-3 **Capping with Pavement in Place**

Alternative 3 differs from Alternative 2 in that the waste is not disposed of in an excavation, but rather spread over the existing pavement and capped in place with the existing landfill. Alternative 3 includes the demolition of most of the on-Site buildings. The main office building would remain on Site, and the landfilled slag would remain in place. Contaminated soil from areas not covered by pavement would be excavated and consolidated with the stockpiled slag and building debris, and excavated wetland sediment. This material would be spread above the pavement that extends from the existing landfill to about 375 feet south of the landfill. A soil cushion layer, a geosynthetic liner, soil cover, and topsoil with grass seeding would be placed over the contaminated material. The new landfill would be about 6.7 acres.

### Alternative S-4 **Capping with Construction of /Above-Ground Disposal Cell**

Alternative 4 differs from Alternatives 2 and 3 in that waste is not disposed of in the area of the existing pavement; instead, it is consolidated over the surface of the existing landfill and capped in place. This method would result in a disposal cell approximately 17 to 18 feet high throughout the

landfill area. This alternative includes the demolition of on-Site pavement and buildings. The main office building and the pavement immediately surrounding this building would remain on Site, and landfilled slag would remain in place. Contaminated soil beneath the pavement would be excavated and consolidated with the stockpiled slag, pavement, and building debris. A soil cushion layer, a geosynthetic liner, a soil cover, and topsoil with grass seeding would be placed over the contaminated material. The new landfill would be about 2.5 acres.

#### **Alternative S-5**

##### **Excavation and On-Site Treatment with Solidification/Stabilization**

###### **Option A - On-Site Disposal of Treated Waste**

Option A for Alternative 5 includes the decontamination and demolition of most of the on-Site pavement and buildings. The main office building and the pavement surrounding this building would remain on Site. The building debris and pavement would be decontaminated by steam/pressure cleaning. Contaminated soil throughout the Site, and buried slag in the landfill would be excavated and consolidated with the stockpiled slag. Contaminants within soil and slag would be physically bound or enclosed within a stabilized mass (solidification), or chemical reactions would be induced between a stabilizing agent and the contaminant to reduce its mobility (stabilization). Solidification/stabilization treatment technologies include the addition of cement, lime, pozzolan, or silicate-based additives or chemical reagents that physically or chemically react with the contaminant. Once treated and confirmed to be nonhazardous, the soil and slag would be consolidated with the pavement debris and disposed of in an on-Site excavation. The decontaminated building debris would be taken off Site to a metal recycling facility. The on-Site disposal area would extend from the northern boundary of the existing landfill to about 700 feet south of the landfill (100 feet north of the Site entrance) and would be about 250 feet wide and 8 feet deep. A soil cover and topsoil with grass seeding would be placed over the entire Site. The new landfill would be about four acres in size.

###### **Option B - Off-Site Disposal of Treated Material**

Option B for Alternative 5 is similar to Option A in that it also consists of the decontamination of most of the on-Site pavement and buildings and on-Site treatment. The main office building and the pavement immediately surrounding this building would remain on Site. The building debris and pavement would be decontaminated by steam cleaning. The decontaminated building debris would be taken off Site to a

metal recycling facility. Contaminated soil throughout the Site, and buried slag in the landfill would be excavated and consolidated with the stockpiled slag. Contaminants in soil and slag would be treated by solidification or stabilization. Option B differs from Option A in that after treatment and confirmation that the soil is nonhazardous, the treated soil and slag would be hauled off Site to a disposal facility. A soil cover and topsoil with grass seeding would be placed over the entire site.

#### **Alternative S-6**

##### **Option A - Capping with Excavation and OnSite Treatment of Principal Threat Waste**

Alternative 6 is similar to Alternative 5 in that it also includes the excavation and treatment of contaminated material via solidification/stabilization. However, Alternative 6 differs from Alternative 5 in that treatment is limited to only that material that is considered a principal threat. As previously stated, principal threat waste includes the landfilled and stockpiled slag, and approximately 500 cubic yards of soil.

Option A for Alternative 6 includes the demolition of most of the on-Site buildings. The main office building would remain on Site. The building debris and pavement would be decontaminated by steam/pressure cleaning. Principal threat wastes would be excavated and consolidated with the stock-piled slag. Contaminants in the principal threat waste would be treated by solidification or stabilization.

Contaminated soil from areas not covered by pavement, and non-principal threat landfill soil would be excavated for and placed in an on-Site landfill along with the treated principal threat waste. This waste (and treated) material would be disposed in the excavated landfill area (450 x 250 x 5 ft. deep). A soil cushion layer, a geosynthetic liner, a soil cover, and topsoil with grass seeding would be placed over the entire site. The new landfill would be about 6.7 acres in size.

##### **Option B - Off-Site Disposal of Treated Principal Threat Waste**

Option B is similar to Option A except that treated principal threat waste is disposed in an off-Site landfill rather than being capped on Site with the low-level threat waste. Like Option A, Option B for Alternative 6 includes the demolition of most of the on-Site buildings. The main office building would remain on Site. The building debris and pavement would be decontaminated by steam/pressure cleaning. On Site contaminated soil considered principal threat waste, and

buried slag in the landfill would be excavated and consolidated with the stockpiled slag. Contaminants in soil and slag would be treated by solidification or stabilization. Contaminated soil from areas not covered by pavement, and non-principal threat landfill soil would be excavated for cement in an on-Site landfill. This low-level threat waste material would be disposed in the excavated landfill area (450 x 250 x 5 ft deep). A soil cushion, a geosynthetic liner, a soil cover, and topsoil with grass seeding would be placed over the entire Site. The new landfill would be about 6.7 acres in size.

## **SUMMARY OF WETLAND ALTERNATIVES**

This section summarizes the three wetland alternatives that EPA evaluated.

*Insitutional controls* (e.g., future land use restrictions, local zoning ordinances, or permitting requirements) are included as components for alternatives W-1 and W-2.

Each of the alternatives include a site monitoring program.

### **Alternative W-1** **No Action**

Under this alternative, no remedial action would be taken with respect to the wetlands. A monitoring program would be implemented to address wetland sediments, surface water and associated uptake by biota utilizing the affected area. The monitoring program would be developed in order to allow for regulators to assess the migration of the contaminants from the wetlands and determine if additional action is necessary. The monitoring program would take place on a yearly basis and an EPA evaluation conducted every five years.

### **Alternative W-2** **Institutional Controls and Creation of Off-Site Wetlands**

Under this alternative, a cap consisting of at least one foot of natural soil would be placed over the 5.7 acres of contaminated wetland sediment and graded evenly. The final component of this alternative is the creation of an off-Site wetlands to mitigate the loss (due to contamination) of the Site wetlands. The purpose of the off-Site creation of wetlands is to match the functional value of the Ross Metals Site wetlands where sediment is contaminated greater than 800 ppm - approximately 5.7 acres. The creation of an off-Site wetlands under this alternative would involve the determination of the functional value of the Site wetlands; acquisition of an appropriate type and

area of land to create the off-Site wetlands; and vegetation of the off-Site land to match or better the functional value of the Site wetlands.

### **Alternative W-3** **Excavation and Revegetation/Restoration of Wetlands**

#### **Option A - Regrading with Clean Fill**

Alternative 6 involves the excavation of contaminated wetland sediments to a depth of one foot, and under Option A, replacing that material with clean soils. Excavated areas will be backfilled to the existing grade and revegetated according to the Wetlands Revegetation Plan developed for the Site wetlands. Maintenance plans to eliminate the intrusion of less desirable species and to promote success would be developed and Site monitoring would also be required. Excavated sediments would be stockpiled with contaminated surface soils and final disposition of the contaminated wetlands sediments would follow the Source Material Alternative selected for surface soils. In excavating the approximately 5.7 acres of sediment with lead concentrations greater than 800 ppm to a depth of one foot; approximately 9,300 cubic yards of contaminated sediment would be generated. Approximately 8,200 cubic yards of the excavated sediment would be considered principal threat waste and 1,100 cubic yards would be considered low-level threat waste.

Monitoring would be required to assess the effectiveness of the cleanup action.

#### **Option B - Regrading with Biosolid Compost Material**

Option B is similar to Option A except that excavated areas would be backfilled with a biosolid compost material rather than clean fill. The compost would serve as the fill material, a metal-binding material and as a source of fertilizer to encourage revegetation/restoration.

As is the case for Option A, excavated sediments would be stockpiled with contaminated surface soils and final disposition of the contaminated wetlands sediment would follow the Source Material Alternative selected for surface soils. In excavating the approximately 5.7 acres of sediment with lead concentrations greater than 800 ppm to a depth of one foot; approximately 9,300 cubic yards of contaminated sediment will be generated. Approximately 8,200 cubic yards of the excavated sediment would be considered principal threat waste and 1,100 cubic yards would be considered low-level threat waste.

## EVALUATION OF ALTERNATIVES

The EPA preferred alternatives for the Ross Metals Superfund Site, operable Unit #1 is Source Materials Alternative S-5B and Wetlands Alternative W-3B. Based on current information, these alternatives provide the best balance of the nine criteria that EPA uses to evaluate alternatives. These criteria are described on the next page. The

Evaluation of Cleanup Alternatives Tables on pages 7-8 provide an analysis and comparison of the alternatives considered. The following information is regarding two of these criteria, State of Tennessee and community acceptance, that is not fully addressed on the evaluation table.

### State of Tennessee Acceptance

The State of Tennessee has assisted

EPA in the review of reports and Site evaluation. The State has tentatively agreed with the proposed remedy and is awaiting public comment before final concurrence.

### Community Acceptance

Community acceptance of the various alternatives will be evaluated during the 30-day public comment period and will be described in the Record of Decision (ROD) for the Site.

## CRITERIA FOR EVALUATING REMEDIAL ALTERNATIVES

EPA always uses the following nine criteria to evaluate alternatives identified in the Feasibility Study. The remedial alternative selected for a Superfund site must achieve the two threshold criteria as well as attain the best balance among the five evaluation criteria. The nine criteria are as follows:

### THRESHOLD CRITERIA

**Overall Protection of Human Health and the Environment:** Degree to which each alternative eliminates, reduces, or controls threats to public health and the environment through treatment, engineering methods or institutional controls.

**Compliance with Applicable or Relevant and Appropriate Requirements (ARARs):** Alternatives are evaluated for compliance with all state and federal environmental laws, and regulations and are determined to be applicable or relevant and appropriate to the site conditions.

### EVALUATING CRITERIA

**Cost:** The benefits of a particular remedial alternative are weighed against the cost.

**Implementability:** Technical feasibility (e.g., how difficult the alternative is to construct, and operate) and administrative ease (e.g., the amount of coordination with other government agencies that is needed) of a remedy, including the availability of necessary materials and services.

**Short-Term Effectiveness:** The length of time needed to implement each alternative and the risks that may be posed to workers and nearby residents during construction and implementation.

**Long-Term Effectiveness:** The ability to maintain reliable protection of public health and the environment over time once the cleanup goals have been met.

**Reduction of Toxicity, Mobility, and Volume:** Degree to which an alternative reduces (1) the harmful nature of the contaminants, (2) their ability to move through the environment, and (3) the volume or amount of contamination at the site.

### MODIFYING CRITERIA

**State Acceptance:** EPA requests state comments on the Remedial Investigation and Feasibility Study reports, as well as the Proposed Plan, and must take into consideration whether the state concurs with, opposes, or has no comment on EPA's preferred alternative.

**Community Acceptance:** To ensure that the public has an adequate opportunity to provide input, EPA holds a public comment period and considers and responds to all comments received from the community prior to the final selection of a remedial action.



EVALUATION OF SOURCE MATERIAL CLEANUP ALTERNATIVES							
Alternative	Overall Protection of Human Health and Environment	Compliance with ARARs	Reduction of Toxicity, Mobility and Volume (TMV)	Short-Term Effectiveness	Implementability	Present Net Worth (*w/wetlands)	Ranked Preferable Alternative
S-1– No Action	NO	NO	Does not affect TMV.	Does not achieve goals <sup>2</sup> ----- 0 years	Routine monitoring. Readily implemented.	\$100,247	8
S-2 – Capping	YES	YES	Toxicity and volume unchanged. Mobility significantly reduced. Does not meet expectation for treatment.	Goals achieved. Protective equipment required. Noise nuisance. ----- 6 months	Technology readily available and constructed. Capping in floodplain and wetlands	\$1,712,412 \$1,735,804*	7
S-3 – Capping with Pavement in Place	YES	YES	Toxicity and volume unchanged. Mobility significantly reduced. Does not meet expectation for treatment.	Goals achieved. Protective equipment required. Noise nuisance. ----- 6 months	Technology readily available and constructed. Capping in floodplain and wetlands	\$1,430,411 \$1,453,803*	5
S-4 – Capping with Construction of Above-Ground Disposal Cell	YES	YES	Toxicity and volume unchanged. Mobility significantly reduced. Does not meet expectation for treatment.	Goals achieved. Protective equipment required. Noise nuisance. ----- 6 months	Technology readily available and constructed. Capping in floodplain and wetlands	\$1,481,865 \$1,506,847*	6
S-5A – Excavation and On-Site Treatment with Solidification/Stabilization and On-Site Disposal	YES	YES	Toxicity and mobility virtually eliminated. Volume may increase Meets EPA expectation for treatment.	Goals achieved. Protective equipment required. Noise nuisance. ----- 6 months	Technology readily available. Moderately complex to implement. Capping in a floodplain.	\$4,244,992 \$4,907,274*	4
S-5B – Excavation and On-Site Treatment with Solidification/Stabilization and Off-Site Disposal	YES	YES	Toxicity and mobility virtually eliminated. Volume may increase Meets EPA expectation for treatment.	Goals achieved. Protective equipment required. Noise nuisance. ----- 6 months	Technology readily available. Moderately complex to implement.	\$6,181,160 \$7,477,199*	1
S-6A – Capping with Excavation and On-Site Treatment and On-Site Disposal	YES	YES	Toxicity and mobility virtually eliminated. Volume may increase Meets EPA expectation for treatment.	Goals achieved. Protective equipment required. Noise nuisance. ----- 6 months	Technology readily available. Moderately complex to implement. Capping in a floodplain.	\$2,729,543 \$3,175,137	2
S-6B – Capping with Excavation and On-Site Treatment and Off-Site Disposal Principal Threat Waste	YES	YES	Toxicity and mobility virtually eliminated. Volume may increase Meets EPA expectation for treatment.	Goals achieved. Protective equipment required. Noise nuisance. ----- 6 months	Technology readily available. Moderately complex to implement. Capping in a floodplain.	\$4,013,508 \$4,936,044*	3

Notes: <sup>1</sup> AGARS - Applicable or Relevant and Appropriate Requirement; <sup>2</sup> Goals (prevent human contact and further degradation of groundwater. )

EVALUATION OF WETLANDS CLEANUP ALTERNATIVES							
Alternative	Overall Protection of Human Health and Environment	Compliance with ARARs	Reduction of Toxicity, Mobility and Volume (TMV)	Short-Term Effectiveness	Implementability	Present Net Worth	Ranked Preferable Alternative
W-1– No Action	NO	NO	No reduction of TMV.	Does not achieve goals ----- 0 years	Routine monitoring. Readily implemented.	\$10,247	4
W-2 – Capping w/Clean Fill and Off-Site Creation of Wetlands	Potentially	NO	No reduction in toxicity of volume. Reduction of mobility. Does not meet EPA expectation of treatment.	Protective equipment required. Noise nuisance from heavy equipment. ----- 6 months	Technology readily available and constructed. Capping in flood-plain and wetland.	\$414,881	3
W-3A - Excavation and Revegetation/Restoration of Wetlands and Regrading w/Clean Fill	YES	YES	TMV virtually eliminated.	Protective equipment required. Noise nuisance from heavy equipment. ----- 6 months	Technology readily available and constructed.	\$583,189	2
W-3B - Excavation and Revegetation/Restoration of Wetlands and Regrading with Biosold Compost	YES	YES	TMV virtually eliminated.	Protective equipment required. Noise nuisance from heavy equipment. ----- 6 months	Technology readily available and constructed.	\$502,667	1

Notes: <sup>1</sup> ARARs - Applicable or Relevant and Appropriate Requirement; <sup>2</sup> Goals (prevent human contact and further degradation of groundwater. )

### EPA's PREFERRED ALTERNATIVE

The EPA preferred alternatives are Source Materials Alternative S-5B and Wetlands Alternative W-3B. Based upon current information, these alternatives appear to provide the best balance among the nine criteria that EPA uses to evaluate alternatives. EPA has determined that the preferred alternatives would be protective of human health and the environment; would attain the Site goals; comply with ARARs; and would be cost effective.

The preferred alternative consists of the following:

- Decontamination/ demolition of pavement and buildings with recycling of metal debris;
- Excavation of contaminated soil, landfilled slag, and contaminated wetlands sediment and appropriate confirmation soil sampling;
- Backfill of excavated soil areas and landfill with clean soil;
- Stabilization or solidification of contaminated soil, stockpiled slag, landfilled slag, and wetlands sediment;
- Off-Site disposal of soils, slag, and sediment at nonhazardous disposal facility;
- Application of a layer of biosolid compost to the entire Ross Metals Site. Grass seeding of the facility and landfill areas; and revegetation of the Site wetlands according to the wetlands revegetation plan developed by EPA, 1998.
- Development of maintenance and monitoring plan to assess the effectiveness of the cleanup action.

The total estimated construction costs associated with both alternatives are \$ 7,736,897. The estimated Operations and Maintenance costs are \$242,969. The estimated total present worth costs are \$ 7,979,866.

### THE NEXT STEP: THE COMMUNITY'S ROLE IN THE SELECTION PROCESS

EPA solicits input from the community on the cleanup alternatives proposed for each Superfund site. EPA has set a public comment period from November 18, 1998 through December 18, 1998, to encourage public participation in the selection process. The comment period includes a public meeting at which EPA will present the RI/FS Report and Proposed Plan, answer questions, and receive both oral and written comments.


The public meeting is scheduled for 6:30 PM, November 30, 1998, and will be held at Rossville Christian Academy in Rossville.

EPA is required to extend the comment period, for a minimum of 30 days, upon receipt of a timely request to do so. At the end of the public comment period, a summary of all the questions and comments received from the public and EPA's responses will be provided in the Responsiveness Summary. The Responsiveness Summary is included in EPA's Record of Decision (ROD), which is the document that presents EPA's final selection for Site cleanup.

The public can send written comments to or obtain further information from :

Beth Brown  
Remedial Project Manager  
U.S. EPA Region IV  
61 Forsyth Street, S.W.  
Atlanta, Georgia 30303-3104  
1-800-435-9233 or  
404-562-8814

The Proposed Plan and the RI/FS Reports have been placed in the information repository and Administrative Record for the Site. These documents are available for public review and copying at the following location:



## GLOSSARY

**Administrative Order on Consent:** A legal and enforceable agreement signed between EPA and Potentially Responsible Parties (PRPs) whereby PRPs agree to perform or pay the cost of the investigation.

**Biosolids:** Organic matter (e.g., wood ash, compost, or wastewater treatment plant sludge) that can be used with topsoil for stabilizing slopes, reducing erosion, and providing a nutrient-rich environment for vegetation.

**Blast Slag:** A by-product or waste that is generated during the lead smelting process.

**Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA):** A federal law passed in 1980 and amended in 1986 by the Superfund Amendments and Reauthorization Act. This law created a special tax that goes into a trust fund, commonly known as Superfund, to investigate and clean up abandoned or uncontrolled hazardous waste sites. Under the Superfund program, EPA can either pay for site cleanup when the responsible parties cannot be located or are unwilling or unable to perform the work, or take legal action to force responsible parties to clean up the site or reimburse EPA for the cost of cleanup.

**Feasibility Study (FS):** A Feasibility Study evaluates different remedial alternatives for site cleanup and recommends the alternative that provides the best balance of protectiveness, effectiveness, implementability, and cost.

**Geosynthetic Liner:** A man-made textile that significantly reduces rainwater from passing through its tightly woven structure of plastics and clay.

**Groundwater:** Water beneath the earth's surface that fills spaces among soil, sand, rock, and gravel. Precipitation, such as rain, reaches the ground and then slowly moves through soil, sand, gravel, and rock into small cracks and crevices below the ground surface. During a process that can take many years, groundwater has the potential of becoming a drinking water source.

**Institutional Controls:** Legal mechanisms to prevent human exposure to contamination remaining on hazardous waste sites.

**Leachate:** A contaminated liquid resulting when water percolates or trickles through waste materials and collects components of those wastes.

**Monitoring:** The continued collection of information about the environment that helps gauge the effectiveness of a cleanup action.

**National Priorities List (NPL):** EPA's list of the most serious uncontrolled or abandoned hazardous waste sites identified for possible long-term remedial action under Superfund.

**Parts Per Billion (ppb or  $\mu\text{g/L}$ ):** A unit of measurement used to describe levels of contamination. For example, one gallon of a liquid in one billion gallons of water is equal to one part per billion.

**Parts Per Million (ppm or  $\text{mg/L}$ ):** A unit of measurement used to describe levels of contamination. For example, one gallon of a liquid in one million gallons of water is equal to one part per million.

**Preferred Alternative:** EPA's selected best alternative, based on information collected to date, to address contamination at a site.

**Proposed Plan:** A fact sheet summarizing EPA's preferred cleanup strategy for a Superfund site, the rationale for the preference, and a review of the alternatives developed in the RI/FS process.

**Resource Conservation and Recovery Act (RCRA):** A law that established a regulatory system to track hazardous substances from the time of generation to disposal. Provides closure and post-closure minimum requirements for landfills.

**Record of Decision (ROD):** A public document that explains which cleanup alternative will be used at an NPL site and the reasons for choosing that cleanup alternative over other possibilities.

**Remedial Alternative:** A list of the most technologically feasible alternatives for a cleanup strategy.

**Remedial Design:** A engineering phase that follows the Record of Decision when technical drawings and specifications are developed for the cleanup action at a Superfund Site.

**Remedial Investigation (RI):** A Remedial Investigation examines the nature and extent of contamination problems at a site.

**Responsiveness Summary:** A summary of written or oral comments received by EPA during a public comment period.

**Superfund:** A term commonly used to describe the Federal program established by CERCLA.

**Superfund Amendments and Reauthorization Act (SARA):** Amendments to CERCLA enacted on October 17, 1986.

**Treatability Study:** A study to evaluate the effectiveness of a technology in remediating contamination.

***B***



STATE OF TENNESSEE  
DEPARTMENT OF ENVIRONMENT AND CONSERVATION  
MEMPHIS ENVIRONMENTAL FIELD OFFICE  
SUITE E-645, PERIMETER PARK  
2510 MT. MORIAH  
MEMPHIS, TENNESSEE 38115-1520

February 3, 1999

Ms. Beth Brown  
Remedial Project Manager  
U.S. Environmental Protection Agency  
Region 4  
61 Forsyth Street, SW  
Atlanta, GA 30303-3104

RE: Ross Metals Superfund Site (TND 09-607-0396)  
Rossville, Fayette County, Tennessee  
ELM, Inc. and Leed Environmental, Inc. Comments on proposed  
ROD  
Dated January 18, 1999

Dear Ms. Brown:

I have reviewed the copy of the comments you forwarded to this office and have some responses concerning these comments. Specifically, I will address the areas covered by the Regulations Governing Solid Waste Processing and Disposal in Tennessee, Rule Chapter 1200-1-7.

The commenters state that the facility is not in the 100 year flood plain. Additionally, they state that the Rossville POTW is not included on the FEMA flood maps. The July 5, 1983 Flood Insurance Rate Maps for Rossville and surrounding Fayette County show that this facility is in the 100 year flood plain and clearly show the Rossville POTW. Portions of the facility may have been raised above the 100 year flood, but the existing disposal area is in the 100 year flood plain. While the Tennessee Regulations do not preclude the placement of a landfill unit in the 100 year flood plain, the standard practice has been to totally remove the facility from the flood plain by constructing a levee. In no case would any facility be located in the flood way. Additionally, Rule 1200-1-7-.04(3) (a)4. requires a 200 foot buffer between a fill area and the normal boundaries of springs, streams, and lakes. The commenters claim that the proposed off-site landfills are also located in the 100 year flood plain, without a list of the proposed facilities I can not make a global assertion, however no currently operational Class I (Sanitary) landfill in Tennessee within 100 miles of this facility are located in a 100 year flood plain.

The existing on site landfill predates the RCRA Subtitle "D"

Ms. Beth Brown  
February 3, 1999  
Page 2

compliant Tennessee Regulations and is therefore not subject to them. Any new waste disposal activity would have to fully comply with the Regulations. This would include the requirements for a geologic investigation and a design that included a synthetic liner. The proposed alternate plan does not appear to include these in it's cost estimate.


Of particular concern to the Tennessee Division of Solid Waste Management is this facility's location in the recharge zone for the "Memphis Aquifer". Numerous private and public wells are located down gradient from this facility. While a geologic buffer is indicated on the bore logs for the on-site monitoring wells, the permeability of the underlying soils has not been established.

The commenters apparently missed some portions of the record. Ross Metals was issued a Notice of Violation for the existing disposal site on June 16, 1986. The Notice of Violation required Ross Metals to either register the site or to close it. Ross Metals chose to apply for a permit and submitted an application. As was the practice at that time, the Division Geologist conducted a preliminary Hydrogeologic Review of the site and determined that the site may have been suitable for a landfill. On December 20, 1988, Paul Patterson of the Memphis DSWM Office notified Ross Metals that the review of their landfill application would be suspended until the status of the slag could be determined.

Considering the sites susceptibility to inundation, the presence of wetlands, and the facility's location in the recharge zone for the Memphis Aquifer, on-site disposal of the slag, as proposed, presents the potential for harm to the public health and the environment. Specifically, the plan does not describe any liner and leachate collection system.

Should you have any questions about this letter or the Regulations Governing Solid Waste Processing and Disposal in Tennessee, please feel free to contact me at (901) 368-7948.

Sincerely,

  
\_\_\_\_\_  
John Boatright, P.E.  
Division of Solid Waste Management

JWB\79019034\ag

c: DSWM MEAC File  
DSWM NCO File  
Jordan English, TDSF/MEAC



## United States Department of the Interior

### FISH AND WILDLIFE SERVICE

446 Neal Street  
Cookeville, TN 38501

January 22, 1999

Ms. Beth Brown  
U.S. Environmental Protection Agency  
Atlanta Federal Center  
61 Forsyth Street  
Atlanta, Georgia 30303-8960

Dear Ms. Brown:


U.S. Fish and Wildlife Service (Service) personnel have reviewed the Remedial Investigation/Feasibility Study (RI/FS) for the Ross Metals Superfund Site in Rossville, Fayette County, Tennessee. We have been actively involved with wetland and ecological risk issues regarding this site and commend the Environmental Protection Agency (EPA) for its close coordination with this office and Service representatives in Edison, New Jersey.

The Service supports the preferred Source Materials (S-5B) and Wetlands (W-3B) alternatives for remediation of contamination at the site. Based on the comments presented by the representatives of the primary responsible parties (PRPs) at the January 19<sup>th</sup> meeting in Atlanta, we could, if necessary, also consider other alternatives for the final disposition of lead contaminated soil and sediment. If engineering studies suggest that on-site disposal of excavated soil and sediment is feasible, potential additional wetland impacts should be fully evaluated and mitigated. Since only a conceptual site restoration plan was offered by the PRP's representatives, we recommend that a detailed wetland mitigation, restoration, and monitoring plan for all excavation and potential disposal areas be developed. This plan should consider and incorporate the technical information previously provided by Roy F. Weston, Inc. (U.S. EPA Work Assignment No.: 2-284) and the U.S. EPA Environmental Response Team Center, as well as any field data subsequently generated during hydrogeological studies of the Ross Metals site. A final plan should then be included in an appropriate decision document and provided to this office for further review.



We appreciate the opportunity to comment. Upon receipt of a ROD, the Service will evaluate the effectiveness of the proposed remedy and whether a covenant not to sue for damages to Service trust resources is appropriate. Should you have any questions or need technical assistance regarding wetland issues at the site, please contact Steve Alexander of my staff at 931/528-6481, ext. 210.

Sincerely,



for Lee A. Barclay, Ph.D.  
Field Supervisor

xc: James H. Lee, DOI, Atlanta  
Nancy Finley, FWS, Edison, New Jersey  
Allen Robison, FWS-ES, Atlanta  
Patricia Cortelyou-Hamilton, DOI, Atlanta



**STATE OF TENNESSEE  
DEPARTMENT OF ENVIRONMENT AND CONSERVATION  
MEMPHIS ENVIRONMENTAL FIELD OFFICE  
SUITE E-645, PERIMETER PARK  
2510 MT. MORIAH  
MEMPHIS, TENNESSEE 38115-1520**

March 31, 1999

Ms. Beth Brown  
Environmental Project Manager  
United States Environmental Protection Agency  
Region IV, Waste Management Division  
61 Forsyth St.  
Atlanta, GA 30303

Re: Concurrence for the Record of Decision for the Ross Metals site, Rossville, Fayette County, Tennessee, April 1999,  
TDSF #24-501.

Dear Ms. Brown:

The Tennessee Division of Superfund (TDSF) has reviewed the draft Record of Decision for the Ross Metals site, Kossville, Fayette County, Tennessee, received in this office on March 16, 1999.

The Tennessee Department of Environment and Conservation (TDEC) is in concurrence with this ROD. The level of cooperation that has occurred among all agencies with regard to this site has been extremely good. TDEC is hopeful that this cooperation will serve as a model for future relationships between the State Of Tennessee and EPA.

Sincerely,

James W. Haynes, Director  
Tennessee Division of Superfund

C: TDSF, NCO file  
TDSF, DAC-M file

*C*

February 9, 1999

Cindy Gibson  
Community Involvement Coordinator  
North Site Management Branch  
United States Environmental Protection Agency  
Region 4  
Atlanta Federal Center  
61 Forsyth Street  
Atlanta, Georgia 30303-8960


Dear Cindy:

Enclosed please find the transcript of the U.S. Environmental Protection Agency's public meeting on November 30, 1998, at the Rossville Christian Academy in Rossville, Tennessee.

I have made the few corrections that you requested that I make and am returning this copy to you. Since the time of this hearing, I have received and updated my computer software. This new update changed the format of my programming, and therefore changed the page layout of this transcript. Because of this I have gone ahead and reprinted the entire transcript rather than just the few pages that needed corrections. I draw your attention to this simply because you are still in possession of the original transcript, and the pages will no longer match.

I hope this transcript now meets with your approval and will serve the purposes for which you had it recorded. If I can be of any further assistance to you, please feel free to contact me.

Sincerely,

A handwritten signature in cursive script, appearing to read "Debra A. Dibble".

Debra A. Dibble  
Alpha Reporting Corporation

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25

EPA SUPERFUND SITE  
  
ROSS METALS, INCORPORATED  
  
ROSSVILLE, TENNESSEE  
  
at the Rossville Christian Academy

November 30, 1998

ALPHA REPORTING CORPORATION  
**Debra A. Dibble, C.S.R., R.P.R.**  
Suite 210-A - 100 North Main Building  
Memphis, TN 38103  
(901) 523-8974

1	P R O C E E D I N G S	
2	MS. BARRETT: EPA is going to present a brief	18:32:33
3	history about the site, findings from the remedial	18:32:33
4	investigation, and the various options for cleaning up the	18:32:36
5	soil and the wetland area here at the site.	18:32:41
6	My name is Diane Barrett. I'm a community	18:32:43
7	involvement coordinator with EPA.	18:32:46
8	Cindy Gibson is the community involvement	18:32:49
9	coordinator for this site, and usually -- she is on an	18:32:51
10	extended holiday with her family, so she'll be back to the	18:32:56
11	office soon.	18:32:57
12	I would like to, first of all, introduce you to EPA	18:32:59
13	participants.	18:33:03
14	Beth Brown. If you'll stand, please. She is the	18:33:03
15	site project manager.	18:33:08
16	Harold Taylor, he is the chief of the	18:33:10
17	Kentucky/Tennessee section in Atlanta.	18:33:11
18	Marlene Tucker. She is the attorney for the site.	18:33:16
19	And Andy Hey, who's a paralegal specialist also	18:33:18
20	working on the site.	18:33:23
21	So we thank you both -- all of you.	18:33:25
22	Are there any officials with us tonight?	18:33:26
23	I guess there is. Thank you for being here.	18:33:27
24	Are there any other officials? Quite a few I	18:33:31
25	I don't know. City and county officials.	18:33:36

1	AUDIENCE: Curry Morris.	
2	MS. BROWN: Let's point out one thing. We do have	18:33:42
3	a court reporter, so she's recording everything that's said	18:33:44
4	at the meeting, so that if at any point you'd like to review	18:33:48
5	what's been said at the meeting, you can.	18:33:51
6	So we just ask that if you do speak, that you bear	18:33:52
7	in mind we're trying to record it.	18:33:58
8	MS. BARRETT: I was going to say that, but further	18:34:00
9	on down. You beat me to it. But I should have said it	18:34:02
10	earlier.	18:34:05
11	Other Officials?	18:34:06
12	AUDIENCE: I'm Ken Spencer, Alderman.	18:34:09
13	AUDIENCE: Ben Farley, Alderman.	
14	MS. BARRETT: Also, we have Sally Spencer here in	18:34:21
15	the community.	18:34:27
16	Representing from the state? State people?	18:34:47
17	AUDIENCE: Phil Davis.	
18	MS. BARRETT: Anybody else? That's got all of	18:34:56
19	these people, and then all interested citizens that are	18:35:00
20	here. We welcome you and thank you for coming. Thank you	18:35:02
21	very much for coming. This is an important meeting.	18:35:06
22	In order to help me relay to you, and I'm not --	18:35:08
23	Is this anyone's first time to attend a meeting?	18:35:15
24	All right, let's just cut to the chase.	18:35:21
25	As you entered the room tonight, I hope you all	18:35:22

1	got your information, got a fact sheet. it's what we're	18:35:24
2	going to be discussing.	18:35:30
3	Also, this packet is what Beth is going to be	18:35:30
4	reviewing with everyone, so this will help you follow along.	18:35:30
5	It makes good night-time reading.	18:35:36
18	And then we have information on capping and	18:35:38
7	immobilization. These are two of the alternatives that are	18:35:41
8	being considered.	18:35:44
9	And then lastly, is what is a superfund process.	18:35:45
10	And so that's kind of what I'm going to go through real	18:35:50
11	quickly with you.	18:35:52
12	Also, as Beth did say earlier, this is an official	18:35:53
13	meeting, and it is being recorded by our court reporter, so	18:35:59
14	as we speak, if you would, when it comes to the question and	18:36:02
15	answer period, if you'd just give your name so that she can	18:36:04
16	make sure she gets it accurately.	18:36:07
17	A transcript will be made of this meeting and	18:36:09
18	placed in the repository. And usually we'll get that back	18:36:12
19	about 14 working days -- 10, 14 working days, and it will be	18:36:16
20	placed in the repository for you to look at.	18:36:19
21	Right now, we are -- you can't see this real good,	18:36:23
22	but we are right here in the public comment period area.	18:36:26
23	And after the public -- after this meeting tonight, the	18:36:31
24	proposed planning meeting, we will take all of the comments	18:36:37
25	from this public comment period, which is from November the	18:36:40



1	18th through December the 18th. All comments received	18:36:44
2	tonight, and in writing, a responsiveness summary will be	18:36:48
3	prepared which will address all of the comments we received.	18:36:51
4	And this responsiveness summary will also be placed in the	18:36:55
5	official document which is called the record of decision.	18:36:59
6	And once that has been completed, then we will, at	18:37:04
7	that time, start renegotiations with the potential	18:37:07
8	responsible parties, and see who will, EPA or they, will pay	18:37:12
9	for and conduct the rest of the process, which is the design	18:37:18
10	and the actual physical construction of whatever treatment	18:37:22
11	process we anticipate having.	18:37:26
12	During this time, during the process of selecting a	18:37:29
13	remedy, we always have to make sure it is, first of all,	18:37:36
14	protective, efficient, implementable, and cost effective for	18:37:38
15	handling all of the contamination at the site.	18:37:44
16	These, the steps that we have remaining, will take	18:37:48
17	about maybe twelve plus months, so it will be maybe the year	18:37:51
18	2000, a little after the first of the year 2000 that actual	18:37:56
19	cleanup activities might occur at this site. And so Beth	18:38:01
20	will go into that more as a projection, but at this time,	18:38:03
21	that's kind of an estimate.	18:38:09
22	And that about concludes what I've got to say as far as	18:38:12
23	community relations.	18:38:17
24	As this chart indicates, community relations	18:38:17
25	activities happen throughout the event. This is a process.	18:38:20

1	The information repository is housed there in the city hall,	18:38:26
2	so all of the documents should be in there as they are	18:38:30
3	developed.	18:38:32
4	We're holding public meetings, presenting fact	18:38:33
5	sheets.	18:38:37
6	Another thing that will occur is that once the	18:38:37
7	process has been collected, the record of decision has been	18:38:40
8	signed, then we will have a notice in the newspaper	18:38:44
9	announcing that collection, and it will be based on all of	18:38:46
10	the data that we have, all of the comments, you know. That	18:38:49
11	will be how we will select the technology.	18:38:54
12	I guess that's it.	18:39:00
13	Are there any comments or questions at this point?	18:39:01
14	Okay. I thank you for your attention. I will turn it	18:39:05
15	over to Beth now. And as she said, when you do get ready to	18:39:08
16	voice your comments, please speak up so our court reporter	18:39:14
17	can hear. Thank you.	18:39:17
18	MS. BROWN: Well, thanks for coming tonight. I know	18:39:20
19	it's probable tough to get back in the swing of things after	18:39:22
20	Thanksgiving.	18:39:24
21	It's been a long time getting to this point in the	18:39:27
22	process, and I'm pleased to say that we're at the decision	18:39:30
23	point. And we'd like you to comment on it if you have any	18:39:33
24	comments at all. Like Diane said, there's information over	18:39:37
25	at city hall.	18:39:40

1	There's probably, I don't know, five or six	18:39:42
2	volumes like this worth of information, and I'm going to try	18:39:48
3	and condense it down at about the next ten minutes. I don't	18:39:51
4	want to overwhelm you tonight. I gave you a lot of	18:39:55
5	information at the last meeting, that has some of the data	18:39:58
6	results. Tonight is just going to be a real brief overview	18:40:00
7	of how we got here.	18:40:04
8	Tonight I'd like to focus more on what the cleanup	18:40:05
9	alternatives are. So this is basically what I'll be	18:40:09
10	covering. The site history, what EPA has done to date,	18:40:13
11	brief summary of the sampling results, what kind of cleanup	18:40:17
12	alternatives we've come up with, and probably what you guys	18:40:22
13	want to know most, when we're going to actually move some	18:40:25
14	dirt.	18:40:27
15	You folks probably know the operational history as well	18:40:30
16	or better than I do. It started operating in 1978 through	18:40:34
17	1992. It's my understanding that they formed a -- or	18:40:42
18	administratively dissolution?	18:40:45
19	MS. TUCKER: The company was actually	18:40:47
20	administratively dissolved. And basically when a company	18:40:47
21	violates a corporate law of the state, the state	18:40:54
22	administratively dissolves the corporation, so it's -- it	18:40:59
23	was involuntarily dissolved, not voluntarily dissolved.	18:41:02
24	MS. BROWN: And I don't mind questions in between	18:41:07
25	if you do have them, so just let me know.	18:41:09

1	Ross Metals actually was producing an alloy that they	18:41:13
2	later sold, and in doing so they accepted wastes from other	18:41:19
3	industries as well as automotive batteries.	18:41:20
4	So far EPA has performed two removal actions, the first	18:41:29
5	one was in 1994-1995, where a pretty large volume of	18:41:37
6	hazardous wastes were removed from the site, and some	18:41:42
7	temporary security measures were taken.	18:41:45
8	At the last meeting in the spring, some of the	18:41:47
9	citizens voiced concerns, and appropriately so, that they	18:41:48
10	wanted -- we had temporarily stored all of the waste, the	18:41:54
11	slag, blast slag in the buildings. And since then the	18:41:56
12	buildings were falling down, they were deteriorating, and	18:41:59
13	they also wanted some additional security measures.	18:42:03
14	It was pointed out that people were actually	18:42:09
15	breaking in the property, for what reason we don't know.	18:42:11
16	So in the summer we actually put up additional	18:42:13
17	fencing and we covered the wastes with tarps, another	18:42:18
18	temporary measure until we take our final action.	18:42:21
19	We've actually conducted at least three or four	18:42:31
20	investigations in the last three years. We've collected	18:42:35
21	soil samples, sediment samples, ground water, surface water.	18:42:38
22	We've done a lot of laboratory evaluations to find out	18:42:44
23	whether or not the contaminants out there would pose a risk	18:42:47
24	to the bugs and critters out there.	18:42:50
25	We also have to do human health risk assessments	18:42:53

1	to determine whether or not there would be an impact to	18:42:55
2	human beings should they come in contact with the waste, or	18:42:58
3	the soils.	18:43:01
4	That's about it.	18:43:06
5	Wipe samples. We actually took samples from the	18:43:07
6	building by just taking a cloth and wiping the buildings and	18:43:10
7	then analyzing that.	18:43:13
8	So that's about it.	18:43:15
9	So as a result of our investigation, EPA's determined	18:43:23
10	that we've got a lot of contaminated media out there. The	18:43:30
11	slag, about 16,000 cubic yards, surface soil about 32,000	18:43:33
12	cubic yards. Very small amount of subsurface soil. The	18:43:36
13	buildings are obviously contaminated, and we've got a lot of	18:43:41
14	construction debris out there that we need to take care of.	18:43:45
15	Ground water, the data has been misleading. We're not	18:43:48
16	sure that we even have a ground water problem.	18:43:51
17	Unfortunately, we're going to split that out.	18:43:55
18	We're going to go ahead and take an immediate action, or an	18:43:59
19	action on the solid medias, all of these, slag, soils,	18:44:01
20	buildings, and demolition debris. In the meantime, we'll go	18:44:06
21	ahead and collect additional ground water data.	18:44:09
22	We decided to look at the site in two ways. The source	18:44:23
23	materials, which are what's out on the actual asphalt and	18:44:28
24	concrete pad where the buildings are, and the wetland	18:44:31
25	sediments is another issue. And so we determined that the	18:44:36

1 most appropriate alternatives to consider are capping; 18:44:39  
2 excavation; immobilization, which is basically just 18:44:44  
3 solidifying it with a type of cement; and disposal, which is 18:44:48  
4 either on site or off site. 18:44:53

5 We're actually required to look at a no action 18:44:56  
6 alternative, just to give us a comparison of whether the 18:44:58  
7 site poses a risk if we don't do anything verses if we do, 18:45:02  
8 you know, one or some of these type of technology. 18:45:07

9 Wetland sediments. We considered certain types of 18:45:11  
10 surface water diversion, sediment control to keep the water 18:45:15  
11 from going into the wetlands and letting them dry up. We 18:45:21  
12 looked at capping it, excavating it, treating it with some 18:45:24  
13 type of solidification, or mitigation is a term that's used 18:45:27  
14 for when you contaminate a wetlands. EPA requires that you 18:45:33  
15 either restore that wetlands on site, or you have to go 18:45:40  
16 somewhere else and create a brand new wetlands. 18:45:42

17 And it's some ratio depending on how important 18:45:46  
18 that wetlands is. If it's a really important wetland you 18:45:51  
19 might have to, say, if you have five acres of contaminated 18:45:53  
20 wetland, you may have to buy 15 acres somewhere else and 18:45:55  
21 revegitate it with all of these wetland type of plants. So 18:46:04  
22 it gets into a more expensive option when you get into 18:46:04  
23 off-site mitigation. 18:46:07

24 In your handout there's actually some pictures of what 18:46:17  
25 some of these alternatives look like. And actually, there 18:46:22

1	are pictures of all of them except for 5-B.	18:46:27
2	I'm trying to find my handout. Here it is.	18:46:30
3	The first one is, you know, the no action, which,	18:46:32
4	again, EPA requires us to evaluate, for really a comparison	18:46:35
5	purpose.	18:46:40
6	The second one is capping. And if you'll look at your	18:46:41
7	handout. And mine, of course, are not in order.	18:46:45
8	AUDIENCE: 10-10.	
9	MS. BROWN: Yeah. The first capping, the S-2.	18:47:02
10	The capping alternative really looks at leaving everything	18:47:07
11	in place as it is now, and just capping over it with a type	18:47:11
12	of soil and clay, and then revegetating it so it would	18:47:16
13	prevent, you know, contact with what's there, but the waste	18:47:21
14	remains there in place.	18:47:26
15	The next alternative is capping with pavement in place,	18:47:27
16	and on this alternative, as you can see, we would go in and	18:47:34
17	excavate some of the surface soils and then compile it all	18:47:37
18	back on the landfill -- and where the pavement exists now,	18:47:42
19	and build a cap over that. So you end up with a cap that's	18:47:47
20	about five feet above ground, and it's about 600 feet long,	18:47:52
21	verses the first alternative, which was about eight feet	18:47:58
22	tall and about 375 feet long.	18:48:02
23	The next alternative looks at excavating all of the	18:48:12
24	surface soil, and then piling it up on the back part of the	18:48:15
25	property, which is the landfill area, so you actually end up	18:48:20

1	with a pretty tall disposal cell, about 15 feet. But the	18:48:23
2	advantage of that is you end up with only a disposal cell	18:48:30
3	that's about 200 feet long, 400 feet wide.	18:48:34
4	Alternative 5a and 5b involve treatment with	18:48:49
5	solidification or stablization. And again, solidification	18:48:55
6	and stabilization is basically adding some kind of additive	18:49:00
7	that will chemically or physically bind the contamination so	18:49:03
8	that it's no longer mobile. It looks like a big concrete	18:49:09
9	mass.	18:49:14
10	And we evaluated it for disposing of that. Everything	18:49:18
11	on site, the soils, the sediments and waste, we would treat	18:49:27
12	it and leave it on site, or treat it and ship it off site.	18:49:30
13	And the last alternative 6, a and b, involves treating	18:49:39
14	the waste that poses the most risk, and shipping it off	18:49:44
15	site, which is option b, or leaving the treated principal	18:49:50
16	waste and leaving it on site.	18:50:02
17	So all of these alternatives either involve capping it	18:50:05
18	and not treating it, or treating it and capping it, or	18:50:07
19	treating and shipping it off.	18:50:12
20	AUDIENCE: Do we have a picture of 5b?	18:50:29
21	MS. BROWN: No. Because everything is gone.	18:50:32
22	Everything is treated and shipped off. The buildings, the	18:50:36
23	demolition debris, the pavement, it's all shipped off.	18:50:39
24	AUDIENCE: It's not hazardous to ship it?	18:50:42
25	MS. BROWN: We hope to achieve that so that the	18:50:45



1 cost will go down, because if you don't treat it you still 18:50:47  
2 have a hazardous waste. Number one, it's expensive, and 18:50:52  
3 it's difficult to ship it off. We have requirements when 18:50:54  
4 you treat it to reach certain levels. 18:50:57

5           Unfortunately, I didn't make an overhead of the 18:51:05  
6 comparative analysis. Does everybody have a copy of this? 18:51:09

7           This is action where we look at the criteria that EPA 18:51:14  
8 is required to in order to evaluate the different 18:51:19  
9 alternatives. 18:51:23

10           Is everybody there? 18:51:29

11           As Diane pointed out, in order for EPA to select an 18:51:33  
12 alternative, first it has to be protective of human health 18:51:37  
13 and the environment, and secondly, it needs to comply with 18:51:42  
14 all of the laws and regulations, because if it doesn't, we 18:51:42  
15 have to do a waiver, and we prefer not to do that. We 18:51:46  
16 prefer to comply with all of the laws and regs. 18:51:50

17           Then we look at whether or not it reduces the toxicity 18:51:53  
18 and mobility or volume of the waste, which is EPA's 18:51:55  
19 preference. And some of these don't effect the toxicity, 18:51:59  
20 volume, or the mobility. Some do parts of it, some do all 18:52:03  
21 of it. 18:52:09

22           And then we have to look at short-term effectiveness. 18:52:11  
23 You know, how does it affect the workers? Can we control it 18:52:14  
24 from negatively affecting the workers? How quickly can we 18:52:18  
25 reach our clean up goals? We look at the implementability. 18:52:23

1	Is this a difficult technology to implement, or is it fairly	18:52:31
2	easily, you know, fairly easy to obtain. And we also look	18:52:34
3	at the cost.	18:52:38
4	And for some reason, I don't know if I ran out of	18:52:39
5	room on this table, we also look at the long-term	18:52:43
6	effectiveness, which is, you know, in the long term, you	18:52:45
7	know, how much is it going to cost us to keep looking at	18:52:48
8	this remedy. Or if we shipped everything off, we don't have	18:52:52
9	any costs.	18:52:55
10	And then the ranking is based on criteria. These	18:52:57
11	criteria and how the contractors are viewed, the	18:53:04
12	alternatives with respect to each of these criteria. You	18:53:09
13	can come up with your own method of ranking the criteria,	18:53:12
14	okay? This is somewhat subjective.	18:53:16
15	We've chosen alternative 5b for the source materials.	18:53:22
16	We feel like it provides the best balance of the nine	18:53:27
17	criteria.	18:53:32
18	It's a technology that's fairly common. It removes the	18:53:32
19	problem. There is no monitoring requirements. And the cost	18:53:37
20	of it to physically go out there and remove everything is	18:53:43
21	about 7.4 million.	18:53:48
22	Okay.	18:53:54
23	AUDIENCE: The next closest to that is about two	18:53:55
24	million less?	18:53:58
25	MS. BROWN: Which one are you looking at?	18:54:00

1	AUDIENCE: 5a, 6a, and 6b.	
2	MS. BROWN: Right.	18:54:07
3	AUDIENCE: So all four of them achieve the goals?	18:54:07
4	MS. BROWN: Correct.	18:54:08
5	AUDIENCE: The two and a half million more to haul	18:54:08
6	it off site?	18:54:11
7	MS. BROWN: Correct. So it gets into how	18:54:12
8	important is it to remove everything, verses contain it on	18:54:14
9	site.	18:54:19
10	AUDIENCE: How much would the monitoring cost,	18:54:21
11	say, over 20 years?	18:54:24
12	MS. BROWN: I think we came up with about 200,000.	18:54:24
13	AUDIENCE: So 20 years of monitoring for 200,000?	18:54:27
14	MS. BROWN: Right.	18:54:31
15	AUDIENCE: Two and a half million to haul it off?	18:54:31
16	MS. BROWN: Correct.	18:54:33
17	You have some other problems, and that's the	18:54:33
18	plain issue and the wetland issue. I didn't mention this,	18:54:35
19	but that whole site is in a 100-year flood plain, and most	18:54:41
20	of these alternatives are going to involve construction in a	18:54:43
21	flood plain, which the Corps of Engineers and FEMA are not	18:54:47
22	advocating any more at all.	18:54:55
23	And actually, we had a lot of discussions with	18:54:55
24	them about what we would have to do on this site to meet the	18:54:57
25	requirements.	18:55:04

1           Anything we do out there is going to have to be 18:55:0  
2 flood proof. It's going to have to be built a foot above 18:55:0  
3 the base flood elevation. 18:55:1

4           We also have the problem of it being a wetlands. 18:55:1  
5 We've already contaminated a wetlands, and if we leave it 18:55:1  
6 there contaminated, we're going to have to go off site and 18:55:1  
7 create a new wetlands. 18:55:2

8           And EPA has a preference for one, not building in 18:55:2  
9 a flood plain. It's actually a policy, on building in a 18:55:2  
10 wetland. 18:55:3

11           MR. TAYLOR: I just want to add something to that. 18:55:3

12           States learned from other sites that the soils in 18:55:3  
13 the area, most of west Tennessee, erodes very easily. And 18:55:4  
14 caps, anything above grade, which is basically anything 18:55:4  
15 above ground surface down there at Ross Metals is going to 18:55:5  
16 erode. There is a lot of costs associated with that. 18:55:5

17           And you can look at the long-term cost to the site 18:55:5  
18 and just say, Well, look at 20 years or look at 30 years. 18:55:5  
19 If you put that remedy in place, it's forever. It's going 18:56:0  
20 to be there forever. And any costs associated with 18:56:0  
21 maintaining that site, or monitoring that site will be there 18:56:1  
22 for eternity. If you look at costs in that perspective, I 18:56:1  
23 think you can stand the extra cost on the early phase. 18:56:1

24           We had a similar site at Gallaway that was continually 18:56:1  
25 eroded. It was a stabilized site. All the waste was 18:56:2

1	solidified, stabilized, but we kept having erosion problems.	18:56:26
2	Just couldn't deal with it. It was costing us 20 to \$30,000	18:56:31
3	a year just to keep the site accessible and presentable	18:56:34
4	where it would keep the waste in the cap. It just didn't --	18:56:37
5	I didn't feel like it was worth the headache. Potential	18:56:40
6	failure.	18:56:44
7	MS. BROWN: Okay. And there's a more in-depth	18:56:48
8	analysis in the RI/FS.	18:56:50
9	The wetland alternatives, again, we had to look at no	18:57:07
10	action, for comparison purposes.	18:57:10
11	We also looked at capping. Leaving the contaminated	18:57:13
12	sediment in place, capping over it with clean fill and	18:57:17
13	creating an off-site wetlands. And it's a hard cost to come	18:57:21
14	up with, because we'd have to work with the Department of	18:57:26
15	Interior to come up with what value they place with -- for	18:57:29
16	that wetlands. So we did the best we could with costing it,	18:57:33
17	but you actually don't know until you go into purchasing the	18:57:39
18	property.	18:57:41
19	And lastly, we looked at excavating all of the	18:57:43
20	sediments, and revegetating it, and restoring it based upon	18:57:47
21	a plan that Fish and Wildlife came up with. And we looked	18:57:51
22	at two options, both of which are good. One is regrading	18:57:56
23	with clean fill and then revegetating on top of it, or	18:57:59
24	regrading it with compost.	18:58:03
25	Are most of you familiar with compost?	18:58:06

1	AUDIENCE: I know what compost is, and it was on	18:58:09
2	the back sheet of terminology, but there was no explanation	18:58:11
3	for clean fill. So my question is --	18:58:17
4	MS. BROWN: Clean fill is just dirt.	18:58:21
5	AUDIENCE: Just dirt. So compost seems the most	18:58:22
6	desirable of the two then?	18:58:27
7	MS. BROWN: Right.	18:58:29
8	AUDIENCE: Correct?	18:58:29
9	MS. BROWN: Mm-hmm.	18:58:31
10	AUDIENCE: All right.	18:58:31
11	MS. BROWN: There's different kinds of compost,	18:58:33
12	which you may be interested in as a citizen, because	18:58:35
13	different kinds of compost may have more smells than others.	18:58:38
14	We haven't specified at this point what type of	18:58:43
15	compost we want, whether we want it to be wood ash, whether	18:58:46
16	we want it to be sludge from the treatment ponds next door,	18:58:49
17	that are very organic rich and provide a very healthy	18:58:54
18	habitat for growing the grasses and different types of	18:58:58
19	vegetation.	18:59:01
20	AUDIENCE: This definition on the glossary thing	18:59:02
21	back here on the back of this sheet that came out said wood	18:59:06
22	ash compost or waste water treatment plant sludge.	18:59:11
23	Is that -- so we're, at this point, optional on	18:59:14
24	which type --	18:59:17
25	MS. BROWN: Right.	18:59:18

1	AUDIENCE: -- of compost, but it would be compost?	18:59:18
2	MS. BROWN: Right. If that's something you would	18:59:20
3	like to comment on, there is some information available on	18:59:24
4	the internet.	18:59:27
5	AUDIENCE: I have no comment other than that I'm	18:59:30
6	pleased that biosolids was better than clean fill.	18:59:32
7	MS. BROWN: Right. Yeah. And it would be very	18:59:37
8	nice if we could just use the sludge from next door. It	18:59:39
9	would be much cheaper.	18:59:43
10	AUDIENCE: The only problem (inaudible) --	18:59:46
11	MS. BROWN: You're right. You're absolutely	18:59:49
12	right.	18:59:51
13	AUDIENCE: What was the statement?	
14	MS. BROWN: He said the odor would be a problem.	18:59:53
15	MS. TUCKER: Obnoxious.	
16	MS. BROWN: And again, I did not make an overhead	19:00:01
17	of the evaluation of the wetland cleanup alternatives.	19:00:05
18	The only one, obviously, that doesn't meet protection	19:00:13
19	of the environment is the no action alternative. In both W,	19:00:17
20	alternative two and three, they both reduce -- I'm sorry,	19:00:24
21	they both reduce the mobility, but alternative two does not	19:00:29
22	reduce the toxicity, or volume, because we're leaving it on	19:00:37
23	site.	19:00:37
24	So we're looking at, alternative two and three, at	19:00:41
25	costs of both about half a million, and we choose	19:00:42

1	alternative 3b.	19:00:46
2	So we're looking at a grand total cost of about 7.7	19:00:53
3	million, and monitoring costs of about 240.	19:00:58
4	AUDIENCE: Is that over the cost to date?	19:01:04
5	MS. BROWN: Are you talking about present worth	19:01:08
6	cost?	19:01:09
7	AUDIENCE: No, the costs that have been incurred	19:01:11
8	to date?	19:01:11
9	MS. BROWN: No. No.	19:01:13
10	Oh, yes, you're right, this is in addition to what	19:01:14
11	we've already spent.	19:01:16
12	AUDIENCE: And it doesn't cover the groundwater?	19:01:18
13	MS. BROWN: Correct.	19:01:20
14	AUDIENCE: And it's not the grand total? The	19:01:20
15	ground water is still out of picture?	19:01:23
16	MS. BROWN: Right. I think, if we actually have	19:01:25
17	to do ground water cleanup, the highest cost we've seen	19:01:25
18	would be about half a million. We think that if we have to	19:01:29
19	clean up ground water there may be some more innovative type	19:01:33
20	technology that we should take a look at rather than the	19:01:36
21	traditional pump-and-treat. Ground water pump and treat.	19:01:39
22	AUDIENCE: Do you have a ballpark of what the	19:01:43
23	costs have been incurred to date?	19:01:46
24	MS. BROWN: No.	19:01:47
25	AUDIENCE: Ballpark?	19:01:49



1	MS. BROWN: I'm sorry, no. Do you guys have any	19:01:50
2	idea?	19:01:52
3	MS. TUCKER: Total costs incurred?	19:01:53
4	AUDIENCE: Costs incurred to date?	19:01:54
5	MS. TUCKER: At the site?	19:01:57
6	MS. BROWN: For the --	19:01:57
7	See, we've done the removal and the investigation of --	19:01:57
8	MS. TUCKER: I think in the region of 1.4, I	19:01:59
9	think.	19:02:01
10	AUDIENCE: What was that figure on the estimates	19:02:05
11	of ground water, if indeed you think it might need some	19:02:08
12	treatment?	19:02:13
13	MS. BROWN: Pump and treat we looked at numbers of	19:02:14
14	about half a million.	19:02:14
15	All of the information on the ground water that we have	19:02:16
16	to date is still in the RIFS. We've just chosen at this	19:02:18
17	point to break it off, and we're going to collect more data.	19:02:23
18	So the numbers are all in the RIFS.	19:02:28
19	That brings up another point I wanted to make.	19:02:30
20	We've actually, as of this week, been able to put the RI --	19:02:31
21	well, the RIFS, on the internet. So I have a web address,	19:02:37
22	most everything in volume one is available. We're working	19:02:41
23	on volume two. It also has the proposed plan on there.	19:02:44
24	Why don't I go ahead and give you guys that	19:02:51
25	internet address.	19:02:53

1	And I did not come up with this address.	19:03:03
2	We're still working on volume one. There may be	19:03:15
3	some figures or tables that still aren't available.	19:03:18
4	Okay, this is still one and this is -- I'm not	19:03:30
5	misspelling this, it is under Ross M-E-T-L.	19:03:45
6	MR. TAYLOR: Beth, you might want to make those	19:03:55
7	dots a little bigger so people won't. . .	19:03:56
8	MS. BROWN: Okay. Diane went over this so, just	19:04:16
9	to reemphasize the importance of your role, here in the next	19:04:19
10	30 days you have an opportunity either -- actually in this	19:04:24
11	meeting as well, I will respond to your verbal comments in	19:04:29
12	this document called the responsiveness summary. I'll also	19:04:33
13	respond to any written comments. We haven't talked about	19:04:36
14	this, but you can request an extension as long as it's done	19:04:40
15	in a timely manner, and that would give you an additional 30	19:04:46
16	days.	19:04:48
17	AUDIENCE: That's 30 days from the end of --	19:04:52
18	MS. BROWN: December 1 through January 18th.	19:04:56
19	Okay. After the comment period is over, I write a	19:05:01
20	formal document that's called a record of decision. It's	19:05:10
21	actually about 40 pages or so long. It will also include	19:05:13
22	the responsiveness summary, which I hope won't be bigger	19:05:16
23	than the record of decision.	19:05:20
24	Then the next step is we will notice -- PRPs is an	19:05:22
25	acronym for potentially responsible parties.	19:05:27

1	Although Ross Metals owned the property, they did	19:05:30
2	business with a lot of folks, and we noticed them back in	19:05:32
3	the spring to let them know that we have their names, that	19:05:35
4	they may be potentially responsible for the contamination at	19:05:40
5	the Ross Metals site. So they are aware that we are about	19:05:43
6	to write a record of decision.	19:05:47
7	Once that's written up we'll send an official	19:05:50
8	notice letter to them and begin an official investigation.	19:05:52
9	Those typically run from three to six months, at	19:05:58
10	which point they will either decide not do the cleanup, or	19:06:01
11	they will do the cleanup, with EPA's oversight, and we'll	19:06:07
12	sign a document, an official document, and EPA will be very	19:06:11
13	involved with the project even though the PRPs will actually	19:06:16
14	be spending their money to do the cleanup.	19:06:18
15	So -- yeah?	19:06:21
16	AUDIENCE: I may not be remembering this	19:06:22
17	correctly, but it was my understanding this was being done	19:06:26
18	last time we met, six months ago.	19:06:29
19	MS. BROWN: Right. You're absolutely right. We	19:06:34
20	had noticed them back in the spring, which is actually when	19:06:37
21	we met.	19:06:37
22	Actually, the day we met with you was the day we	19:06:39
23	met with the responsible parties. They have actually been	19:06:41
24	waiting on EPA to write this record of decision. And once	19:06:45
25	we've done that, which will be in December, that is our	19:06:47

1	legal -- that's a -- legally we can now notice them to do	19:06:47
2	the cleanup.	19:07:00
3	MS. TUCKER: This is all done through the regs and	19:07:01
4	statute. We can't notice them without having done the	19:07:04
5	remedy, selecting a remedy to clean up the site.	19:07:09
6	AUDIENCE: It was my understanding that was what	19:07:12
7	we were doing last time. And it was my understanding -- as	19:07:15
8	a matter of fact I recall well, on the subject, which would	19:07:17
9	be 60 days from now we're going to do this and we'll do	19:07:20
10	that.	19:07:22
11	MS. BROWN: Right.	19:07:22
12	AUDIENCE: Obviously that hasn't happened. This	19:07:22
13	is still going on. How do we know if it really goes on?	19:07:24
14	How can we check on --	19:07:27
15	MS. BROWN: You're absolutely right. When I met	19:07:29
16	with you in the spring I said in July we will have a record	19:07:31
17	of decision. And at that point I had a remedial	19:07:34
18	investigation feasibility study, and it went through a peer	19:07:38
19	review. And one of the ground water hydrologists found	19:07:42
20	problems with our ground water data. And so for the next	19:07:48
21	couple of months we were trying to figure out whether or not	19:07:51
22	we could go ahead and declare a pump and treat, or a cleanup	19:07:52
23	technology for ground water or not. So we actually spent	19:07:57
24	several months on that issue.	19:08:00
25	AUDIENCE: Well, if we run into something similar	19:08:03

1	to that again, is there any way we, as the city and citizens	19:08:05
2	in general, will be notified of that, or is there anything	19:08:08
3	we can do to help it along?	19:08:11
4	MS. BROWN: I've been negligent. I should have	19:08:13
5	sent you guys fact sheets when I'm not meeting my schedule	19:08:15
6	with you.	19:08:19
7	AUDIENCE: I didn't mean to jump on Beth. I'm	19:08:19
8	trying to find out how we can --	19:08:21
9	MS. BROWN: I take responsibility.	19:08:23
10	AUDIENCE: -- to make it work.	19:08:25
11	MS. BROWN: Fortunately, at this point I can say	19:08:26
12	with confidence, the record of decision will be written by	19:08:27
13	mid January. And I would like it to be written in December.	19:08:32
14	If no one requests an extension to the public comment	19:08:35
15	period, I can write it by December. And then really we'll	19:08:38
16	notice the PRPs in January. But if I have to wait until mid	19:08:44
17	January, we're not going to notice the PRP's until mid	19:08:49
18	January.	19:08:53
19	AUDIENCE: What value would it be to us if we had	19:08:54
20	an extension? Is that just simply to allow more people to	19:08:57
21	comment?	19:09:00
22	MS. BROWN: Right. If you don't feel like you've	19:09:00
23	had adequate time to review the documents, then you should	19:09:03
24	request an extension.	19:09:08
25	Now, how it will actually happen is, when you	19:09:11

1	write your comments, if you have technical comments that	19:09:12
2	impact the decision that we've made. Say someone, you know,	19:09:16
3	writes some incredible, you know, dissertation on why we	19:09:21
4	should have chosen capping verses excavation and off-site	19:09:25
5	treatment, and they have a solid technological reason for	19:09:30
6	it, we have to consider it.	19:09:35
7	AUDIENCE: So assuming -- you're going to have to	19:09:39
8	talk layman to me.	19:09:45
9	MS. BROWN: Sure.	19:09:46
10	AUDIENCE: My understanding is that the PRPs were	19:09:46
11	notified that they were responsible. What they are now, and	19:09:48
12	waiting for, is the amount of money that they are	19:09:51
13	responsible for. Is that correct?	19:09:55
14	MS. BROWN: Partially.	19:10:00
15	AUDIENCE: Because you didn't tell them -- you	19:10:00
16	simply told them you're responsible?	19:10:00
17	MS. BROWN: Right.	19:10:03
18	AUDIENCE: But you didn't tell them how much money	19:10:03
19	they were going to have to come up with?	19:10:05
20	MS. BROWN: We didn't tell them what they were	19:10:05
21	going to have to do. We just said you're potentially	19:10:07
22	responsible, and we'll notice you at a later date that	19:10:11
23	here's what we want you to do.	19:10:15
24	So this record of decision will say, EPA has	19:10:17
25	selected, you know, treatment and off-site disposal. PRP's,	19:10:22

1	you perform it.	19:10:27
2	AUDIENCE: All right. Now, my question is -- all	19:10:29
3	right. If you -- if the public comment period is over by	19:10:31
4	December the 18th, and you have a month there until the	19:10:35
5	middle of January to get this long, drawn-out, epistle	19:10:37
6	written, then you would notify these people in mid January,	19:10:43
7	and they now have three to six months? The three to six	19:10:48
8	months bothers me because, you know, I'm struggling here	19:10:53
9	with a Tag group that was fussing over why didn't we get	19:10:57
10	cancelled in July, and August, and September, and October,	19:11:02
11	and November, and you say three to six months, and I don't	19:11:05
12	understand why three to six months.	19:11:10
13	MS. TUCKER: That is statutorily required as well.	19:11:14
14	I mean, it says so in the statute, you have 120 days to	19:11:17
15	negotiate.	
16	AUDIENCE: If the negotiations period would be,	19:11:22
17	let's say I'm a PRP, I negotiate with you how much of that	19:11:25
18	millions of dollars I am willing or can spend? Is that	19:11:29
19	what we're negotiating?	19:11:34
20	MS. TUCKER: No. I think typically we're offering	19:11:37
21	you the opportunity to do the work, and that's the ultimate	19:11:38
22	statement. You do the work or we'll do the work.	19:11:44
23	MS. BROWN: But you're actually partially correct,	19:11:50
24	because they'll also be on the hook for everything EPA has	19:11:53
25	spent to date, so we have to negotiate that.	19:11:54

1	Plus there's, in total, I think about 600 of	19:11:58
2	of which, you know, they all have to coordinate, and we have	19:11:59
3	to coordinate meetings with them.	19:12:03
4	So a lot of -- unfortunately, a lot of it becomes	19:12:06
5	logistics between a large group of people. And you can	19:12:09
6	imagine with, you know, say 100 different people, they have	19:12:13
7	different interests.	19:12:16
8	AUDIENCE: Can they ask for an extension period of	19:12:17
9	more than six months?	19:12:20
10	MS. BROWN: That -- yes, they can.	19:12:23
11	MS. TUCKER: They can, but it's gotten really	19:12:25
12	difficult to grant extensions. We try to stick to the	19:12:27
13	schedule of 120 days. And we have to have a good reason.	19:12:31
14	MR. TAYLOR: They ask for it, but we don't have to	19:12:37
15	say yes.	19:12:40
16	AUDIENCE: But in my public comment sheet that I	19:12:41
17	have here, then one of my public comments could be that no	19:12:43
18	extension be given to these PRPs. Is that correct?	19:12:45
19	MS. BROWN: Sure.	19:12:50
20	AUDIENCE: I mean, I assume I can say anything I	19:12:51
21	want to, but. . .	19:12:54
22	MS. TUCKER: You're entitled to.	19:12:56
23	AUDIENCE: And I won't have a problem with that.	19:12:57
24	However, you know, if we give them an extension	19:13:00
25	of, in addition to six months more then we are looking at	19:13:02



1	beyond the year 2000, and personally I've waited 15 years,	19:13:05
2	and I'm not willing to wait another bunch.	19:13:09
3	MS. TUCKER: Well, we'll take that into	19:13:13
4	consideration then. This has been taking long, and we	19:13:17
5	really wouldn't want an extension to further delay the	19:13:17
6	project.	19:13:21
7	AUDIENCE: Because at this point, now, I see here	19:13:23
8	it says actual field work, September 1999, but what Beth	19:13:24
9	said was 2000.	19:13:29
10	MS. BROWN: Oh, Diane did.	19:13:32
11	MS. BARRETT: I was anticipating --	19:13:35
12	MS. BROWN: This is optimistic. And I came up	19:13:37
13	with four months of negotiations, and then a period of about	19:13:41
14	four months for designing the actual cleanup.	19:13:44
15	AUDIENCE: I thought the cleanup was designed.	19:13:50
16	MS. BROWN: No, the basic -- let me explain that	19:13:52
17	part.	19:13:54
18	From the remedial investigation feasibility study,	19:13:55
19	that's all the information we've collected to date.	19:13:58
20	And now, say we had chosen to cap. Well, you can't	19:14:01
21	just go out there and build a cap. We don't have plans for	19:14:05
22	exactly how they should build it. You know, how much, how	19:14:12
23	high. These are conceptual diagrams that I've put in there,	19:14:15
24	but they're not engineering specifications.	19:14:17
25	AUDIENCE: I guess my question is, why in the	19:14:22

1	world are we not just going ahead with figuring out what the	19:14:25
2	design will be, in December, January, and April? Why must	19:14:28
3	we wait for August if, in fact, you do go with these W-3b	19:14:34
4	and S-5b?	19:14:40
5	What's the reason for waiting until all of this	19:14:41
6	period of time has progressed before we go ahead with the	19:14:45
7	design process?	19:14:49
8	It seems to me you could go ahead with that at	19:14:49
9	this point if, in fact, these are the two options that area	19:14:53
10	selected, and at least move the thing along by a few months.	19:14:56
11	MS. BROWN: That is an excellent question.	19:15:01
12	Unfortunately, I don't think you're going to like the	19:15:03
13	answer.	19:15:06
14	AUDIENCE: Oh, well all right, give it to me and	19:15:07
15	let me grump about that in my comments.	19:15:09
16	MS. BROWN: EPA has a preference for not spending	19:15:12
17	the superfund money, the EPA money. We have a preference	19:15:16
18	for the PRPs to spend their money.	19:15:20
19	So we have to -- I don't know if it's statutorily	19:15:22
20	required.	19:15:24
21	MS. TUCKER: We have to do. We have to offer them	19:15:26
22	the opportunity to do the work.	19:15:28
23	MS. BROWN: I believe it's a policy, though, isn't	19:15:31
24	it?	19:15:31
25	So once you identified these group of people,	19:15:33

1	which we now have, by law we are required to give them the	19:15:37
2	opportunity. So you can't -	19:15:39
3	AUDIENCE: So what you're saying is --	
4	MS. BROWN: Until we let them --	19:15:42
5	AUDIENCE: That these PRPs could essentially do	19:15:44
6	the work, or have the work done on this site themselves, and	19:15:50
7	the EPA would merely monitor what they do?	19:15:52
8	MS. BROWN: Right.	19:15:58
9	AUDIENCE: As opposed to the EPAs selecting people	19:15:58
10	to do the work?	19:16:00
11	MS. BROWN: Right. But everything that PRP does	19:16:01
12	is subject to EPA approval. If they select a contractor, I	19:16:03
13	have to approve it. If they submit a plan, I have to	19:16:08
14	approve it.	19:16:11
15	If they're out here doing field work, there's an	19:16:11
16	EPA representative on site most of the time.	19:16:16
17	AUDIENCE: All right. So is that the real big	19:16:17
18	advantage of having a TAG coordinator there? Is that the	19:16:21
19	big advantage?	19:16:27
20	MS. BROWN: Can you ask me one more time? I'm not	19:16:28
21	sure I understood.	19:16:31
22	AUDIENCE: If the PRPs do the work?	19:16:31
23	MS. BROWN: Mm-hmm.	19:16:33
24	AUDIENCE: Let's assume that. And the CAG group	19:16:39
25	gets a TAG grant?	19:16:39

1	MS. BROWN: Okay.	19:16:41
2	AUDIENCE: Then is that essentially the biggest	19:16:42
3	advantage of having the TAG grant, and having that TAG	19:16:45
4	person on site to see that it's monitored?	19:16:47
5	MS. BROWN: It's certainly additional oversight.	19:16:53
6	AUDIENCE: But you have EPA do all of that?	19:17:00
7	MS. BROWN: Right.	19:17:03
8	AUDIENCE: And you may want to explain what the	19:17:03
9	TAG grant is. Some of the people may not know.	19:17:04
10	MS. BROWN: I'm going to let Diane answer that	19:17:07
11	one.	19:17:11
12	MS. BARNETT: A TAG grant is one that is offered	19:17:11
13	to a community, a work community, and each superfund site.	19:17:14
14	The site is on the national priorities list, so it does	19:17:17
15	apply. It is applicable for a group to request to receive a	19:17:21
16	TAG grant.	19:17:26
17	A TAG grant is \$50,000, and that's like -- it's	19:17:26
18	put into an account for the group, and then they would	19:17:31
19	select a consultant that would work with the group to go	19:17:34
20	over all of the documents, explain the documents to it, and	19:17:40
21	submit comments to EPA.	19:17:43
22	And as the work is done, then monies will be drawn	19:17:45
23	down from the account to pay the accountant -- or the	19:17:48
24	consultant, excuse me.	19:17:53
25	Also, in a TAG grant, the group would put in like,	19:17:54

1	I think it's been reduced down to about 10 to 15 percent	19:18:01
2	in-kind services, whereas like if you had an accountant that	19:18:03
3	would want to take care of the records, voluntarily, then	19:18:07
4	that would be in-kind service. So what the process, if you	19:18:10
5	are interested in that, you can submit a letter of intent to	19:18:16
6	the EPA.	19:18:18
7	AUDIENCE: I've already done that.	19:18:20
8	MS. BARNETT: Well, if Cindy has it, then she's	19:18:23
9	got that in process.	19:18:26
10	MS. BROWN: Any other questions?	19:18:28
11	Please feel free, because this is an important	19:18:29
12	meeting for you guys.	19:18:31
13	AUDIENCE: If you say that you're going to give	19:18:32
14	the PRPs the opportunity to clean this up. What's the	19:18:34
15	recourse if they don't do it?	19:18:38
16	MS. BROWN: Well, I'll let Marlene address that	19:18:40
17	one.	19:18:42
18	MS. TUCKER: If they refuse to do the work, EPA	19:18:42
19	Superfund's money will be used to do the work. Then, after	19:18:50
20	spending our funds, we will sue them for reimbursement of	19:18:57
21	all of the cost.	19:19:01
22	MS. BROWN: Three times? Not three times?	19:19:02
23	MS. TUCKER: Another option that we have -- thanks	19:19:06
24	for reminding me.	19:19:09
25	We can issue a UAL, which is a Unilateral	19:19:09

1	Administrative Order to order them to do the work. That's	19:19:17
2	another option.	19:19:17
3	MS. BROWN: We can ask them to do it. They may	19:19:17
4	agree, if we sign a certain kind of document. And if they	19:19:22
5	don't agree to it we can actually order them to do it. And	19:19:24
6	then if they still don't comply with this order, we can	19:19:26
7	actually sue them for three times the cost of our cleanup.	19:19:30
8	So in this case it would be, you know, \$22 million.	19:19:33
9	MS. TUCKER: We actually have two other options.	19:19:41
10	We can do the work ourselves, then sue them later, or we can	19:19:43
11	issue an order to force them to do it.	19:19:46
12	AUDIENCE: Up to this point it seems like we're	19:19:49
13	spending a mighty lot of time giving them the opportunity to	19:19:53
14	clean it up. I don't understand why they might want to	19:19:56
15	consider it.	19:19:56
16	MS. BROWN: In fairness to this group of	19:19:58
17	potentially responsible parties, most of them, the first	19:19:59
18	time they even heard about the site was in the spring of	19:20:02
19	this year.	19:20:05
20	AUDIENCE: I doubt that.	19:20:07
21	AUDIENCE: Has the delay until now been a result	19:20:09
22	of PRPs activities?	19:20:11
23	MS. BROWN: I still don't understand.	19:20:15
24	AUDIENCE: Has the delay from June until now been	19:20:18
25	the responsibility of the PRPs?	19:20:18

1	MS. BROWN: No. It's been EPA's responsibility.	19:20:22
2	The PRPs actually have been waiting for this date and to be	19:20:24
3	notified to do the cleanup.	19:20:28
4	MR. TAYLOR: In fact, to the PRPs credit, they	19:20:31
5	have been doing what we've asked them to do so far. That	19:20:33
6	is, organizing themselves in a group, and getting ready for	19:20:37
7	this next notice letter which they know they're going to be	19:20:39
8	getting.	19:20:44
9	You know, if we had -- if each of you were a PRP,	19:20:44
10	it would take a while for all of you to come together to	19:20:47
11	agree on how to do something. We noticed 128 of them. So	19:20:52
12	it naturally takes them a while to organize the group.	19:20:56
13	They have done that, and I think they're pretty	19:21:01
14	much ready for this letter to come. That is called the	19:21:01
15	special notice letter. It starts the negotiations for the	19:21:06
16	actual cleanup.	19:21:10
17	MS. BROWN: And some of these folks are folks that	19:21:11
18	sent their batteries to Ross Metals. They were battery	19:21:13
19	recyclers. Some of it was waste from their plants that they	19:21:18
20	sent to Ross Metals to recover the lead.	19:21:21
21	AUDIENCE: All these possibilities that they had at --	19:21:26
22	I don't know a better word other than stalling.	19:21:30
23	In other words, they could refuse to do the work,	19:21:33
24	they could be cited and all of those different things.	19:21:39
25	Those are very time-consuming things, as I understand it.	19:21:39

1	MS. BROWN: You're absolutely correct.	19:21:43
2	THE WITNESS: I'm still back on the 2000 problem.	19:21:45
3	MS. TUCKER: I just wanted to add, if we issue a	19:21:47
4	unilateral administrative order, it's effective in 30 days.	19:21:52
5	AUDIENCE: So if you tell them they must clean	19:21:54
6	up --	19:21:56
7	MS. TUCKER: That alternative won't create any	19:21:56
8	delay. In fact, it would expedite it.	19:21:58
9	MS. BROWN: Realistically, I mean, you're right.	19:22:03
10	If they enter in negotiations with us, but they don't have	19:22:03
11	any intentions of doing a cleanup, but they're just, you	19:22:08
12	know, requesting an extension. You know, we have to	19:22:10
13	evaluate their requests --	19:22:14
14	MS. TUCKER: -- in good faith?	19:22:16
15	MS. BROWN: -- requesting this extension in good	19:22:18
16	faith? Are they really interested in doing the work?	19:22:19
17	At some point during this three to four months	19:22:21
18	we're going to have to decide, and if we don't think they're	19:22:25
19	acting in good faith, or we don't think maybe they are	19:22:29
20	acting in good faith but they can't come together, we'll	19:22:31
21	issue an order and then that really starts the clock	19:22:35
22	ticking, because if they don't comply with it within 30	19:22:39
23	days, EPA can hire a contractor to begin the design.	19:22:46
24	AUDIENCE: Whatever happened to the actual owners	19:22:46
25	that made the mess?	19:22:48



1	MS. BROWN: There's rumors, but I don't know	19:22:49
2	anything for sure.	19:22:51
3	MR. TAYLOR: Well, Malcolm Ross is -- the owner,	19:22:55
4	is dead. His son --	19:22:58
5	MS. TUCKER: His son I have spoken to, and I can	19:22:59
6	contact him. I don't have an address for him, but he has	19:23:04
7	called the 1-800 number and has spoken to me about	19:23:07
8	background of the ownership.	19:23:12
9	There is David Johnson, who appears to be a major	19:23:14
10	player as far as past owners. He has not been forthright in	19:23:19
11	his involvement, so he is someone what we'll end up deposing	19:23:27
12	so we can get on record the truth and have a document that	19:23:34
13	we can use in a court situation.	19:23:38
14	AUDIENCE: (Inaudible) -- don't have any assets?	19:23:43
15	MS. TUCKER: As far as I know. You know, that's	19:23:46
16	something that, you know, I think we will eventually find	19:23:49
17	out more about.	19:23:52
18	AUDIENCE: Is David Johnson the son that you're	19:23:57
19	referring to?	19:23:57
20	MS. BROWN: No, Steve Ross. Steve Ross is the	19:23:59
21	son.	19:24:00
22	David Johnson, I think was the president of the	19:24:01
23	company for a while. When Malcolm Ross stepped out of the	19:24:05
24	picture, David Johnson and Steve ran the company.	19:24:14
25	AUDIENCE: I heard at one time, I thought maybe	19:24:17

1	somebody in the family had gone to Mexico and maybe set up	19:24:21
2	an operation.	19:24:25
3	MS. BROWN: Yeah, we've heard they set up an	19:24:26
4	operation. Actually they were operating in Mexico. And do	19:24:28
5	you have any information?	19:24:31
6	AUDIENCE: They ran a joint project with another	19:24:32
7	company in Mexico.	19:24:36
8	MS. BROWN: And they cracked open the batteries in	19:24:39
9	Mexico. Again, this is -- I've only heard this. They	19:24:42
10	cracked open the batteries in Mexico, and sent them to	19:24:44
11	Galveston where they then reclaim the lead.	19:24:48
12	AUDIENCE: In answering your question about	19:24:52
13	whether they have money, we're still looking?	19:24:55
14	MS. TUCKER: Right. It's hard to tell at this	19:25:00
15	point, but it's going to take deposing these parties and	19:25:00
16	swearing them under oath.	19:25:03
17	AUDIENCE: There's nothing to hook them on. if	19:25:04
18	there's anything to hook them on, we will, but if there's	19:25:09
19	nothing to hook, what can we do?	19:25:12
20	MS. TUCKER: In the meantime, we have 128 major	19:25:15
21	parties that we can get and try to get them to do the work.	19:25:18
22	And they also, these parties, once they sign on to	19:25:25
23	agree to do the work, they have a cause of action against	19:25:26
24	the owners if they have assets. So we'll just have to see	19:25:29
25	how it plays out.	19:25:35

1 But for now we are more interested in getting to 19:25:35  
2 the parties that we have, and know that they're doing things 19:25:38  
3 and getting them to do the work. And we'll see who else 19:25:42  
4 falls into that. 19:25:44

5 MS. BROWN: And it's a way of keeping you 19:25:45  
6 informed. We can issue a fact sheet, you know, after the 19:25:47  
7 negotiations are through to let you know who's signed on to 19:25:50  
8 do the work, whether it's fallen to the early or whether 19:25:54  
9 we -- 19:25:57

10 Yes, sir?

11 AUDIENCE: As a matter of public comment, it seems 19:25:58  
12 to me, the importance of the red tape is more important than 19:26:02  
13 the need in our community. There's something wrong with our 19:26:07  
14 system on this. 19:26:11

15 The people that have left the lead have all of the 19:26:14  
16 opportunities to get out of it, and we have all of the 19:26:17  
17 opportunities to consume more lead. 19:26:19

18 The town is not big enough to do anything about it. 19:26:26  
19 We've asked the federal government to help, and I can't tell 19:26:26  
20 if the bigger pollutant is lead or red tape. 19:26:29

21 MS. BROWN: You know, I think most of us have been 19:26:32  
22 working in the Superfund for a while, and I don't think 19:26:35  
23 you'll hear any disagreements on our part. 19:26:37

24 AUDIENCE: I don't understand it. There's no 19:26:42  
25 realistic question, in anybody's mind here, whether or not 19:26:46

1	you're going to be able to collect any money from these	19:26:50
2	people. It won't happen. But still we go through this	19:26:52
3	dance, while we live here with the lead, and pay taxes to	19:26:55
4	support the Superfund.	19:27:00
5	MS. BROWN: Yeah. You're right.	19:27:03
6	I guess the only good news I have for you is that	19:27:03
7	there are no current risks to human health at the site.	19:27:06
8	There are, however, acute risks to the bio, the	19:27:10
9	bugs and the bunnies. We're taking action based on the	19:27:14
10	future risks, if someone should come into contact with the	19:27:18
11	waste or the soils, and the acute risks and chronic risks to	19:27:21
12	the bugs and bunnies.	19:27:27
13	AUDIENCE: Because we're looking at another year	19:27:28
14	--	
15	MS. BROWN: Yes, ma'am.	19:27:32
16	AUDIENCE: -- before anything happens, and it	19:27:32
17	makes me angry that there is all this time consumed in	19:27:32
18	giving these people an opportunity to delay it, and you know	19:27:39
19	darn good and well if you were one of these PRPs, you would	19:27:42
20	delay as long as possible, whether or not -- you know, it's	19:27:46
21	a question of who we can get a hold of. And if Mr. Ross is	19:27:49
22	not get-a-holdable, then you'll go after the next fella down	19:27:54
23	the line.	19:28:00
24	And personally, it's going to come out of my	19:28:01
25	pocket one way or another, any way you look at it. You are	19:28:03

1	not controlling the Superfund, you are controlling my pocket	19:28:07
2	book, and I'm ready to spend it.	19:28:11
3	MS. BROWN: Right.	19:28:13
4	AUDIENCE: And I resent the fact that these people	19:28:15
5	seem to have more rights than I do. And I -- you know, this	19:28:17
6	is silly. I'm not joking.	19:28:20
7	Fifteen years is long enough, and you're telling me	19:28:23
8	now, that it's going to be another year and a couple of	19:28:25
9	months before the first possibility that you could actually	19:28:29
10	get your shovel in the dirt --	19:28:34
11	MS. BROWN: Right.	19:28:37
12	AUDIENCE: -- is about to happen, and that's just	19:28:37
13	flat out unacceptable.	19:28:39
14	I mean, it is. It really is.	19:28:42
15	And I understand they have 30 days, they have 60	19:29:42
16	days, they have 120 days. They have been having 30, 60, and	19:28:44
17	120 days since last June.	19:28:50
18	MS. BROWN: I understand your point. I mean, I	19:28:52
19	guess that, again, EPA did take care of what we considered	19:28:55
20	the immediate risks.	19:28:58
21	AUDIENCE: And I appreciate that. in the last	19:29:00
22	meeting when we voiced all of the comments about the	19:29:02
23	dilapidated buildings and all of that, that you did come	19:29:06
24	right behind it and take care of that, and I do appreciate	19:29:07
25	that. Because I'm close enough to the site to be able to	19:29:13

1	look at it out my back yard.	19:29:15
2	However, I know darn good and well that this little	19:29:17
3	town is expanding. We have 100 and some odd houses going up	19:29:22
4	here. We have a school here, and it's impossible for us, as	19:29:26
5	a community, to get more and more people here if they know	19:29:28
6	about it.	19:29:33
7	MS. BROWN: Well, it is an eye sore, there is no	19:29:35
8	doubt.	19:29:38
9	AUDIENCE: The eye sore is not the concern. In	19:29:38
10	other words, not all of these 100 and so houses know that we	19:29:42
11	have a superfund site less than four blocks away from their	19:29:43
12	houses. If they did, they might not be so anxious to plop	19:29:47
13	down \$114,000 for a house.	19:29:51
14	MS. BROWN: We can help you out with that. That's,	19:29:55
15	a matter of education. Because you guys are all aware of	19:29:58
16	the carrier plant in Collierville? That's a Superfund	19:30:00
17	site, and it certainly hasn't impacted Collierville's	19:30:04
18	growth.	19:30:07
19	And every time that there is a business that wants	19:30:07
20	to locate next to that site, they write a letter to EPA, or	19:30:09
21	make a phone call, and I write a letter to them. And it	19:30:13
22	hasn't impacted their growth.	19:30:17
23	So it is possible to live next to a Superfund	19:30:17
24	site, and as long as we keep everyone informed and educated,	19:30:21
25	you know, you can survive the economic, you know, growth or,	19:30:25

1	you know, you can encourage the growth.	19:30:29
2	AUDIENCE: You say that you have got it contained	19:30:32
3	in the fact it's piled on the concrete slabs?	19:30:35
4	MS. BROWN: Right.	19:30:38
5	AUDIENCE: And it's covered with tarp?	19:30:40
6	MS. BROWN: Temporarily, yes.	19:30:43
7	AUDIENCE: What about all of that that's buried	19:30:44
8	out under the ground under the back? There is no cap or no	19:30:45
9	anything. These many years leads have been leaking out.	19:30:48
10	MS. BROWN: We took samples above the slag, took	19:30:52
11	samples of the slag, and took samples below the slag. It's	19:30:56
12	not migrating very fast. We anticipate that it would take	19:31:00
13	about 70 years for the lead in that slag to impact ground	19:31:07
14	water.	19:31:09
15	AUDIENCE: Well, we've got 15 working on it.	19:31:12
16	MS. BROWN: I know. Unfortunately, folks, I don't	19:31:12
17	know that I -- I'm not going to have any answer for you	19:31:16
18	tonight that's going to make you more comfortable with the	19:31:19
19	schedule at all.	19:31:21
20	I mean, I understand.	19:31:26
21	AUDIENCE: How come your late is September '99	19:31:34
22	date for the actual field work? Is that pretty firm?	19:31:34
23	MS. BROWN: No. That's optimistic.	19:31:34
24	AUDIENCE: Wow.	19:31:40
25	MS. BROWN: I think if you talk to a lot of	19:31:45

1	communities that have lived near a Superfund site, probably	19:31:47
2	the biggest complaint we hear is about how long it takes us.	19:31:50
3	It is the most common one I hear.	19:31:54
4	AUDIENCE: The good point is that things are in	19:31:59
5	motion. Something is going to happen. There is a set	19:32:04
6	schedule, maximum is three, four, five years down the road.	19:32:05
7	It's going to be cleaned up.	19:32:11
8	MS. BROWN: Yes, it is.	19:32:12
9	AUDIENCE: Beth, is it all going to be off site?	19:32:15
10	MS. BROWN: That's EPA's preference.	19:32:19
11	AUDIENCE: Who makes the decision?	19:32:22
12	MS. BROWN: I do, with my management's approval.	19:32:22
13	I'm sure I'm going to have to respond to comments,	19:32:25
14	you know, for those that aren't in favor of treating it on	19:32:27
15	site and shipping it off, but we chose this on very firm	19:32:31
16	ground. We can back it up.	19:32:35
17	AUDIENCE: You're going to dig it out of the	19:32:40
18	ground and haul it off?	19:32:41
19	MS. BROWN: As far as I know. I can't think of	19:32:44
20	any argument that anyone would have that would make EPA	19:32:46
21	change their mind. And if, you know, the long shot, that	19:32:51
22	were to happen or information were to be, you know, to come	19:32:55
23	available to EPA, we'd have to come to you again.	19:32:59
24	AUDIENCE: When you get through with it we'll be	19:32:03
25	able to use it for anything we want to? Like a park or	19:32:05



1	anything?	19:33:08
2	MS. BROWN: That's really going to depend on	19:33:11
3	whether EPA does the clean up, or whether the PRPs do the	19:33:12
4	clean up, and who actually will have control of the	19:33:15
5	property.	19:33:18
6	My understanding is there isn't a whole lot of	19:33:18
7	interest in that property ever being industrial. I mean,	19:33:21
8	it's in a wetlands, it's in a flood plain.	19:33:25
9	AUDIENCE: The history of the property is -- it	19:33:28
10	used to be in a park.	19:33:32
11	MS. BROWN: Right.	19:33:33
12	AUDIENCE: The city is interested in taking up a	19:33:33
13	study to see if it can be made into a park again.	19:33:36
14	MS. BROWN: EPA would love that, and we're, if we	19:33:38
15	do it, I think, you know, it will happen. If the PRPs do	19:33:41
16	it, we'll work with the community and encourage the PRPs to	19:33:45
17	do that with the property.	19:33:50
18	AUDIENCE: Do you mean if the PRPs do it then they	19:33:51
19	will not necessarily have to do it to your specifications?	19:33:55
20	You mean --	19:33:58
21	MS. BROWN: As far as what the future use of the	19:34:03
22	property is?	19:34:03
23	MR. TAYLOR: He's talking about clean up levels.	19:34:03
24	AUDIENCT: From the answer that you gave me, that	19:34:09
25	if you do the job it would be done right. If the PRPs do	19:34:09

1	the job, it might be done right or it may not be done right.	19:34:05
2	MS. BROWN: No, it will be done right, but the	19:34:17
3	difference is who owns the property after the clean up.	19:34:17
4	That was your question, right?	19:34:17
5	AUDIENCE: Well, no. I wanted to know about the	19:34:22
6	clean up.	19:34:22
7	MS. BROWN: Clean up is going to be done right	19:34:22
8	whether we do it or the PRPs do it.	19:34:26
9	AUDIENCE: I want to know, according to you, other	19:34:26
10	than I would like to see it done correctly, and whomever	19:34:29
11	owns it, the property could do with it whatever they want	19:34:31
12	to.	19:34:34
13	MS. BROWN: After it's cleaned up --	19:34:36
14	AUDIENCE: After it's cleaned up.	19:34:38
15	MS. BROWN: Go ahead.	19:34:38
16	AUDIENCE: First of all, since I've been so ugly	19:34:40
17	to you, I want to tell you that these two options are the	19:34:42
18	ones I chose. I read this eleventy-seven times. Let's see	19:34:45
19	her type that.	19:34:50
20	MS. BROWN: How many typos did you find?	19:34:52
21	AUDIENCE: Well, being an English teacher, I did	19:34:54
22	pretty well and didn't look for that.	19:34:59
23	But these options were the two that I chose before	19:35:00
24	I read the back page to see which ones you had chosen. So	19:35:04
25	these were, without question, the two better options.	19:35:09

1	My surprise, when we talked before the meeting began,	19:35:12
2	was that if the PRPs clean this property up, then	19:35:16
3	essentially it does provide them with ownership.	19:35:20
4	MS. BROWN: Well, actually -- not ownership.	19:35:25
5	They're going to have to take control of the property	19:35:28
6	temporarily to do the cleanup. But then it's a matter of	19:35:31
7	who owes the back taxes, and all of that. And I think that	19:35:35
8	the county is going to have to put it up for sale.	19:35:41
9	AUDIENCE: Okay, the city and the CAG group, the	19:35:44
10	CAG group has already gone on record, but I want to make	19:35:47
11	sure that I make a statement tonight, that the CAG group	19:35:49
12	choice was that the property be turned over, purchased by,	19:35:53
13	or whatever legal requirements were necessary, by the City	19:35:57
14	of Rossville, to be used as community property, the entire	19:36:01
15	tract of 7.5 acres. And that it be used -- isn't that	19:36:05
16	correct, 7.5?	19:36:11
17	MS. BROWN: You're talking about just the facility	19:36:14
18	record and the backfill?	19:36:16
19	AUDIENCE: Well, that plus the wetlands.	19:36:17
20	MS. BROWN: The landfill and the facility is about	19:36:17
21	eight, and then the wetlands is about another eight.	19:36:23
22	MS. BROWN: Right. Of about a 242-acre parcel.	19:36:23
23	AUDIENCE: Correct. That the entire tract of land	19:36:26
24	be turned over to the City of Rossville to do with for	19:36:29
25	community property; parks, recreational areas, community	19:36:32

1	area.	19:36:38
2	And that, you know, that was our request in the	19:36:39
3	very back -- or the very beginning of this.	19:36:41
4	MS. BROWN: And I think that's a great idea. And	19:36:46
5	maybe it's a matter of getting the county mayor -- is it	19:36:49
6	still Jim Voss? -- involved, because I'm not sure how your	19:36:50
7	local laws work with the --	19:36:54
8	AUDIENCE: When I talked to him he assured me if	19:36:58
9	the property was available, and the cost of it was back	19:37:00
10	taxes, that the city of Rossville would have no difficulty	19:37:03
11	in acquiring the property.	19:37:08
12	MS. BROWN: Would they have to bid against	19:37:10
13	other --	19:37:12
14	AUDIENCE: According to Mr. Voss, at that time,	19:37:12
15	no.	19:37:14
16	MS. BROWN: We need to look into that.	19:37:16
17	AUDIENCE: Because of the back taxes, and some	19:37:17
18	legal ramifications that were involved, that the city could	19:37:20
19	basically assume it.	19:37:25
20	MS. BROWN: Hmm. Let's get it cleaned up first.	19:37:27
21	AUDIENCE: I do care who owns it, very much.	19:37:32
22	MS. BROWN: For those of you that arrived late,	19:37:36
23	we're not trying to heat -- make you guys hot, but we turned	19:37:39
24	the heat off so we could actually hear each other.	19:37:41
25	AUDIENCE: Who owns that property now?	19:37:44

1	MS. BROWN: It's - - nobody.	19:37:46
2	AUDIENCE: Well, somebody.	19:37:47
3	MS. BROWN: Back taxes are owed.	19:37:49
4	AUDIENCE: The company did?	19:37:50
5	MS. TUCKER: The company still owns it as far as	19:37:52
6	we know.	19:37:54
7	AUDIENCE: I thought you said it was	19:37:56
8	administratively dissolved.	19:37:58
9	MS. TUCKER: The corporation. It doesn't mean	19:38:00
10	that they don't own the property.	19:38:02
11	MS. BROWN: I mean, I've been told, you know, off	19:38:06
12	the record, that it's actually Greyhound that owns it.	19:38:09
13	AUDIENCE: You mean the bus?	19:38:12
14	MS. BROWN: They're a financial service that was	19:38:14
15	interested in taking over the property.	19:38:16
16	MS. TUCKER: I think they loaned - -	19:38:21
17	MS. BROWN: In redeveloping it.	19:38:23
18	MS. TUCKER: They loaned the money to David	19:38:25
19	Johnson to purchase it from Malcolm, so somehow they have a	19:36:27
20	financial investment in the property.	19:38:31
21	MS. BROWN: All I know is the county called me	19:38:33
22	about two years ago wanting to foreclose on it for back	19:38:36
23	taxes, and decided not to because it was a Superfund site,	19:38:40
24	and they didn't know that this -- if they bought the	19:38:45
25	property today they might get a letter saying you have to	19:38:50

1	clean it up.	19:38:50
2	AUDIENCE: So Greyhound actually, on the record	19:38:52
3	book, owns it at this point?	19:38:55
4	MS. BROWN: I can't say for sure.	19:38:57
5	MR. TAYLOR: I think, on the record book, if you	19:38:59
6	went up to the courthouse, I think you would see Ross	19:39:00
7	Metals, Incorporated is the official owner.	19:39:03
8	But, again, that company has been administratively	19:39:07
9	dissolved, and the taxes have not been paid, and I think	19:39:12
10	that's what you're referring to.	19:39:13
11	AUDIENCE: Is it possible that Greyhound have	19:39:16
12	mortgage interests in the property?	19:39:19
13	MS. TUCKER: I believe that may be the case, yeah.	19:39:22
14	MS. BROWN: Greyhound actually looked into	19:39:26
15	cleaning it up themselves a number of years ago when we were	19:39:29
16	doing the removal, and the deal fell through. EPA	19:39:32
17	negotiated with them.	19:39:36
18	Well, I tell you what, we'll hang around here if	19:39:42
19	anybody else would have any questions they have for us.	19:39:45
20	So, you know, as far as the official meeting,	19:39:48
21	thank you very much for coming.	19:39:50
22	MS. BARNETT: One quick question.	19:39:53
23	MS. BROWN: Sure.	
24	MS. BARNETT: Did everybody sign in?	19:39:56
25	And the reason I ask this is that if you did not	19:39:58

1	get mail, and if you want to receive information about the	19:39:59
2	site in the future, be sure to sign this so I can make sure	19:40:03
3	you're on the mail list to receive it.	19:40:06
4	So I just want to make sure you sign this.	19:40:09
5	That's all.	19:40:12
6	MS. BROWN: Thanks again	19:40:13
7	(Whereupon, the public meeting	
8	was concluded at 7:40 p.m.)	
9	*    *    *	
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		
22		
23		
24		
25		

1 STATE OF TENNESSEE )

)ss

2 COUNTY OF SHELBY )

3 THIS IS TO CERTIFY that the foregoing  
4 proceeding was taken before me, DEBRA A. DIBBLE, a Certified  
5 Shorthand Reporter and Notary Public in and for the State of  
6 Tennessee, residing at Oakland, Tennessee.

7 That the proceeding was reported by me in  
8 Stenotype, and thereafter caused by me to be transcribed  
9 into typewriting, and that a full, true and correct  
10 transcription of said proceeding so taken and transcribed is  
11 set forth in the foregoing pages numbered from 2 to 50  
12 inclusive.

13 I further certify that I am not of kin or  
14 otherwise associated with any of the parties to said cause  
15 of action, and that I am not interested in the event  
16 thereof.

17  
18   
Debra A. Dibble, C.S.R., R.P.R.

